




Paleontological Resource Inventory and Monitoring

EASTERN RIVERS AND MOUNTAINS NETWORK



Paleontological Resource Inventory and Monitoring

EASTERN RIVERS AND MOUNTAINS NETWORK

Alison L. Koch
Paleontological Technician
Santa Monica Mountains National Recreation Area

Vincent L. Santucci
Chief Ranger
George Washington Memorial Parkway

June 2004

National Park Service, TIC #D-265

On the Cover:

A *Neuropteris pocahontas* specimen from the Pocahontas Formation of West Virginia. *Neuropteris pocahontas* is abundant in this formation and is represented by fronds, pinnules, male reproductive bodies, and seeds. This plant species is used as a marker fossil to help paleontologists delineate the bottom section of the Pennsylvanian system. New River Gorge National River deposits contain these fossil remains. Additional fossil plant material has been recorded from multiple parks within the Eastern Rivers and Mountains Network.

TABLE OF CONTENTS

INTRODUCTION	I
METHODS AND INVENTORY STRATEGIES.....	2
ALLEGHENY PORTAGE RAILROAD NATIONAL HISTORIC SITE	6
BLUESTONE NATIONAL SCENIC RIVER	16
DELAWARE WATER GAP NATIONAL RECREATION AREA.....	19
FORT NECESSITY NATIONAL BATTLEFIELD	31
FRIENDSHIP HILL NATIONAL HISTORIC SITE	35
GAULEY RIVER NATIONAL RECREATION AREA	38
JOHNSTOWN FLOOD NATIONAL MEMORIAL	41
NEW RIVER GORGE NATIONAL RIVER.....	44
UPPER DELAWARE SCENIC AND RECREATIONAL RIVER	48
ACKNOWLEDGMENTS.....	53
APPENDIX A: GEOLOGIC TIME SCALE	54

INTRODUCTION

Paleontological resources are the remains of past life preserved in a geologic context. These fossils are non-renewable resources that possess scientific and educational values.

Establishment of baseline paleontological resource data is essential for the appropriate management of fossils found within National Park Service areas. Although over 160 National Park Service areas have been identified with paleontological resources, only a small percentage of these parks have adequate baseline paleontological resource data.

In conjunction with the National Park Service Geologic Resources Division and Inventory and Monitoring Networks, comprehensive paleontological resource inventories have been initiated in dozens of parks service-wide. This report represents paleontological resource inventory and monitoring data compiled for the parks within the Eastern Rivers and Mountains Network.

The Eastern Rivers and Mountains Network is comprised of 9 National Park Service areas: Allegheny Portage Railroad National Historic Site, Bluestone National Scenic River, Delaware Water Gap National Recreation Area, Fort Necessity National Battlefield, Friendship Hill National Historic Site, Gauley River National Recreation Area, Johnstown Flood National Memorial, New River Gorge National River, and Upper Delaware Scenic and Recreational River. These parks are located in New Jersey, New York, Pennsylvania, and West Virginia. The Eastern Rivers and Mountains Network preserves unique river and significant mountain forest resources.

Fossiliferous geologic units range from the Middle and Upper Ordovician (around 450 million years ago) to the Quaternary. Significant fossils of invertebrates, vertebrates, plants, and traces have been found in many of the parks, and the potential to discover new localities and specimens is great.

In particular, existing documentation on paleontological resources within Delaware Water Gap National Recreation Area and New River Gorge National River illustrate the significance and richness of fossils preserved by the Eastern Rivers and Mountains Network.

The variety, abundance, and continuing great potential for fossils in the Eastern Rivers and Mountains Network warrant the inclusion of these parks into the growing list of paleontological resource gems within the National Park Service.

ALISON L. KOCH
VINCENT L. SANTUCCI

METHODS AND INVENTORY STRATEGIES

In order to better document fossil occurrences and to provide baseline paleontological resource data in National Park Service areas, the NPS Geologic Resources Division (GRD) and the NPS Inventory and Monitoring Program (I&M) have established three paleontological resource inventory strategies. These strategies include: comprehensive park-specific paleontological resource inventories, service-wide thematic paleontological resource inventories, and Inventory & Monitoring Network based baseline paleontological resource inventories, each established with their own goals and objectives. An article outlining basic paleontological resource monitoring strategies and potential threats to fossil resources is presented by Santucci and Koch (2003).

Comprehensive park inventories are designed to identify all known paleontological resources within a single park unit. Comprehensive park inventories involve the assembly of a team of specialists from within the NPS and from educational institutions and cooperators. These specialists work together with the park to identify and address all aspects of the paleontological resources within the targeted park, including resource management, museum curation, law enforcement, and interpretation. The goals and objectives of a park-specific paleontological resource inventory are detailed by Santucci (2000). An important component of many comprehensive paleontological inventories is to provide paleontology-specific training for park staff. Such park-specific comprehensive paleontological resource inventories have been completed at Yellowstone NP (first park to complete inventory), Arches NP, Bighorn Canyon NRA, Death Valley NP, Grand Teton NP, Santa Monica NRA, Walnut Canyon NM, and Zion NP.

Service-wide thematic paleontological resource inventories are designed to compile data regarding specific types of paleontological resources which occur in parks throughout the NPS. The first thematic paleontological resource inventory accomplished was an inventory of fossil vertebrate tracks from NPS areas (Santucci et al. 1998). Through this thematic inventory, a total of nineteen NPS units were identified as preserving fossil vertebrate tracks. Subsequent discoveries have increased the number of parks identified with fossil vertebrate tracks to twenty-five. Another example of a thematic paleontological resource inventory is the inventory of paleontological resources associated with NPS caves (Santucci et al. 2001). Fossils occur in two contexts relative to caves. First, fossils can be preserved in the marine limestones in which caves develop. Second, the remains of Ice Age animals and plants that lived, died or were transported into caves after death, are common types of cave fossils. The NPS Cave Paleontological Resource study initially identified thirty-five parks with cave fossils.

The third paleontological resource inventory strategy is the Inventory & Monitoring Network-based inventory strategy. Network-based paleontological resource inventories are designed to compile baseline paleontological resource data for each of the parks assigned to a particular network. Network-based inventories have been completed for one-third of the 32 I&M Networks including: the Eastern Rivers and Mountains, Greater Yellowstone, Mediterranean Coast, Mojave Desert, National Capital Region, Northeast Coastal and Barrier, Northern Colorado Plateau, Rocky Mountain, Southern Plains, and Southwestern Alaska networks. A similar paleontological inventory underway for the Upper Columbia Basin Network is scheduled for completion during FY2005.

The Network-based paleontological inventories are funded directly by the individual networks. Funds are used to provide stipends or salary for contractors, interns, or paleontological technicians who perform data mining activities. A brief summary outlining the basic techniques used to put together an I&M Network-based inventory is presented below.

The most valuable component of any paleontological resource inventory is an intensive literature search. Various databases contain citations for geology or paleontology themed publications. GeoRef, established by the American Geological Institute, is the primary database for geology references and contains millions of references from the mid 1700s through today. GeoRef, available in both online or CD-ROM versions, is accessible at many major university libraries. The NPS NatureBib (which supercedes PaleoBib) is an internet based database for scientific citations presented as bibliographic references. NatureBib is a work in progress.

and does not yet contain a comprehensive paleontology bibliography. The USGS Library in Reston, Virginia is a premier repository for geologic publications, and houses most of the publications obtained for the network-based paleontological resource inventories. Additionally, museum libraries such as the Smithsonian Institution's National Museum of Natural History, and university libraries provide access to a wide range of geological and paleontological publications. Individual state geological surveys are also excellent sources of information and geologists familiar with local geology and paleontology.

The literature search also includes gray (unpublished) literature, searches of individual park files, museum archives, local newspapers, etc. These are often excellent sources of anecdotal information about park resources. In addition to literature searches, interviews with park staff, university faculty, geologists from the USGS and state surveys, and even local amateur geologists or paleontologists can yield information regarding park paleontological resources. These interviews frequently result in capturing data that may otherwise be undocumented and potentially lost or unrecognized.

As part of the bibliographic searches, a search for geologic maps associated with each park is undertaken. Tim Connors, a geologist with the NPS Geologic Resources Division, maintains a database of geological map coverage for many parks in the NPS. In addition, the USGS National Geologic Map Database (NGMDB; see citation below in References section) lists maps for a given geographic area or place name. The NGMDB also provides information on where to obtain maps. Geologic maps show the type of rocks and the associated geological formations present within a park area. These maps, alone, will often indicate the potential for paleontological resources to occur within a park. Fossils, with only rare exceptions, are found in sedimentary rocks such as sandstones, shales, and limestones. Fossils, with few exceptions, are not found within igneous rocks (volcanic, or of molten origin) or metamorphic rocks (mechanically and chemically altered) due to the extreme heat and/or pressure associated with the origin and history of these rocks types. The nomenclature for geologic formations can be confusing. The NGMDB also includes a searchable lexicon of valid geologic formation names. This lexicon provides a basic summary for each formation and summarizes current and past usage of the various formation names found in the literature. It also provides an annotated bibliography for each formation. The lexicon is very useful in cleaning up nomenclatural confusion.

The information from all these various sources for each park is then compiled and summarized in a written report and developed into individual datasets. The reports undergo peer review by professional geologists, paleontologists, and staff from each park, for accuracy before being submitted to the network. This report is designed to consolidate baseline paleontological resource data for each park to support management operations and decision-making. Therefore, the reports are written in NPS language and in addition to the scientific information, the reports address issues of resource management, protection, and interpretation.

The paleontological resource inventory reports synthesize information regarding the scope and significance of fossils documented from each park. Fossils are assessed and organized based upon taxonomy, stratigraphy, and paleoecology. Taxonomically, paleontological resources can be divided into four groups: paleobotany (fossil plants), invertebrates (animals without backbones), vertebrates (animals with backbones), and trace fossils (evidence of biological activity such as track, trace, burrow, etc.). Stratigraphically, fossils typically have a finite span and occurrence in geologic time (a geologic time scale is included in Appendix A). The period between the first occurrence and final occurrence of a fossil species is referred to as the stratigraphic range zone. Thus specific groups of fossils may be identified directly with a particular stratigraphic unit or stratigraphic range. Likewise, rock units often represent specific ancient sedimentary depositional environments. Paleoecologically, fossil groups may occur primarily, or in some instances only, in specific environmental conditions (temperature, aquatic, terrestrial, etc.). Thus many fossils may be useful as indicators of past environmental conditions. The reports are organized stratigraphically presenting the geologic and paleontologic information chronologically from oldest to youngest. Important fossils documented from localities outside a park are often reported in the park inventory, as this data may indicate the potential for fossils in similar stratigraphic units exposed in park boundaries.

Given the tremendous diversity of past life, the existence of life for over a billion years, and the range of environments that life has adapted, there is a broad spectrum of research interests in paleontology. It is not surprising that most of what is to be learned about the history of life remains to be discovered. Through

research, over 170 NPS areas have been identified as containing paleontological resources. However, the paleontological research for a particular park may vary widely from an incidental fossil discovery to over a century of intensive paleontological investigations. The inventory reports include information on the history of paleontological research, descriptions of current cooperative projects, identification of any museum or universities serving as repositories for park fossils, and a comprehensive list of publications related to paleontological research associated with the park. Organizationally, the reports include any and all bibliographies that may be associated to a park's paleontological resources. However, bibliographic data are subdivided in the report into those cited in the narrative (References Cited) and other associated bibliographies (Additional References). The cooperative projects section highlights projects, if any, that the park has funded or supported relating to paleontological resources. Formal datasets are established for known associated paleontological collections, research, or activities.

Our knowledge of the fossil record is only as good as our previous field season. The potential for new paleontological discoveries is proportionally related to our understanding as managers and stewards of this non-renewable evidence of life from the past. We believe that the baseline information provided in these reports and the resulting increased understanding of paleontological resources will inevitably result in paving the way for future fossil discoveries in NPS areas.

ADDITIONAL REFERENCES AND WEBSITES OF INTEREST

- Kenworthy, J. and V. L. Santucci, 2003. Paleontological Resource Inventory and Monitoring, Southwestern Alaska Network. National Park Service TIC# D- 93. 27 pp.
- Kenworthy, J. and V.L. Santucci, 2003. Paleontological Resource Inventory and Monitoring, Northeast Coastal and Barrier Network. National Park Service TIC# D- 340. 28 pp.
- Koch, A.L. and V.L. Santucci, 2002. Paleontological Resource Inventory and Monitoring, Northern Colorado Plateau Network. National Park Service TIC# D- 206. 44 pp.
- Koch, A.L. and V.L. Santucci, 2003. Paleontological Resource Inventory and Monitoring, Southern Plains Network. National Park Service TIC# D- 107. 34 pp.
- Koch, A.L. and V.L. Santucci, 2003. Paleontological Resource Inventory and Monitoring, Greater Yellowstone Network. National Park Service TIC# D- 1025. 20 pp.
- Koch, A.L. and V.L. Santucci, 2003. Paleontological Resource Inventory and Monitoring, Mediterranean Coast Network. National Park Service TIC# D- 177.
- Koch, A.L. and V.L. Santucci, 2004. Paleontological Resource Inventory and Monitoring, Eastern Rivers and Mountains Network. National Park Service TIC# D- 265. 50 pp.
- Koch, A.L., J. Kenworthy, and V.L. Santucci. in preparation. Paleontological Resource Inventory and Monitoring, Rocky Mountain Network. National Park Service TIC# D- 436.
- Santucci, V.L. 1998. The Yellowstone Paleontological Survey. Yellowstone Center for Resources, Yellowstone NP, WY. YCR- NR- 98- 1. 54 pp. (<http://www2.nature.nps.gov/geology/paleontology/surveys/yell.pdf>)
- Santucci, V.L., 2000. What constitutes a comprehensive National Park Service paleo survey? Online information: (http://www2.nature.nps.gov/geology/paleontology/surveys/survey_outline.htm)
- Santucci, V.L., A.P. Hunt, and M.G. Lockley. 1998. Fossil vertebrate tracks in National Park Service areas. *Dakoterra* 5:107- 114.

Santucci, V.L., J. Kenworthy, and R. Kerbo, 2001. An inventory of paleontological resources associated with National Park Service Caves. NPS Geological Resources Division, Denver. Technical Report NPS/NRGRD/GRDTR- 01/02. (TIC# D- 2231). 50 pp. (<http://www2.nature.nps.gov/geology/paleontology/pub/cavepaleo.pdf>)

Santucci, V.L. and A.L. Koch, 2003. Paleontological resource monitoring strategies for the National Park Service. *Park Science* 22(1): 22- 25.

Santucci, V.L., A.L. Koch, and J. Kenworthy, 2004. Paleontological Resource Inventory and Monitoring, Mojave Desert Network. National Park Service TIC# D- 305. 50 pp .

New Jersey Geological Survey: <http://www.state.nj.us/dep/njgs/>

New York Geological Survey (unofficial page): <http://www.albany.net/~go/survey/>

NPS Eastern Rivers and Mountains Network: <http://www1.nature.nps.gov/im/units/ermn/>

NPS Geologic Resources Division: <http://www2.nature.nps.gov/geology/>

NPS Paleontology Program: <http://www2.nature.nps.gov/geology/paleontology/>

NPS Park Paleontology Newsletter: <http://www2.nature.nps.gov/geology/paleontology/news/newsletter.htm>

Pennsylvania Geological Survey: <http://www.dcnr.state.pa.us/topogeo/>

Smithsonian National Museum of Natural History Dept. of Paleobiology: <http://www.nmnh.si.edu/paleo/>

Topozone (access to all U.S. topographic maps): <http://www.topozone.com>

U.S. Geological Survey: <http://www.usgs.gov>

U.S. Geological Survey National Geologic Map Database (NGMDB): <http://ngmdb.usgs.gov/>

U.S. Geological Survey Library Catalog: <http://igsr.glibo3.er.usgs.gov:8080/#focus>

West Virginia Geological and Economic Survey: <http://www.wvgs.wvnet.edu/>

ALLEGHENY PORTAGE RAILROAD NATIONAL HISTORIC SITE

Allegheny Portage Railroad National Historic Site (ALPO) was originally established in 1964. This site preserves traces of the first railroad crossing of the Allegheny Mountains. The inclined plane railroad was built between 1831 and 1834, and subsequently abandoned no later than 1857.

BASELINE PALEONTOLOGICAL RESOURCE INVENTORIES:

Fossils have been recorded from the Pottsville Formation and/or Allegheny Formation within the boundaries of ALPO. Park managers know the exact locations of these recorded fossils. Other formations found within the park are known to contain paleontological resources, although no reported discoveries have occurred within ALPO.

ALPO preserves two separate administrative areas in Blair County, Pennsylvania. The eastern area contains the visitor center, Lemon House, Engine House 6 Exhibit Building, and Skew Arch Bridge. The geologic formations preserved in this eastern area (range from Devonian to Pennsylvanian) and include: Brallier, Harrell, Scherr, Foreknobs, Catskill, Rockwell, Burgoon, Mauch Chunk, Pottsville, Allegheny, and Glenshaw formations. The western area preserves the Staple Bend Tunnel, which contains the Allegheny, Pottsville, and Mauch Chunk formations.

The Harrell and Brallier formations are Upper Devonian in age and are composed of siltstone, shale, and black shale. The lower half of the Harrell Formation contains styliolinids, lingulid brachiopods, and conodonts (Harper, 1999). Palynomorph assemblages of both of these formations from Pennsylvania were studied by Norton and Allen (1970). Many of the forms represent a distinct flora similar to those described in Europe. Rossbach (2000) investigated migration and endemism of fossil invertebrates, including conularids from the Brallier Formation. Rossbach concluded close evolutionary ties with European fauna.

The Upper Devonian Scherr Formation is primarily composed of siltstone, sandstone, shale, and mudstone. Berg and others (1980) report that the Scherr Formation contains marine fossils.

The Foreknobs Formation is found stratigraphically above the Scherr Formation and is also Upper Devonian in age. This formation is composed of sandstone, siltstone, shale, and conglomerate. Dennison (1970) reports scattered marine fossils in the shale beds of the Foreknobs Formation. Rutledge and others (2002) identified two distinct fossil assemblages in the Foreknobs Formation that are characterized by the presence or absence of brachiopods and pelecypods. Berg and others (1980) also report some marine fossils from this formation.

The Devonian Catskill Formation consists of sandstone, siltstone, shale, conglomerate, and mudstone. This formation contains both marine and nonmarine fossils (Berg et al., 1980; Harper, 1999). The Academy of Natural Sciences in Philadelphia is currently working on what they refer to as the Catskill Project. This research led to the discovery of plants, plant spores, invertebrates, and all major classes of vertebrates. Additionally, they have discovered and described two new taxa of limbed (tetrapod) vertebrates from the Catskill Formation; *Densignathus rowei* and *Hynerpeton bassetti*. These significant tetrapod discoveries from Clinton County, Pennsylvania have extended the temporal range of North American tetrapods and shed light on morphological evolution (Daeschler et al., 1994). Additionally, the State Museum of Pennsylvania houses many fish specimens and the University of California Museum at Berkeley houses 1 plant and 4 vertebrate specimens from the Catskill Formation. Specific paleobotanical research was conducted by Scheckler and Banks (1971) and Brauer (1980). Scheckler and Banks investigated a new genus of progymnosperms and suggest some evolutionary trends among the Aneurophytales. Brauer discusses interesting features of a *Barinophyton citrulliforme* and suggests various interpretations. Fossil pollen analyses were conducted from Catskill Formation material in order to help date rocks and differentiate sedimentary units (Traverse, 1974; Wilson and Traverse, 1975). Lastly, Walter (2001) researched evidence for the earliest known wildfire from a charcoal deposit in the Catskill Formation.

The Rockwell Formation was deposited during the Devonian- Mississippian transition. This geologic unit is composed of argillaceous (composed of clay minerals) sandstone, shale, carbonaceous (rich in carbon) shale, conglomerate, and diamictite (massive, structureless rock). Palynological studies of fossil spores from the Rockwell Formation were conducted by Wood (1987). Brownish- gray to grayish- black shale beds are known to contain marine fossils; in particular, the unit called the Riddlesburg Shale. (Berg, 1999; Reger, 1927). Dennison and others (1986) report brackish- water fauna and green- gray *Skolithos* burrowed (worm tube burrowed) sandstones from the Rockwell Formation.

The Mississippian Burgoon Sandstone is primarily a non- marine, fluvial sandstone (T. Kammer, written communication, 2004). This formation also consists of conglomerate, shale, and coal. Trace fossils have been discovered in this formation in central- western Pennsylvania and plant fossils are noted from northern, western, and central Pennsylvania (Berg et al., 1980).

The Mauch Chunk Formation is also Mississippian in age and is composed of shale, siltstone, sandstone, conglomerate, and limestone. Brezinski (1984) describes a bioturbated (churned sediments by an organism) mudstone that was deposited in a shoal environment in a shallow lagoon from the Mauch Chunk Formation. Fossil plants in the Mauch Chunk Formation have been studied, with a particular emphasis on the morphology of *Adiantites antiquus* (Jennings, 1985) and on new interpretations of *Lepidocarpon* (Miklaussen, 1989). Hoque (1968) investigated fish fragments and worm burrows and Edmunds and others (1979) researched invertebrate body fossils from the Mauch Chunk Formation. Two trilobite species from the genus *Paladin* were discovered in the Mauch Chunk Formation (Brezinski, 1988). These fossils were primarily found in nearshore shaly environments within bivalve- dominated communities. Most notably, the Thompson Quarry located near Chalk Hill, Pennsylvania, has produced abundant and diverse marine fossils from the Mauch Chunk Formation. Researchers have identified corals, conulariids, bryozoans, brachiopods, gastropods, pelecypods, cephalopods, trilobites, blastoids, and crinoids (Simonsen, 1988). Additionally, the same research team discovered microfossils of foraminifera, conodonts, and ostracodes. Rollins and Brezinski (1988) also studied the Thompson Quarry site and reported on bryozoans, brachiopods, bivalves, trilobites, and crinoids.

The Pottsville Formation is Pennsylvanian in age and has a wide compositional range including; sandstone, conglomerate, shale, siltstone, claystone, limestone, and coal. Edmunds and others (1999) report that the shales periodically contain marine and brackish- water fauna in western Pennsylvania. Also, marine invertebrates and plant fossils from the Pottsville Formation were researched by Edmunds (1992), which aided in defining age determinations for the formation. In northeastern Pennsylvania, preservation of fossil plants from the Pottsville Formation were studied by Grandstaff (1977) and fossil insects were researched by Carpenter (1960, 1967). In western Pennsylvania, macrofauna investigations were conducted by Williams (1960, 1980) and microfauna explorations of fusulinids and conodonts have been recorded (Smyth, 1974; Merrill, 1970- 1971).

The Allegheny Formation overlies the Pottsville Formation and is also Pennsylvanian in age. The Allegheny Formation consists of sandstone, shale, limestone, clay, and coal. Microfossils including conodonts and two species of the fusulinid *Beedeina* were studied from the Allegheny Formation (Rice et al., 1994). Twenty- five species of gastropods were studied by Sturgeon (1945) from the Allegheny Formation of eastern Ohio. In western Pennsylvania, macrofauna investigations were conducted by Williams (1960, 1980) and microfauna explorations of fusulinids and conodonts have been recorded (Smyth, 1974; Merrill, 1970- 1971). Smith (1968) studied macrofauna of the Allegheny Formation. Specific research was conducted on the Allegheny Formation cephalopods (Sturgeon, 1964; Murphy, 1966) and vertebrates (Lund, 1975).

The youngest unit in ALPO is the Glenshaw Formation, which is composed of shale, sandstone, limestone, and coal. The Glenshaw Formation is known to be very fossiliferous in many areas of Pennsylvania, Ohio, and West Virginia, most notably in the Brush Creek, Pine Creek, and Ames marine zones. In southwestern Pennsylvania, Roen and others (1968) report that the limestone and calcareous shale contain marine fossils. Biogenic mounds containing abundant vertical burrows, presumably from malacostracan crustaceans, are known from southwestern Pennsylvania and eastern Ohio exposures of the Glenshaw Formation (Carothers

and Norton, 1975). Crinoid and trilobite fossils from the Glenshaw Formation were used for investigations of mineralogy and fluorescence of skeletal carbonates by Durika and others (1987). Foraminifera have also been studied from the Glenshaw Formation. Palaeotextulariid foraminifera and endothyroid foraminifera were reported on from the Appalachian basin (Moir et al., 1988; Hoare and Sturgeon, 1998). From a quarry in eastern Ohio, Rollins and others (1979) report a variety of fauna from the Glenshaw Formation including, fusulinids, bryozoans, brachiopods, crinoids, and fish fragments. Lepold (2003) reports corals, brachiopods, bivalves, and crinoids from the Glenshaw Formation in eastern Ohio. Conodonts were examined at Ebensburg, Pennsylvania to identify the marine unit as part of the Ames (Merrill, 1988). Additional fauna at the site include foraminifera, brachiopods, bivalves, gastropods, cephalopods, echinoderms, and shark teeth (Brady et al., 1985). An additional locality in Beaver County of the Ames marine zone produced over 30 species of invertebrates, vertebrates, and trace fossils (Harper, 1986). Conodonts from the Ames and Brush Creek marine zones were used for testing the validity of using uranium, thorium, and lead contents for dating (Kovach and Zartman, 1981).

Although these specimens were collected outside the boundaries of ALPO, historically important fossil discoveries were made along the Allegheny Portage Railroad from a number of formations and localities. Harper (2002) outlines the significance and historical events of fossil collecting and geologic mapping in the 1800s. In the 1830s Edward Miller investigated the geology and paleontology of the Portage Railroad route and made several collections along the way. Miller (1835) discovered plant fossils in what is probably the upper Rockwell Formation or Burgoon Sandstone. Harlan (1835) was the first to describe the plant specimens that Miller collected from the Portage Railroad (*Pecopteris obsolete*, *Pecopteris milleri*, and *Neuropteris* sp.). Conrad (1835) published a subsequent paper on research based from Miller's specimens. New species from this work included the marine gastropods *Stylifer primogenia*, *Turbo tabulatus*, *Turbo insectus*, the brachiopod *Productus confragosus* and the bivalve *Pecten armigerus*. Although Conrad's type specimens are lost, these species are known to occur in the Allegheny and Conemaugh groups, including the Glenshaw Formation in particular (Harper, 2002). Conrad's 1835 report is historically significant because it is the first published report of invertebrate fossils from the Coal Measures (Pennsylvanian) of North America (Harper, 2002). Additionally, Leidy (1856) describes a new shark tooth, *Petalodus allegheniensis*, from specimens found near the Bens Creek Station within the Glenshaw Formation.

REFERENCES CITED:

- Berg, T. M., 1999. Chapter 8; Devonian- Mississippian Transition in Schultz, C. H., (ed.), The Geology of Pennsylvania: Pennsylvania Geological Survey and Pittsburgh Geological Survey: 129- 138.
- Berg, T. M., A. R. Geyer, W. E. Edmunds, and other compilers, 1980. Geologic map of Pennsylvania: Pennsylvania Geologic Survey, 4th ser., Map 1.
- Brady, K., J. A. Harper, and J. Inners, 1985. Ames or not Ames? an ambiguous Conemaugh marine zone at Ebensburg: Pennsylvania Geology, 16(6): 7- 12.
- Brauer, D. F., 1980. *Barinophyton citrulliforme* (Barinophytales incertae sedis, Barinophytaceae) from the Upper Devonian of Pennsylvania: American Journal of Botany, 67(8): 1186- 1206.
- Brezinski, D. K., 1984. Micro-platform carbonate development and facies in Mauch Chunk Formation (Chesterian) of southwestern Pennsylvania: American Association of Petroleum Geologists Bulletin, 68(12): 1- 1916.
- Brezinski, D. K., 1988. Appalachian Carboniferous trilobites: Journal of Paleontology, 62(6): 934- 945.
- Carothers, M. C. and C. W. Norton, 1975. Biogenic mounds in the lower Conemaugh (Missourian, Pennsylvanian) of the Appalachian Basin: Geological Society of America, Northeastern Section, 7(1): 37- 38.
- Carpenter, C. W., 1960. Studies on North American Carboniferous insects the *Protodonta*: Psyche, 67: 98- 110.
- Carpenter, C. W., 1967. Studies of North American insects the genera *Metropator*, *Eubleptus*, *Haploptera*, and *Hadentomum*: Psyche, 72: 175- 190.
- Conrad, C. A., 1835. Description of five new species of fossil shells [coal measures, Pennsylvania]: Geological Society of Pennsylvania, 1: 267- 270.

- Daeschler, E. B., N. H. Shubin, K. S. Thomason, and W. W. Amaral, 1994. A Devonian tetrapod from North America: *Science*, 265: 639- 642.
- Dennison, J. M., 1970. Stratigraphic divisions of Upper Devonian Greenland Gap Group (Chemung Formation) along Allegheny Front in West Virginia, Maryland, and Highland County, Virginia: *Southeastern Geology*, 12(1): 53- 82.
- Dennison, J. M., J. D. Beuthin, and K. O. Hasson, 1986. Latest Devonian- earliest Carboniferous marine transgressions central and southern Appalachians, USA, *in* Bless, M.J. and M. Streel, (eds.), Late Devonian events around the Old Red Continent; field conference in Aachen (FRG), with excursions in the Ardenne (Belgium), the Rheinisches Schiefergebirge (FRG) and in Moravia (USSR): *Annales de la Societe Geologique de Belgique*, 109(1):123- 129.
- Durika, N. J., J. F. Taylor, and K. R. Cercone, 1987. Mineralogy and fluorescence of skeletal carbonates, Brush Creek marine interval, Virgilian Glenshaw Formation, southwestern Pennsylvania: *Geological Society of America Abstracts with Programs*, 19(7): 649.
- Edmunds, W. E., 1992. Early Pennsylvanian (Early Morrowan) marine transgression in south- central Pennsylvania: *Northeastern Geology*, 14(4): 225- 231.
- Edmunds, W. E., T. M. Berg, W. D. Sevon, R. C. Piotrowski, L. Heyman, and L. V. Rickard, 1979. Pennsylvania and New York: U. S. Geological Survey Professional Paper: B1- B33.
- Edmunds, W. E., V. W. Skema, and N. K. Flint, 1999. Chapter 10; Pennsylvanian *in* Schultz, C. H., (ed.), *The Geology of Pennsylvania: Pennsylvania Geological Survey and Pittsburgh Geological Survey*: 149- 169.
- Grandstaff, D. E., 1977. A multistage model of preservation in some fossil plants: *Geological Society of America Abstracts with Programs, Northeastern Section*: 304.
- Harlan, R., 1835. Notice of fossil vegetable remains from the bituminous Coal Measures of Pennsylvania, being a portion of the illustrative specimens accompanying Mr. Miller s essay or geological section of the Alleghany Mountains, near Port Railway: *Transactions of the Geological Society of Pennsylvania*, 1: 256- 259.
- Harper, J. A., 1986. Beaver County fossil locality: *Pennsylvania Geology*, 17(1): 13- 16.
- Harper, J. A., 1999. Chapter 7; Devonian *in* Schultz, C. H., (ed.), *The Geology of Pennsylvania: Pennsylvania Geological Survey and Pittsburgh Geological Survey*: 109- 127.
- Harper, J. A., 2002. The history and geology of the Allegheny Portage Railroad, Blair and Cambria Counties, Pennsylvania: *Guidebook for the Pittsburgh Geological Society Field Trip, May 11, 2002*: 1- 104.
- Hoare, R. D. and M. T. Sturgeon, 1998. Pennsylvanian endothroid Foraminifera from the Appalachian Basin: *Journal of Paleontology*, 72(3): 405- 418.
- Hoque, M., 1968. Sedimentologic and paleocurrent study of the Mauch Chunk sandstones (Mississippian), south- central and western Pennsylvania: *American Association of Petroleum Geologists Bulletin*, 52(2): 246- 263.
- Jennings, J. R., 1985. Fossil plants from the Mauch Chunk Formation of Pennsylvania; morphology of *Adiantites*: *Journal of Paleontology*, 59(5): 1146- 1157.
- Kovach, J. and R. E. Zartman, 1981. U- Th- Pb dating of conodonts: *Geological Society of America Abstracts with Programs, North- Central Section*, 13(6): 285.
- Leidy, J., 1856. Descriptions of some remains of fishes from the Carboniferous and Devonian formations of the United States: *Academy of Natural Sciences in Philadelphia Journal*, 2nd series, 3: 159- 165.
- Lepold, J. G., 2003. Lithologic and faunal patterns related to shoreline position in the Ames Member of the Glenshaw Formation (Virgilian, Upper Pennsylvanian): *Geological Society of America Abstracts with Programs*.
- Lund, R., 1975. Vertebrate- fossil zonation and correlation of the Dunkard Basin *in* Barlow, J. A. and S. Burkhammer, (eds.), *The Age of the Dunkard, Proceedings of the First I. C. White Memorial Symposium: West Virginia Geological and Economic Survey*: 171- 182.
- Merrill, G. K., 1970- 1971. The central Appalachians *in* Sweet, W. C. and S. M. Bergström, (eds.), *Symposium on conodonts biostratigraphy: Geological Society of America Memoir*, 127: 407- 414.
- Merrill, G. K., 1988. Conodonts confirm that the Conemaugh marine unit at Ebensburg is Ames: *Pennsylvania Geology*, 19(2): 8- 13.
- Miklaussen, A. J., 1989. New interpretations of *Lepidocarpon* based on impression organs of Upper Mississippian plant fossils from southcentral Pennsylvania: *American Journal of Botany*, 76(6, Suppl.): 171.

- Miller, E., 1835. Geological description of a portion of the Allegheny Mountain, illustrated by drawings and specimens: Transactions of the Geological Society of Pennsylvania, 1: 251- 255.
- Moir, M. M., R. D. Hoare, and M. T. Sturgeon, 1988. Pennsylvanian Palaeotextulariid Foraminifera from the Appalachian Basin: Journal of Paleontology, 62(5): 724- 730.
- Murphy, J. L., 1966. The Pennsylvanian nautiloid *Kionoceras ungeri* (Sturgeon and Miller): Journal of Paleontology, 40: 1388- 1390.
- Norton, N. J. and D. Allen, 1970. Analyses of palynomorph assemblages from mid- continent and eastern Devonian formations: Geological Society of America Abstracts with Programs, 2(6): 399- 400.
- Rager, D. B., 1927. Pocono stratigraphy in the Broadtop basin of Pennsylvania: Geological Society of America Bulletin, 38: 397- 410.
- Rice, C. L., R. M. Kosanke, and T. W. Henry, 1994. Revision of nomenclature and correlations of some Middle Pennsylvanian units in the northwestern part of the Appalachian basin, Kentucky, Ohio, and West Virginia in Rice, C. L., (ed.), Elements of Pennsylvanian stratigraphy, central Appalachian basin: Geological Society of America Special Paper, 294: 7- 26.
- Roen, J. B., B. H. Kent, and S. P. Schweinfurth, 1968. Geologic map of the Monongahela quadrangle, southwestern Pennsylvania: U. S. Geological Survey Geologic Quadrangle Map, GQ- 743, scale 1:24,000.
- Rollins, H. B. and D. K. Brezinski, 1988. Reinterpretation of crinoid- platyceratid interaction: Lethaia, 21(3): 207- 217.
- Rollins, H. B., M. Carothers, and J. Donahue, 1979. Transgression, regression and fossil community succession: Lethaia, 12(2): 89- 104.
- Roszbach, T. J., 2000. Limited migration and endemism of fossil invertebrates from the Brallier and Foreknobs formations (Upper Devonian) of Virginia and West Virginia: Geological Society of America Abstracts with Programs, Southeastern Section, 32(2): 70.
- Rutledge, F. A., III, H. E. McCoy, K. L. Avary, D. L. Matchen, and R. R. McDowell, 2002. Preliminary investigation of new exposures of Upper Devonian strata, Elkins, West Virginia: Geological Society of America Abstracts with Programs, North- Central Section and Southeastern Section Joint Meetings.
- Scheckler, S. E. and H. P. Banks, 1971. *Proteokalon* a new genus of Progymnosperms from the Devonian of New York State and its bearing of phylogenetic trends in the Group: American Journal of Botany, 58(9): 874- 884.
- Simonsen, A. H., 1988. Chesterian fossil site in the Mauch Chunk Formation, Chalk Hill, Pennsylvania: Northeastern Geology, 10(1): 50- 56.
- Smith, R. D., 1968. Paleontology of the Columbia shale near Corsica, Pennsylvania: Master s Thesis, Pennsylvania State University.
- Smyth, P., 1974. Fusulinids in the Appalachian basin: Journal of Paleontology, 48: 856- 858.
- Sturgeon, M. T., 1945. Some fossil gastropods from the Allegheny Formation of eastern Ohio: Geological Society of America Bulletin, 56(12, Part 2): 1- 1203.
- Sturgeon, M. T., 1964. New descriptions of hitherto inadequately known Pennsylvanian gastropods: Journal of Paleontology, 38: 740- 748.
- Traverse, A., 1974. Plant Microfossils Help Date Rocks of Questionable Age: Earth and Mineral Sciences, 43(4): 28- 29.
- Walter, L. C., III, 2001. Evidence of Earliest Known Wildfires: Palaios, 16(2): 171- 174.
- Williams, E. G., 1960. Marine and fresh water fossiliferous beds in the Pottsville and Allegheny groups of western Pennsylvania: Journal of Paleontology, 34: 908- 922.
- Williams, E. G., 1980. Marine and fresh water fossiliferous beds in the Pottsville and Allegheny groups of western Pennsylvania in Fern, J. C., J. C. Horne, G. A. Weisenfluh, and J. R. Staub, (eds.), Carboniferous depositional environments in the Appalachian region: University of South Carolina, Geological Department: 35- 49.
- Wilson, B. R. and A. Traverse, 1975. Further information on the palynological stratigraphy of Devonian- Carboniferous rocks of central Pennsylvania: Geoscience and Man, 11: 160.
- Wood, W. D., Jr., 1987. Spores from the Late Devonian- Early Mississippian Rockwell Formation on northwestern Maryland: Geological Society of America Abstracts with Programs, Northeastern Section, 19(1): 66.

ADDITIONAL REFERENCES:

- Ahlberg, P. E., Z. Johanson, and E. B. Daeschler, 2001. The Late Devonian lungfish *Soederberghia* (Sarcopterygii, Dipnoi) from Australia and North America, and its biogeographical implications: *Journal of Vertebrate Paleontology*, 21: 1- 12.
- Allen, J. R. L. and P. F. Friend, 1968. Deposition of the Catskill facies, Appalachian region; with some notes on some other Old Red Sandstone basins, Late Paleozoic and Mesozoic continental sedimentation, northeastern North America: *Geological Society of America Symposium*: 21- 74.
- Al Qayim, B. A., 1983. Facies analysis and depositional environment of the Ames Marine Member (Virgilian) of the Conemaugh Group (Pennsylvanian) in the Appalachian Basin: PhD Thesis, University of Pittsburgh, Pennsylvania: 1- 344.
- Banks, H. P., J. D. Grierson, and P. M. Bonamo, 1985. The flora of the Catskill clastic wedge in Woodrow, D. L. and W. D. Secon, (eds.), *The Catskill Delta: Geological Society of America Special Publication*, 20: 125- 141.
- Berg, T. M., 1972. Clam burrows in the upper Devonian or; Quo Vadis Archanodon? : *Pennsylvania Geology*, 3(6): 6- 8.
- Berg, T. M., 1977. Bivalve burrow structures in the Bellvale Sandstone, New Jersey and New York: *New Jersey Academy of Science Bulletin*, 22: 1- 5.
- Berg, T. M., 1999. Devonian- Mississippian transition in Schultz, C. H., (ed.), *The geology of Pennsylvania: Geological Survey of Pennsylvania Special Publication*: 128- 137.
- Berg, T. M., C. H. Dodge, and L. J. Lentz, 1986. Upper Devonian and Mississippian stratigraphy of the Broad Top region: *Guidebook for the Annual Field Conference of Pennsylvania Geologists*, 51: 81- 91.
- Bjerstedt, T. W., 1987. Latest Devonian- Earliest Mississippian nearshore trace- fossil assemblages from West Virginia, Pennsylvania, and Maryland: *Journal of Paleontology*, 61: 865- 889.
- Brezinski, D. K., 1983. Paleoecology of the Upper Mississippian trilobite *Paladin chesterensis* in southwestern Pennsylvania: *Compass of Sigma Gamma Epsilon*, 1915- 84, 61(1): 2- 7.
- Brezinski, D. K., 1999. Mississippian in Schultz, C. H., (ed.), *The geology of Pennsylvania: Geological Survey of Pennsylvania, Special Publication*: 138- 147.
- Brezinski, D. K. and H. B. Rollins, 1983. Genetic lithostratigraphy of the Mauch Chunk Formation of the Central Appalachians: *Program of the Appalachian Basin Industrial Associates Fall 1983 Meeting*, 5: 57- 76.
- Busanus, J. W. and R. D. Hoare, 1991. Bivalves (Mollusca) from the Mauch Chunk Group (Mississippian, Chesterian) of northern West Virginia and southwestern Pennsylvania: *Journal of Paleontology*, 65(3): 465- 480.
- Busch, R. M., 1984. Stratigraphic analysis of Pennsylvanian rocks using a hierarchy of transgressive-regressive units: PhD Thesis, University of Pittsburgh, Pennsylvania: 1- 449.
- Cercone, K. R. and J. F. Taylor, 1989a. Stop GeeBee fossil locality at Geistown; faunal and lithologic characteristics of the Pennsylvanian (Missourian) Brush Creek marine interval, Glenshaw Formation, Conemaugh Group: *Guidebook for the Annual Field Conference of Pennsylvania Geologists*, 54: 222- 224.
- Cercone, K. R. and J. F. Taylor, 1989b. Stop Shelocta fossil locality; taphonomy and geochemistry of the Brush Creek marine interval, Glenshaw Formation, Conemaugh Group: *Guidebook for the Annual Field Conference of Pennsylvania Geologists*, 54: 178- 182.
- Clausen, J. E., 1981. Paleoecology and stratigraphy of Upper Devonian (Frasnian- Famennian) clastic facies units in Randolph County, West Virginia: Master's Thesis, Rutgers, The State University, New Brunswick, New Jersey: 1- 115.
- Cotter, E., 1993. Overview of geology of central Pennsylvania: *University of Tennessee, Knoxville, Tennessee, Studies in Geology (Knoxville)*, 22: 1- 22.
- Cressler, W. L., III, 2001. Evidence of earliest known wildfires: *Palaos*, 16(2): 171- 174.
- Cuomo, M. C. and D. C. Rhoads, 1987. Biogenic sedimentary fabrics associated with pioneering polychaete assemblages; modern and ancient: *Journal of Sedimentary Petrology*, 57: 537- 543.
- Daeschler, E. B., 2000. An early actinopterygian fish from the Catskill Formation (Late Devonian, Famennian) in Pennsylvania, U. S. A.: *Proceedings of the Academy of Natural Sciences of Philadelphia*, 150: 181- 192.

- Dennison, J. M., 1993. Fragment shape used for detailed stratigraphic mapping in Devonian shales of Central Appalachians: American Association of Petroleum Geologists and Economic Paleontologists and Mineralogists Annual Meeting Abstracts: 91.
- Dennison, J. M., J. K. Filer, and T. J. Rossbach, 1995. Episodic redbeds in Devonian marine strata of Central Appalachian Catskill Delta: Geological Society of America Abstracts with Programs, 27(6): 326.
- Diemer, J. A. and P. A. Phillips, 1987. Depositional environments of the upper Catskill Formation, south-central Pennsylvania; implications for Catskill Basin development: Geological Society of America Abstracts with Programs, 19(7): 642.
- Driese, S. G., C. I. Mora, and J. M. Elick, 1997. Morphology and taphonomy of root and stump casts of the earliest trees (Middle to Late Devonian), Pennsylvania and New Yorks, USA: *Palaos*, 12: 524- 537.
- Droser, M. L., 1984. Characteristics of Paleozoic marginal marine trace fossil assemblages: Geological Society of America Abstracts with Programs, 16(6): 494.
- Easterday, C. R. and L. E. Babcock, 2000. Fauna and taphonomy of a Mazon Creek-type deposit (Pennsylvanian) from eastern Ohio: Geological Society of America Abstracts with Programs, North-Central Section, 32(4): 12.
- Edmunds, W. E., 1981. The Mississippian-Pennsylvanian boundary in Pennsylvania: Geological Society of America Abstracts with Programs, 13(7): 445.
- Edmunds, W. E. and J. R. Eggleston, 1993. Stop 1; Unconformable Mississippian-Pennsylvanian contact (Mauch Chunk, Pottsville, and Allegheny formations): Guidebook for the Annual Field Conference of Pennsylvania Geologists, 58: 81- 88.
- Elliot, D. K., 1981. An edrioasteroid from the Foreknobs Formation (Upper Devonian) of West Virginia: Proceedings of the West Virginia Academy of Science, 53(2,3, and 4): 69- 73.
- Elliot, D. K. and A. C. Taber, 1981. *Cooperidiscus alleganius* (Clarke) (Edrioasteroidea) from the Upper Devonian of West Virginia: Proceedings of the West Virginia Academy of Science, 53(1): 1- 14.
- Elliot, D. K., E. B. Daeschler, H. G. Johnson, R. Cloutier, and R. K. Carr, 2000. Middle and Late Devonian vertebrates of the western Old Red Sandstone Continent: CFS Courier Forschungsinstitut Senckenberg, 223: 291- 308.
- Flores, R. M., 1965. Genetic types of some sandstones in the Allegheny Formation of Ohio: Bulletin of the American Association of Petroleum Geologists, 49(3): 1- 340.
- Gill, S. and K. Yemane, 1999. Illitization in a Paleozoic, peat-forming environment as evidence for biogenic potassium accumulation: Earth and Planetary Science Letters, 170: 327- 334.
- Godfrey, S. J., 1988. Isolated tetrapod remains from the Carboniferous of West Virginia: *Kirtlandia*, 43: 27- 36.
- Grabau, A. W., 1906. Notes on the character and origin of the Pottsville Formation of the Appalachian region: *Science*, 24: 691.
- Grabau, A. W., 1908. Notes on the character and origin of the Pottsville Formation of the Appalachian region: *Annals of the New York Academy of Sciences*, 18: 1- 294.
- Grierson, J. D., 1983. The Catskill flora; where we are with the evidences: Geological Society of America Abstracts with Programs, Northeastern Section, 15(3): 133.
- Harper, J. A., 1992. Life in a fossil shellfish community; an excellent outdoor classroom and a collector's paradise: *Pennsylvania Geology*, 23(2): 9- 14.
- Harper, J. A. and R. W. Morris, 1978. A new encrinasterid ophiuroid from the Conemaugh Group (Pennsylvanian) of western Pennsylvania, and revision of the Encrinasteridae: *Journal of Paleontology*, 52(1): 155- 163.
- Harper, J. A. and R. G. Piotrowski, 1979. Stratigraphic correlation of surface and subsurface Middle and Upper Devonian, southwestern Pennsylvania: Guidebook for the Annual Field Conference of Pennsylvania Geologists, 44: 18- 37.
- Hoare, R. D., 1996. Upper Pennsylvanian *Endothranella* (Foraminifera) from the Appalachian Basin: *The Compass*, 73(1): 18- 21.
- Hoque, M., 1965. Stratigraphy, petrology, and paleogeography of the Mauch Chunk Formation in south-central and western Pennsylvania: PhD Thesis, University of Pittsburgh, Pittsburgh, Pennsylvania: 1- 467.
- House, M. R. and W. T. Kirchgasser, 1993. Devonian goniatite biostratigraphy and timing of facies movements in the Frasnian of eastern North America: Geological Society of London Special Publication, 70: 267- 292.

- Kochanov, W., 1997. Stop 5; The Elmhurst Boulevard pit and the stumps ; fossil plants and the remains of a Mississippian paleoforest in the Mauch Chunk Formation: Guidebook for the Annual Field Conference of Pennsylvania Geologists, 62: 111- 119.
- Kocher, A. C., 1999. Structural geology and fossil strain analysis in Augusta, Hanging Rock, Levels, Rio, and Springfield 7.5 quadrangles, Hampshire County, West Virginia: Master s Thesis, University of Toledo, Toledo, Ohio: 1- 77.
- Kosanke, R. M. and C. B. Cecil, 1996. Late Pennsylvanian climate changes and palynomorph extinctions: Review of Palaeobotany and Palynology, 90(1- 2): 113- 140.
- Kressel, M. D., J. R. Shalis, and A. E. Wegweiser, 1993. Stop 5; Fossil fish, ichnofossils, and sedimentary structures of the Schaffer Run- Wills Creek confluence section, southeastern Somerset County, Pennsylvania: Guidebook for the Annual Field Conference of Pennsylvania Geologists, 58: 102- 116.
- Laughrey, C. D., J. A. Harper, U. Kaktins, D. K. Brezinski, and A. Iranpanah, 1989. Stop Conemaugh Gorge through Laurel Hill; Mississippian and Devonian stratigraphy, depositional systems, and structures *in* Harper, J. A., (ed.), Geology in the Laurel Highlands of southwestern Pennsylvania: Guidebook for the Annual Field Conference of Pennsylvania Geologists, 54: 182- 211.
- Liebfreid, D. J., 1992. An investigation of the fossils of the Allegheny Formation from selected sites in the Johnstown Pennsylvania area: Master s Thesis, Indiana University of Pennsylvania, Indiana, Pennsylvania: 1- 57.
- Lyke, W. L., 1986. The stratigraphy, paleogeography, depositional environment, faunal communities, and general petrology of the Minnehaha Springs Member of the Scherr Formation, an Upper Devonian turbidite sequence, central Appalachians: Southeastern Geology, 26: 173- 192.
- Maloney, M. M., R. D. Hoare, and M. T. Sturgeon, 1988. Pennsylvanian palaeotexullariid foraminifera from the Appalachian Basin: Journal of Paleontology, 62(5): 724- 730.
- Marks, W. J., R. I. Marks, and A. M. Pompa, 1998. Problematic tracks in the Casselman Formation of Cambria County: Pennsylvania Geology, 29(2- 3): 2- 6.
- Marple, M. F., 1950. Ostracodes from the Pottsville Formation in Ohio: PhD Thesis, Ohio State University, Columbus, Ohio.
- Marple, M. F., 1955. Small Foraminifera of the Pottsville Formation in Ohio: The Ohio Journal of Science, 55(2): 81- 89.
- McGhee, G. R., Jr., 1976. Late Devonian benthic marine communities of the central Appalachian Allegheny Front: Lethaia, 9: 111- 136.
- McGhee, G. R., Jr. and R. G. Sutton, 1981. Late Devonian marine ecology and zoogeography of the central Appalachians and New York: Lethaia, 14: 27- 43.
- McGhee, G. R., Jr. and R. G. Sutton, 1983. Evolution of late Frasnian (Late Devonian) marine environments in New York and the central Appalachians: Alcheringa, 7: 9- 21.
- Meckel, L. D., Jr., 1964. Pottsville conglomerates in Pennsylvania; paleocurrents and origin: Bulletin of the American Association of Petroleum Geologists, 48(4): 1- 538.
- Miklaussen, A. J., 1988. Is this nonstrobilar plant a *Lepidocarpon*? The interpretation of the impression organs of an Upper Mississippian plant fossil from Pennsylvania: American Journal of Botany, 75(6, Part 2): 1- 113.
- Moore, J. I., 1923. A review of the present knowledge of fossil scorpions with the description of a new species from the Pottsville Formation of Clay County, Indiana: Proceedings of the Indiana Academy of Science: 125- 134.
- Mora, C. I., S. G. Driese, and L. A. Colarusso, 1996. Middle to late Paleozoic atmospheric CO (sub 2) levels from soil carbonate and organic matter: Science, 271(5252): 1105- 1107.
- Morningstar, H., 1921. The fauna of the Pottsville Formation of Ohio below the lower Mercer Limestone: PhD Thesis, Bryn Mawr College: 1- 92.
- Morrison, J. O. and U. Brand, 1985. Pyritization; an example of high- Mg calcite alteration: Geological Association of Canada, Mineralogical Association of Canada, and Canadian Geophysical Union Joint Annual Meeting Program with Abstracts, 10: A40.
- Myer, G. H., J. de Santis, B. E. Grandstaff, and D. E. Grandstaff, 1977. A multistage model of preservation in some fossil plants: Geological Society of America Abstracts with Programs, 9(3): 304.
- Risek, R. M., 1995. Paleoenvironmental reconstruction of the Harlem and Ames coal beds (Glenshaw Formation- Upper Pennsylvanian); implication for the Missourian- Virgilian stage boundary: PhD Thesis, University of Pittsburgh, Pennsylvania: 1- 321.

- Risek, R. M., 1996. Paleoenvironmental reconstruction of the Harlem and Ames coal beds (Glenshaw Formation- Upper Pennsylvanian); implications for the Missourian- Virgilian stage boundary: Geological Society of America Abstracts with Programs, Northeastern Section, 28(3): 94.
- Robb, A. J. and C. A. Cuffey, 1989. Fossil fish locality in the Catskill Formation (Upper Devonian) near Port Matilda, Centre County, Pennsylvania: Pennsylvania Geology, 20(6): 2- 8.
- Rollins, H. B. and J. Donahue, 1971. Faunal community asymmetry in the Conemaugh (upper Pennsylvanian) of the Appalachian basin; theoretical implications: Geological Society of America Abstracts with Programs, 3(7): 687.
- Roszbach, T. J., 1993. Pattern of extinction in a deltaic system near the Upper Devonian Frasnian- Famennian boundary in the Central Appalachians: Geological Society of America Abstracts with Programs, 25(6): 332.
- Schopf, J. M., E. G. Ehlers, D. V. Stiles, and J. D. Birlle, 1965. Fossil iron bacteria preserved in pyrite: Proceedings of the American Philosophical Society, 109(5): 288- 308.
- Shultz, C., ed., 1999. The Geology of Pennsylvania: Pennsylvania Geological Survey and Pittsburgh Geological Survey: 1- 888.
- Slingerland, R. and J. P. Loule, 1988. Wind/wave and tidal sedimentation along the Upper Devonian Catskill shoreline in Pennsylvania, USA: West Virginia Geological and Economic Survey, Circular: 1- 61.
- Sohn, I. G., 1938. Ostracoda from the Mauch Chunk (Mississippian of West Virginia): Master s Thesis, Columbia University, Teachers College, New York, New York.
- Steel, M. and A. Traverse, 1978. Spores from the Devonian/Mississippian transition near the Horseshoe Curve section, Altoona, Pennsylvania, U.S.A.: Review of Palaeobotany and Palynology, 26(4): 21- 39.
- Strimple, H. L., 1969. Fossil crinoid studies pt.3, Pennsylvanian crinoids from Ohio and Oklahoma: Kansas University Paleontological Contributions, Paper 42: 11- 17.
- Sturgeon, M. T., 1933. The stratigraphy and paleontology of the middle portion of the Allegheny Formation of the Lisbon Ohio Quadrangle: Master s Thesis, Ohio State University, Columbus, Ohio.
- Swales, W. E., 1951. Mauch Chunk (Pennsylvanian) series in northern West Virginia and Southwest Pennsylvania: Master s Thesis, West Virginia University, Morgantown, West Virginia.
- Swartz, C. K. and H. Bassler, 1919. Typical section of the Allegheny Formation: Geological Society of America Bulletin, 30(1): 153- 154.
- Thoms, R. E. and T. M. Berg, 1974. Comparison of the burrowing habits of a Devonian pelecypod with those of a recent analogue: Geological Society of America Abstracts with Programs, Cordilleran Section, 6(3): 267.
- Thoms, R. E. and T. M. Berg, 1980. Interpretation of fossil fluvial bivalve burrows in Catskill Formation, based on analog with *Margaritifera margaritifera* (L.): American Association of Petroleum Geologists Bulletin, 64(5): 1- 792.
- Thoms, R. E. and T. M. Berg, 1985. Interpretation of bivalve trace fossils in fluvial beds of the basal Catskill Formation (Late Devonian), Eastern U.S.A.: Society of Economic Paleontologists and Mineralogists, Special Publication, 35: 13- 20.
- Thomson, K. S., 1972. New evidence on the evolution of the paired fins of *Rhipidistia* and the origin of the tetrapod limb, with description of a new genus of Osteolepidae: Postilla, 157: 1- 7.
- Thomson, K. S., 1976. The faunal relationships of rhipidistian fishes (Crossopterygii) from the Catskill (upper Devonian) of Pennsylvania: Journal of Paleontology, 50: 1203- 1208.
- Traverse, A., 1974. Plant Microfossils Help Date Rocks of Questionable Age: Earth and Mineral Science, 43(4): 28- 29.
- Van Tassell, J., 1986. Upper Devonian Catskill delta margin cyclic deposition; Virginia, West Virginia, and Pennsylvania: Geological Society of America Abstracts with Programs, Northeastern Section, 18(1): 73.
- Walker, R. G. and J. C. Harms, 1975. Shorelines of weak tidal activity; upper Devonian Catskill Formation, central Pennsylvania in Ginsburg, R. N., (ed.), Tidal deposits; a casebook of recent examples and fossil counterparts: Springer- Verlag, New York, New York: 103- 108.
- Warg, J. B. and A. Traverse, 1973. A palynological study of shales and coals of a Devonian- Mississippian transition zone, central Pennsylvania: Geoscience and Man, 7: 39- 46.
- Warne, A. G., 1986. Stratigraphic analysis of the Upper Devonian Greenland Gap Group and Lockhaven Formation near the Allegheny Front of central Pennsylvania: Master s Thesis, Rutgers, The State University, New Brunswick, New Jersey: 1- 219.

- Warne, A. G. and G. R. McGhee, Jr., 1986. Lithostratigraphy of Upper Devonian Scherr- Foreknobs and Lockhaven formations near Allegheny Front of central Pennsylvania: American Association of Petroleum Geologists Bulletin, 70(5): 1- 661.
- Warne, A. G. and G. R. McGhee, Jr., 1991. Stratigraphic subdivisions of the Upper Devonian scherr, Foreknobs, and Lock Haven formations near the Allegheny Front of central Pennsylvania: Northeastern Geology, 13(2): 96- 109.
- Weary, D. J. and A. G. Harris, 1994. Early Frasnian (Late Devonian) conodonts from the Harrell Shale, western foreland fold- and- thrust belt, West Virginia, Maryland, and Pennsylvania, U.S.A.: Courier Forsch.- Institut Senckenberg, 168: 195- 225.
- White, C. D., 1900. Part 2; The stratigraphic succession of the fossil floras of the Pottsville Formation in the southern anthracite coal field, Pennsylvania: United States Geological Survey Annual Report, 20(Part 2): 749- 930.
- Williams, E. G. and R. L. Slingerland, 1986. Catskill sedimentation in central Pennsylvania: Guidebook for the Annual Conference of Pennsylvania Geologists, 51: 73- 79.
- Wilson, B. R. and A. Traverse, 1975. Further information on the palynological stratigraphy of Devonian- Carboniferous rocks of central Pennsylvania: Geoscience and Man, 11: 160.
- Wilson, B. R., A. Traverse, and E. G. Williams, 1984. Palynological delineation of the Mississippian- Pennsylvanian unconformity in west- central Pennsylvania: International Congress on Carboniferous Stratigraphy and Geology, 9(2): 337- 344.
- Wnuk, C., 1984. The paleoecology and growth habits of arborescent lycopods from an in situ swamp forest of Middle Pennsylvanian age (Bernice Basin, Sullivan County, Pennsylvania: Unpublished PhD Thesis, University of Pennsylvania, Philadelphia: 1- 162.
- Woodrow, D. L., R. A. J. Robinson, A. R. Prave, A. Traverse, E. B. Daeschler, N. D. Rowe, and N. A. DeLaney, 1995. Stratigraphic, sedimentologic, and temporal framework of Red Hill (Upper Devonian Catskill Formation) near Hyner, Clinton County, Pennsylvania; site of the oldest amphibian known from North America: Guidebook for the Annual Field Conference of Pennsylvania Geologists, 60.
- Yu, J. and H. B. Rollins, 1987. Ostracode distribution within the Brush Creek member (Glen Shaw Formation, Upper Pennsylvanian) of the North American Appalachian Basin: International Congress on Carboniferous Stratigraphy and Geology Abstracts of Papers, 11: 108.

DATA SETS:

- | | |
|------------------|---|
| DS- ALPO-
XXX | Allegheny Portage Railroad National Historic Site Paleontological Archives. 5/1985 present. (hard copy data; reports; electronic data; photographs; maps; publications). Originated by Santucci, Vincent; status: Active. |
| DS- ALPO-
XXX | Allegheny Portage Railroad National Historic Site Files, Archive, Museum Records. 8/1964 present. (hard copy data; reports; electronic data; photographs; maps; publications). Originated by Allegheny Portage Railroad National Historic Site; status: Active. |

BLUESTONE NATIONAL SCENIC RIVER

Bluestone National Scenic River (BLUE) was originally established in 1988 to preserve natural and historic features of the Appalachian Plateau within an 11-mile stretch of the lower Bluestone River.

BASELINE PALEONTOLOGICAL RESOURCE INVENTORIES:

The majority of BLUE is placed within the Upper Mississippian Hinton Formation. The perimeter of the park boundary also crosses into small sections of the Bluestone and Princeton formations. Additionally, Quaternary alluvium can be found in a limb that extends into the northeastern section of the park.

The oldest geologic formation within BLUE is the Upper Mississippian Hinton Formation. This formation is composed of sandstone, shale, siltstone, limestone, and coal and represents the interrelationship of marine and terrestrial sediments. Englund and others (1979a) report that plant fossils are found in the Hinton Formation and the flora correlates with the Namurian A Stage of Europe. *Stigmaria stellata* is a characteristic plant fossil found in this formation. Marine fossils are known from the limestone and calcareous shale deposits. These include rugose corals, bryozoans, brachiopods, pelecypods, gastropods, trilobites, crinoids, and a few fish fossils (Englund et al., 1979a; Miller, 1998). Brackish and freshwater assemblages also occur in the Hinton Formation (Henry and Gordon, 1979). Additionally, Hoare (1993) reports bivalve fauna from the Hinton and Bluestone formations of Virginia and West Virginia that include 49 different species from 29 genera. Miller (1998) reports rare occurrences of amphibian teeth up to 2cm in length from a basal conglomerate of the Hinton Formation. Beuthin and Blake (2004) have revised the stratigraphy and nomenclature for the Upper Hinton Formation and used general fossil content along with other characteristics to define the members. The fossils that were mentioned in this revision include ostracodes, lycopsid roots and stems, bivalve-dominated bioherms, corals, conularids, bryozoans, brachiopods, myalinid and pectinid bivalves, gastropods, cephalopods, trilobites, pelmatozoans (echinoderms), and burrows.

The Princeton Sandstone and the Bluestone Formation are mapped undivided within the boundaries of BLUE. These two Upper Mississippian formations consist of sandstone, shale, and siltstone. The Princeton Sandstone contains marine fauna, while the Bluestone Formation has produced marine, fresh, and brackish water fauna. The Bluestone Formation contains abundant ostracodes, pelecypods, and the brachiopod *Lingula* (Englund et al., 1979b). From the Bluestone Formation in Virginia and West Virginia, nonmarine ostracodes were researched by Sohn (1985). These ostracodes are of particular importance because they represent the oldest record in North America of particular adductor-muscle-attachment scar patterns. Henry and Gordon (1979) report on 21 different fossil invertebrate species from this formation. Miller (1998) reports in a Bluestone Formation shale member thin-valved bivalves, plant fragments, and imprints of shrimp-like arthropods. At a locality in Mercer County, West Virginia, a fossil lag deposit occurs at the contact between the Princeton and Bluestone formations and contains marine bivalves, brachiopods, and gastropods (Miller, 1998). Plant fossils are also known from these two geologic units and include *Lepidodendron veltheimi*, *Sphenopteris elegans*, and *Stigmaria stellata* (Gillespie and Pfefferkorn, 1979). Additionally *Sphenophyllum tenerrimum*, *Stigmata ficoides*, *Cordaitea* spp., *Calamites* spp., and *Asterophyllites longifolius* are also identified from the Bluestone Formation.

REFERENCES CITED:

- Beuthin, J. D. and B. M. Blake Jr., 2004. Revised Stratigraphy and Nomenclature for the Upper Hinton Formation (Upper Mississippian) Based on Recognition of Regional Marine Zones, Southern West Virginia: Southeastern Geology, 42(3): 165-178.
- Englund, K. J., W. H. Gillespie, and T. W. Henry, 1979a. Stop descriptions; first day: AGI Selected Guidebook Series, 1: 3-5.
- Englund, K. J., H. W. Pfefferkorn, and T. W. Henry, 1979b. Stop descriptions; second day: AGI Selected Guidebook Series, 1: 7-14.

- Englund, K. J., R. E. Thomas, and J. B. Roen, 1994. Geology of the Cumberland Gap area, Kentucky, Tennessee, and Virginia in Schultz, A. P. and E. K. Rader, (eds.), Studies in eastern energy and the environment: Virginia Division of Mineral Resources Publication, 132: 38- 42.
- Gillespie, W. H. and H. W. Pfefferkorn, 1979. Distribution of commonly occurring plant megafossils in the proposed Pennsylvanian system stratotype: AGI Selected Guidebook Series, 1: 87- 96.
- Henry, T. W. and M. Gordon, Jr., 1979. Late Devonian through Early Permian (?) invertebrate faunas in proposed Pennsylvanian System stratotype area: AGI Selected Guidebook Series, 1: 97- 103.
- Hoare, R. D., 1993. Mississippian (Chesterian) bivalves from the Pennsylvanian stratotype area in West Virginia and Virginia: Journal of Paleontology, 67(3): 374- 396.
- Miller, D. J., 1998. Depositional Environments and Sequence Stratigraphy of Upper Mississippian Strata in the Central Appalachian Basin: PhD Thesis, Virginia Polytechnic Institute and State University: 1- 87.
- Sohn, I. G., 1985. Latest Mississippian (Namurian A) nonmarine ostracodes from West Virginia and Virginia: Journal of Paleontology, 59(2): 446- 460.

ADDITIONAL REFERENCES:

- Gordon, M. Jr. and T. W. Henry, 1981. Paleontologic evidence concerning the Mississippian- Pennsylvanian boundary in the central Appalachian Basin: Geological Society of America Abstracts with Programs, 13(7): 462.
- Henry, T. W. and M. Gordon, Jr., 1992. Middle and upper Chesterian brachiopod biostratigraphy, eastern Appalachians, Virginia and West Virginia: Oklahoma Geological Survey Circular, 94: 1- 21.
- Henry, T. W. and M. Gordon, Jr., 1990. Upper Mississippian brachiopod biostratigraphy, eastern Appalachians: Geological Society of America Abstracts with Programs, South- Central Section, 22(1): 8- 9.
- Henry, T. W. and G. Mackenzie, Jr., 1992. Middle and upper Chesterian brachiopod stratigraphy, eastern Appalachians, Virginia and West Virginia: Oklahoma Geological Survey Circular, 94: 1- 11.
- Huffman, S. P. and J. D. Beuthin, 2001. Paleoenvironmental and sequence stratigraphic sequence interpretation of a marine shellbed in the Hinton Formation, southern West Virginia: Geological Society of America Abstracts with Programs, Southeastern Section, 33(2): 76.
- Nolde, J. E., 1994. Devonian to Pennsylvanian stratigraphy and coal beds of the Appalachian plateaus province in Geology and mineral resources of the southwest Virginia coalfield: Virginia Division of Mineral Resources Publication, 131: 1- 85.
- Smithson, T. R., 1982. The cranial morphology of *Greererpeton burkemorani* Romer (Amphibia, Temnospondyli): Zoological Journal of the Linnean Society, 76(1): 29- 90.
- Sullivan, W. A. and J. L. Allen, 2001. Stratigraphy of upper Hinton Formation sandstones in the Bluestone River Gorge, southern West Virginia: Geological Society of America Abstracts with Programs, Southeastern Section, 33(2): 77.
- Weems, R. E. and J. F. Windolph, Jr., 1986. A new actinopterygian fish (Pelecanisciformes) from the Upper Mississippian Bluestone Formation of West Virginia: Proceedings of the Biological Society of Washington, 99(4): 584- 601.
- Windolph, J. F., Jr. and R. E. Weems, 1987. The significance of a fossil fish (*Tanypteroichthys pridenensis*) from the Lower Carboniferous (Namurian) Pride Shale Member of the Bluestone Formation of West Virginia, USA: International Congress on Carboniferous Stratigraphy and Geology, 11: 102- 103.
- Winston, R. B., 1990. Implications of paleobotany of Pennsylvanian- age coal of the central Appalachian basin for climate and coal- bed development: Geological Society of America Bulletin, 102: 1720- 1726.

DATA SETS:

- DS- BLUE- Bluestone National Scenic River Paleontological Archives. 5/1985 present. (hard copy
XXX data; reports; electronic data; photographs; maps; publications). Originated by Santucci,
Vincent; status: Active.

DS- BLUE- Bluestone National Scenic River Files, Archive, Museum Records. 10/1988 present. (hard
XXX copy data; reports; electronic data; photographs; maps; publications). Originated by
Bluestone National Scenic River; status: Active.

DELAWARE WATER GAP NATIONAL RECREATION AREA

Delaware Water Gap National Recreation Area (DEWA) was established in 1965 to preserve relatively unspoiled scenic and historic land along the uppermost section of the Delaware River that forms the political boundary between northwestern New Jersey and northeastern Pennsylvania. As the park name implies, the park preserves the segment of river that flows through the famous gap in the Appalachian Mountains.

BASELINE PALEONTOLOGICAL RESOURCE INVENTORIES:

Delaware Water Gap National Recreation Area contains a rich Paleozoic fossil record and sparse, but under-explored Pleistocene (Ice Age) fossils. Over 1,300 paleontological specimens within DEWA's museum collection profile are held at the New Jersey State Museum, 90% of which have been identified and cataloged. There are plans to catalog these remaining specimens at the New Jersey State Museum when funding becomes available.

The Middle and Upper Ordovician Martinsburg Formation is the oldest fossiliferous unit exposed within DEWA. This thick unit (maximum thickness of 12,800 feet) is primarily composed of shales, sandstones, slates and greywacke siltstone (Epstein, 2001a; Parris and Cruikshank, 1984). There are reports of hundreds of specimens of shelly and graptolitic material recovered from the Martinsburg Formation at a number of sites in and around DEWA (Parris and Cruikshank, 1984, 1992; Parris et al., 1998a, 2001). Conulariid (*Conularia* cf. *trentonensis*), bryozoan (cf. *Prasopora* sp.), brachiopod (*Plectorthis plicatella*, *Dinorthis* sp., *Sowerbyella rugosa*, *Resserella multisecta*, *Dalmanella testudinaria*, and *Orbiculoidea* sp.), bivalve (*Prolobella corrugate*), nautiloid, gastropod (cf. *Sinuities* sp., cf. *Hormotoma* sp., and *Murchisonia* sp.), trilobite (cf. *Pterygomotopus* sp. and *Cryptolithus tessellatus*), worms (*Cornulites* sp.), and crinoid (Crinoidea, indeterminate) specimens have been documented. Additionally, Beerbower (1956) reports on the occurrence of the trilobite *Triarthrus*, but unfortunately the locality is completely covered by construction (Parris and Cruikshank, 1984). From more than 20 localities within the Martinsburg Formation in the DEWA area, 26 graptolite genera have been identified including: *Adelograptus*, *Amplexograptus*, *Callograptus*, *Climacograptus*, *Clonograptus*, *Corynoides*, *Cryptograptus*, *Dicellograptus*, *Dicranograptus*, *Dictyonema*, *Didymograptus*, *Diplograptus*, *Glossograptus*, *Glyptograptus*, *Hallograptus*, *Isograptus*, *Lasiograptus*, *Nemagraptus*, *Orthograptus*, *Pseudisograptus*, *Pseudoclimacograptus*, *Pseudotrigranograptus*, *?Reteograptus*, *Retiograptus*, *Tetragraptus*, and *Xiphograptus* (Parris and Cruikshank, 1992; Parris et al., 1998a, 2001). A specific report on brachiopod ecology of the Martinsburg Formation was written by Bretsky and others (1969).

The Silurian Shawangunk Formation has a maximum thickness of 2,100 feet and primarily consists of coarse conglomerate, quartzose sandstone, and shale (Laughrey, 1999). The deposits represent fluvial and paralic environments (Laughrey, 1999). The Shawangunk Formation is sparsely fossiliferous and contains lingulid brachiopods, extinct arthropods (eurypterid remains including cf. *Hughmilleria shawangunk*), and rare Dipleurozoa (jellyfish-like fauna including *Rutgersella delawarensis*) (Parris and Cruikshank, 1984; Laughrey, 1999; Faul, 1990; Fox, 1968). Additionally, trace fossils are known from the Shawangunk Formation, including the feeding burrow *Arthropycus alleghaniense* and vertical burrow *Skolithos* (Metz, 1997).

Overlying the Shawangunk Formation is the Silurian Bloomsburg Formation. This unit is composed of grayish-red claystone, siltstone, shale, sandstone, and conglomeratic sandstone. The formation is a time-transgressive unit (increasing young to the east) with deltaic sediments that have been deposited in saline waters supporting brackish-water fauna (Laughrey, 1999). Brachiopods and ostracodes are locally common while foraminifera, bryozoans, mollusks, and crinoids are rare (Laughrey, 1999). Fish scales of ostracoderms (*Vernonaspis* and *Americaspis*) occur locally in the Bloomsburg Formation (Epstein, 2001a; Monteverde, 2001a). Beerbower and Hait (1959) reported on two fish localities near DEWA that produced significant specimens of *Archegonaspis van ingeni*. Staff at the New Jersey State Museum relocated those sites and expanded the search for further fish evidence (Stein and Parris, 1979). This material awaits study and cataloging at the museum. Robert Denison (1964) investigated Silurian fish and was responsible for

formalizing some of the taxonomy used for Silurian and Devonian Cyathaspididae. Hoskins (1960a, 1960b, 1961) reports specifically on the fossils found within the red beds of the Bloomsburg Formation; citing foraminifera, ostracods, bryozoans, brachiopods, mollusks, crinoids, and fish scales. Metz (2000) reports the partial trace of an ancestral horseshoe crab that has rarely been documented.

The Silurian Bossardville Limestone consists of laminated argillaceous limestone and calcareous shale and averages 100 feet in thickness (Laughrey, 1999; Epstein, 2001a). The depositional environments can be categorized as supratidal, intertidal, and subtidal marine environments (Laughrey, 1999). Ostracodes are the dominant fossils in this formation and Leperditidae specimens were found within DEWA (Parris and Albright, 1979a). Epstein and others (1967) also discuss the paleontology of the Bossardville Limestone.

The Silurian Decker Formation is composed of arenaceous and argillaceous limestone, calcareous sandstone and siltstone, and quartz-pebble conglomerate (Epstein, 2001a; Laughrey, 1999). The formation is approximately 100 feet thick and most likely represents a barrier beach and/or biostromal banks (Laughrey, 1999). This geologic unit is abundantly fossiliferous. Parris and Albright (1979a) report 9 coral, 4 bryozoan, 21 brachiopod, 3 gastropod, 1 nautiloid, 8 ostracod, 5 trilobite, 3 worm, and 1 crinoid species from the Decker Formation. Between 1996 and 2003, Metz conducted many investigations regarding trace fossils of the Decker Formation. The ichnogenera *Cruziana* isp., *Diplichnites* isp., *Lockeia siliquaria*, *Palaeophycus heberti*, *Planolites beverleyensis*, *Protovirgularia rugosa*, and *Skolithos* sp. have been identified and the likely producers of these trackways are arthropods, mollusks, and worm-like forms. In addition to the trace fossils, Metz also reports corals, bryozoans, brachiopods, and crinoid debris from the Decker Formation.

The Upper Silurian and Lower Devonian Rondout Formation is approximately 30 feet thick and is composed of calcareous shale, argillaceous limestone, biostromal limestone, and laminated dolomite (Epstein, 2001a). Fauna from this formation within DEWA include 6 coral, 2 bryozoan, 3 brachiopod, 1 clam, 4 ostracod, and 1 crinoid species (Parris and Albright, 1979a; Herper, 1951a).

The Lower Devonian Coeymans Formation consists of many members, including beds of the previously named Manlius Limestone. The Coeymans Formation primarily consists of arenaceous, argillaceous, and biogenic limestone and preserves a nearshore environment (Epstein, 2001a; Laughrey, 1999). Epstein (2001b) recounts the occurrence of conodonts from the Coeymans Formation. Parris and Albright (1979a) report 6 coral, 4 bryozoan, 30 brachiopod, 6 clam, 3 gastropod, 1 nautiloid, 6 ostracod, 3 trilobite, 1 crinoid, and 2 worm species from this unit within DEWA. According to National Park Service Investigator Annual Reporting between 1996 and 2003, Metz reports the occurrence of crinoid columnals and the trace fossils *Skolithos linearis*, *S. verticalis*, *S. pusillus*?, *Chondrites affinis*, *C. isp.*, *Palaeophycus tubularis*, and *Planolites beverleyensis* from the Coeymans Formation. There are fossil-rich patch reefs and reef flanks in the Coeymans Formation that contain bioclastic debris of tabulate corals (*Cladopora* and *Favosites*), rugose corals, stromatoporoids, brachiopods, and crinoids (Monteverde, 2001b; Metz, 2003).

The Lower Devonian New Scotland Formation is approximately 70 feet thick and is composed of dark-gray silty calcareous shale with lenticular argillaceous limestone (Epstein, 2001a). Both the shale and the limestone are known to contain fossils. Sponges (*Hindia fibrosa*), corals (*Enterolasma strictum*), bryozoans, brachiopods (28 species), clams (3 species), gastropods (2 species), nautiloids (Michelinoceratidae), trilobites (2 species), crinoids (*Ichthyocrinus magnaradialis*), and worms (*Tentaculites elongates*) have been discovered from the New Scotland Formation within DEWA (Parris and Albright, 1979a).

The Lower Devonian Minisink Limestone is a dark- to medium-gray argillaceous limestone (Epstein, 2001a). Although the thickness is less than 15 feet, fossils have been found from this geologic unit. The fauna resembles that of the New Scotland Formation and consists of corals, bryozoans, brachiopods, clams, gastropods, ostracods, trilobites, and crinoids (Parris and Albright, 1979a).

The Lower Devonian Port Ewen Shale is 150 feet thick and is a laminated calcareous shale and siltstone (Epstein, 2001a). Parris and Albright (1979a) report 11 brachiopod species, ostracods, 3 trilobite species, and crinoids from the Port Ewen Shale within DEWA. Additionally, Albright (1995) reports a single specimen of

conulariid, *Conularia pyramidalis*, from a site that has since been destroyed. This report also includes other specimens occurring in DEWA from younger strata.

The Lower Devonian Oriskany Group is composed of multiple geologic units; Shriver Chert, Ridgeley Formation, and Glenierie Formation (Ver Straeten et al., 1995). The Shriver Chert is 50- 85 feet thick and composed of shale, siltstone, pods of dark- gray chert, and minor calcareous sandstone (Epstein, 2001a). The Ridgeley Sandstone, with a maximum thickness of 16 feet, is a fine- to coarse- grained calcareous sandstone with lesser amounts of siltstone, arenaceous limestone, and chert (Epstein, 2001a). Parris and Albright (1979a) refer to collections discovered from the Oriskany Formation within DEWA. Further research has indicated that these collections come from the Glenierie Formation (northernmost sections of DEWA) and the Ridgeley Formation (southern sections of DEWA) (S. Albright, personal communication, 2004). These collections include 3 coral, 1 bryozoan, 41 brachiopod, 5 gastropod, 1 nautiloid, 3 worms, 2 ostracod, 3 trilobite, and 1 crinoid species. Specifically from the Ridgeley Sandstone, Metz (2002) reported *Planolites* trace fossils that indicates a beach or barrier beach deposition. Ver Straeten (2001a) reports large, robust brachiopods (*Costispirifer*, *Rensselaeria*, and *Hipparionyx*) from the Oriskany Sandstone. Ostracodes from Sussex County, New Jersey, including Oriskany Formation specimens, were the topic of a Master's Thesis by Horton (1950).

The Lower Devonian Esopus Formation has a maximum thickness of 300 feet and consists of shale and arenaceous siltstone (Epstein, 2001a). *Taonurus* burrows are common in this geologic unit (Epstein, 1984; 2001a). Metz (1996- 2003) collected *Taonurus* and *Skolithos* trace fossils from the Esopus Formation. Additionally, *Zoophycos* and *Chondrites* ichnofossils are also present (Ver Straeten, 2001a). Corals, conularids, brachiopods, gastropods, cephalopods, arthropods, and crinoids have been discovered from the Esopus Formation within DEWA (Parris and Albright, 1979b). The type specimen of *Reticulaconularia sussexensis* (conulariid) was discovered in the Esopus Formation and described by Henry Herpers (1949). Investigations by Babcock and Feldman (1986a, 1986b) resulted in the complete taxonomic revision of these rare, problematic organisms.

The Lower Devonian Schoharie Formation is 100 to 150 feet thick and is primarily composed of argillaceous calcareous siltstone (Epstein, 2001a). Corals, brachiopods, gastropods, cephalopods, and trilobites are noted from DEWA (Parris and Albright, 1979b; Ver Straeten, 2001b). Trace fossils of *Zoophycos* and *Chondrites* are also common in the Schoharie Formation (Ver Straeten, 2001a).

The Middle Devonian Buttermilk Falls Limestone is predominately composed of a fossiliferous gray limestone. Parris and Albright (1979b) report 3 coral, 1 bryozoan, 23 brachiopod, 2 cephalopod, and 6 trilobite species from DEWA. Epstein (1984) reports crinoid columnals in the Buttermilk Falls Limestone. *Helminthopsis* trace fossils that were deposited in subtidal waters have been found in this unit (Metz, 2002).

The Middle Devonian Marcellus Formation has a maximum thickness of 1,150 feet and consists of silty shale, laminated shale, and shaly limestone, (Epstein, 2001a). Paleontological sites are rare within the Marcellus Formation and occur in fine- grained, black shale containing diminutive fauna typical of under- oxygenated, deep marine waters (S. Albright, personal communication, 2004). Indeterminate plant material, an indeterminate conulariid, indeterminate bryozoans, 15 brachiopod species, 10 bivalves, 1 worm (*Styliolina fissurella*), 2 cephalopod species, 2 trilobite species, and an additional arthropod (*Onychodus sigmoides*?) were all discovered in the Marcellus Formation within DEWA (Parris and Albright, 1979b). Storm (1985) studied fauna from the Marcellus Formation for a Master's Thesis that included sites from Sussex County, New Jersey.

The Middle Devonian Mahantango Formation has a maximum thickness of over 2,000 feet and is composed of siltstone and silty- shale (Epstein, 2001a). This formation has produced plant fragments, algae (*Receptaculites*? sp.), corals, conularids, bryozoans, brachiopods, bivalves, gastropods, cephalopods, trilobites, additional arthropods, worms, crinoid columnals, fish, and burrows (Parris and Albright, 1979b). Within DEWA, Parris and Albright (1979b) report that the Mahantango Formation is very well- known for its fossils and contains plant impressions and carbonized fragments, 4 coral species, 3 bryozoan species, 12 brachiopod species, 6 bivalve species, 3 trilobite species, crinoid columnals, and trace fossils (burrows, tracks,

and trails). In 1971, El-Ashry reported on the discovery of a new coral reef named Barton's reef that represents a stable shelf environment with rugose and tabulate corals. A faunally rich area from the Mahantango Formation termed the Centerfield Fossil Zone/Horizon is located within Monroe County (Beerbower, 1957; Wilt, 2001). Cramer (1959) describes a starfish (*Hudsonaster wardi*) found near Milford, Pennsylvania that expanded the age range for the genus. Colonial coral populations from the Mahantango Formation of Monroe County, Pennsylvania were the emphasis of study for Wolosz and Wallace (1981). Conularids from the Mahantango Formation were reported by Babcock (1985) and Kasznica (1986).

The Upper Devonian Trimmers Rock Formation is 720-1,825 feet in thickness and consists of siltstone, shale, and very fine-grained sandstone (Epstein, 2001a). Fauna from the Trimmers Rock Formation is diverse due to the wide age and geographical range. A broad variety of plants, corals, bryozoans, brachiopods, bivalves, gastropods, worms, trilobites, additional arthropods, crinoids, and fish specimens have been recovered from this formation (Parris and Albright, 1979b). Inners (1981) studied the invertebrate fauna from beds within the Trimmers Rock Formation in Columbia County, Pennsylvania.

Pleistocene deposits are found within the boundaries of DEWA and have potential to produce paleontological resources. Fossils have been discovered from several localities neighboring the park. Many mastodons have been recovered including a mastodon from Marshall's Creek that was discovered in bog muds (Hoff, 1969). The most complete specimen of a *Cervalces scotti* (elk-moose) was found in Warren County, New Jersey and an additional specimen was found just outside DEWA along with freshwater mollusks (Parris and Albright, 1979a). Hartman Cave (or Crystal Hill Cave) in Monroe County, Pennsylvania has produced a wealth of vertebrate material. This cave contains material from a probable date range of the Pleistocene, Colonial, and Recent periods (Parris and Albright, 1979a). Hay (1923) reports the following species list from Hartman Cave: *Chelydra serpentine* (common snapping turtle), *Terrapene carolina* (eastern box turtle), *Meleagris gallopavo* (turkey), *Rangifer caribou* (caribou), *Odocoileus virginianus* (white-tailed deer), *Mylohyus pennsylvanicus* (extinct peccary), *Equus* sp. (horse), *Cervus canadensis* (elk), *Bison bison* (questionable bison identification), *Marmota monax* (woodchuck), *Tamias striatus* (eastern chipmunk), *Sciurus carolinensis* (eastern gray squirrel), *Castor canadensis* (beaver), *Peromyscus leucopus* (white-footed mouse), *Neotoma floridana* (eastern woodrat), *Microtus pennsylvanicus* (meadow vole), *Erethizon dorsatum* (porcupine), *Castoroides ohioensis* (extinct giant beaver), *Sylvilagus floridanus* (eastern cottontail), *Myotis subulatus* (small-footed myotis), *Eptesicus fuscus* (big brown bat), *Scalopus aquaticus* (eastern mole), *Procyon lotor* (raccoon), *Mustela erminea* (short-tailed weasel), *Mephitis mephitis* (striped skunk), *Urocyon cinereoargenteus* (gray fox), *Canis lupus* (questionable gray wolf identification), and *Lynx canadensis* (Canada lynx).

COOPERATIVE PROJECTS:

- Ordovician Faunas in the Delaware Water Gap region David Parris, New Jersey State Museum (1984-2000).
- Lower and Middle Paleozoic Paleontology of the Delaware Water Gap National Recreation Area and Vicinity Shirley Albright, New Jersey State Museum (1991-1998).
- Geology of Delaware Water Gap National Recreation Area Jack Epstein, U.S. Geological Survey (1996-1999).
- Ichnologic investigation of Paleozoic rocks in northern New Jersey (Delaware Water Gap National Recreation Area) Robert Metz, Kean University (1996-2003).
- Geologic and Paleontologic Scoping of Delaware Water Gap National Recreation Area National Park Service Geologic Resources Division (October 2001).

REFERENCES CITED:

- Albright, S. S., 1995. The Conulariida of New Jersey *in* Baker, J., (ed.), Proceedings of the 12th Symposium of the Geological Association of New Jersey: Contributions to the Paleontology of New Jersey: 222- 228.
- Babcock, L. E., 1985. Mahantango conulariid considered a hyolithid: Pennsylvania Geology, 16(3): 14- 16.
- Babcock, L. E. and R. M. Feldman, 1986a. Devonian and Mississippian Conulariids of North America. Part A. General Description and *Conularia*: Carnegie Museum of Natural History, Annals, 55(15): 349- 410.
- Babcock, L. E. and R. M. Feldman, 1986b. Devonian and Mississippian Conulariids of North America. Part B. *Paraconularia*, *Reticulaconularia*, New Genus, and organisms rejected from Conulariida: Carnegie Museum of Natural History, Annals, 55(16): 411- 479.
- Beerbower, J. R. 1957. Paleocology of the Centerfield coral zone, East Stroudsburg locality, Monroe County, Pennsylvania: Pennsylvania Academy of Sciences Proceedings, 31: 91- 97.
- Beerbower, J., 1956. The Ordovician- Silurian Contact, Delaware Water Gap, New Jersey: Pennsylvania Academy of Science, XXX: 146- 149.
- Bretsky, P. W., K. W. Flessa, and S. S. Bretsky, 1969. Brachiopod ecology in the Ordovician of eastern Pennsylvania: Journal of Paleontology, 43(2): 312- 321.
- Cramer, H. R., 1959. Devonian starfish from Pike County, Pennsylvania: Journal of Paleontology, 33(3): 471- 473.
- Denison, R. H., 1964. The Cyathaspididae, a Family of Silurian and Devonian Jawless Vertebrates: Fieldiana, 13(5): 309- 473.
- El-Ashry, M. T., 1971. New Devonian Coral Reef from Monroe County, Eastern Pennsylvania: Proceedings of the Pennsylvania Academy of Science, 45: 5- 8.
- Epstein, J. B., 2001a. Stratigraphy in the region of the Delaware Water Gap National Recreation Area *in* Inners, J. D. and G. M. Fleeger, (eds.), 2001 a Delaware River odyssey, Guidebook, 66th Annual Field Conference of Pennsylvania Geologists, Shawnee- on- Delaware, PA: 1- 13.
- Epstein, J. B., 2001b. Stop 3; Yards creek pump- storage generating station: regional geology Ordovician- Silurian unconformity, Taconic/allegghanian deformation, and origin of slaty cleavage *in* Inners, J. D. and G. M. Fleeger, (eds.), 2001 a Delaware River odyssey, Guidebook, 66th Annual Field Conference of Pennsylvania Geologists, Shawnee- on- Delaware, PA: 171- 182.
- Epstein, J. B., 1984. Onesquethawan stratigraphy (Lower and Middel Devonian) of northeastern Pennsylvania: U. S. Geological Survey Professional Paper, 1337: 1- 91.
- Epstein, A. G., J. B. Epstein, W. J. Spink, and D. S. Jennings, 1967. Upper Silurian and Lower Devonian stratigraphy of northeastern Pennsylvania and New Jersey, and southeasternmost New York: U. S. Geological Survey Bulletin, 1243: 1- 74.
- Faul, C., 1990. Eurypterids from a new locality in the Shawangunk Formation, New Jersey and Pennsylvania: Geological Association of New Jersey, Annual Field Conference, 4: 78.
- Fox, S. K., Jr., 1968. Dipleurozoa from Lower Silurian of North America: Science, 162(3849): 119- 120.
- George, C., J. R. Wright, and K. High, 1997. Delaware Water Gap National Recreation Area Paleontological Database: information gathered from reports submitted by Parris and Albright (1979a, 1979b) and Parris and Cruikshank (1984).
- Hay, O. P., 1923. Report on work done on the Pleistocene epoch and its vertebrate fossils: Carnegie Institution of Washington, Year Book, 21: 1- 395.
- Herpers, H. F., Jr., 1949. A new conularid from the Esopus Formation, Sussex County, New Jersey: New Jersey Department of Conservation, Miscellaneous Geology Paper: 1- 7.
- Herpers, H. F., Jr., 1951a. The stratigraphy of the Rondout Limestone in New Jersey: New Jersey Department of Conservation, Geology Series Bulletin, 60: 1- 14.
- Hoff, D., 1969. Mastodon at Marshall s Creek: Pennsylvania Game News, 40(2): 2- 7.
- Horton, E. H., 1950. Some Lower Devonian Ostracoda from northern New Jersey: Master s Thesis, Rutgers, The State University, New Brunswick, New Jersey: 1- 57.
- Hoskins, D. M., 1960a. Fossils from the red beds of the Bloomsburg Formation of central Pennsylvania: Geological Society of America Bulletin, 71(12, Part 2): 1- 1891.

- Hoskins, D. M., 1960b. The stratigraphy and paleontology of the Silurian Bloomsburg Formation (red beds) of Pennsylvania: PhD Thesis, Bryn Mawr College, Bryn Mawr, Pennsylvania: 1- 241.
- Hoskins, D. M., 1961. Stratigraphy and Paleontology of the Bloomsburg Formation of Pennsylvania and adjacent states: Topographic and Geologic Survey Bulletin, G- 36.
- Inners, J. D., 1981. The fossiliferous Stoney Brook beds of Columbia County, Pennsylvania: *Pennsylvania Geology*, 12(5): 8- 13.
- Kasznica, J. M., 1986. A conularid from the Mahantango Formation; first document report: *Pennsylvania Geology*, 17(3): 13- 16.
- Laughrey, C. D., 1999. Chapter 6; Silurian and Transition to Devonian *in* Schultz, C. H., (ed.), *The Geology of Pennsylvania: Pennsylvania Geological Survey and Pittsburgh Geological Survey*: 91- 107.
- Metz, R., 1997. Lower Silurian trace fossils from the Shawangunk Formation, Delaware Water Gap, New Jersey: *Geological Society of America Abstracts with Programs, Northeastern Section*, 29(1): 66.
- Metz, R., 2000. Ancestral horseshoe crab (suborder Synziphosurina) and trace fossils from the Paleozoic of northwestern New Jersey: *Geological Society of America Abstracts with Programs, Northeastern Section*, 32(1): 59.
- Metz, R., 2001. Trace fossils in Silurian and Devonian strata from the Delaware Water Gap National Recreation Area, New Jersey: *PaleoBios*, 21(2, Suppl.): 1- 93.
- Metz, R., 2002. Trace fossils, including that of a myriad- like arthropod tracemaker, from Silurian and Devonian strata of New Jersey: *Geological Society of America Abstracts with Programs*.
- Metz, R., 2003. Lower Devonian trace fossils from shallow marine deposits, Shawnee Island Member of the Coeymans Formation, northwestern New Jersey: *Northeastern Geology and Environmental Sciences*, 25(3): 206- 214.
- Monteverde, D. H., 2001a. Pahaquarry Copper Mine *in* Inners, J. D. and G. M. Fleeger, (eds.), 2001 a Delaware River odyssey, Guidebook, 66th Annual Field Conference of Pennsylvania Geologists, Shawnee- on- Delaware, PA: 150- 155.
- Monteverde, D. H., 2001b. Montague mini- mall fossil site: Flank of a coralline bioherm in the Coeymans Formation *in* Inners, J. D. and G. M. Fleeger, (eds.), 2001 a Delaware River odyssey, Guidebook, 66th Annual Field Conference of Pennsylvania Geologists, Shawnee- on- Delaware, PA: 191- 198.
- Parris, D. C. and K. M. Cruikshank, 1984. Ordovician Fossils of the Delaware Water Gap Area: Contractual Report to the National Park Service: 1- 28.
- Parris, D. C. and K. M. Cruikshank, 1992. Graptolite Biostratigraphy of the Ordovician Martinsburg Formation in New Jersey and Contiguous Areas: *New Jersey Geological Survey Report*, 28: 1- 18.
- Parris, D. C. and S. S. Albright, 1979a. Fossil Resources of the Delaware Water Gap National Recreation Area; Part I: Silurian and Early Devonian Fossils: Contractual Report to the National Park Service: 1- 49.
- Parris, D. C. and S. S. Albright, 1979b. Fossil Resources of the Delaware Water Gap National Recreation Area; Part II: Devonian Fossils: Contractual Report to the National Park Service: 1- 60.
- Parris, D. C., L. F. Miller, and R. Dalton, 2001. Biostratigraphic determination of the basal Martinsburg Formation in the Delaware Water Gap region *in* Inners, J. D. and G. M. Fleeger, (eds.), *A Delaware Odyssey, Guidebook, 66th Annual Field Conference of Pennsylvania Geologists, Shawnee- on- Delaware, PA: 68- 71.*
- Parris, D. C., L. F. Miller, and S. C. Finney, 1998a. Comparative Graptolite Biostratigraphy of the Jutland Klippe to the Martinsburg Formation at Delaware Water Gap National Recreation Area *in* Santucci, V. L. and L. McClelland, (eds.), *National Park Service Paleontological Research Abstract Volume, Technical Report NPS/NRGRD/GRDTR- 98/01: 49- 52.*
- Stein, R. J. and D. C. Parris, 1979. Silurian Fish from the Delaware Water Gap Area: Contractual Report of the U.S. Department of the Interior: 1- 4.
- Storm, E. V., 1985. A study of a diminutive fauna from the Marcellus Formation (Middle Devonian- Erian) from sites in Albany County, New York, and Sussex County, New Jersey: Master s Thesis, Montclair State College, Upper Montclair, New Jersey: 1- 27.
- Ver Straeten, C. A., 2001a. Event and sequence stratigraphy and a new synthesis of the Lower to Middle Devonian, eastern Pennsylvania and adjacent areas *in* Inners, J. D. and G. M. Fleeger, (eds.), 2001 a Delaware River odyssey, Guidebook, 66th Annual Field Conference of Pennsylvania Geologists, Shawnee- on- Delaware, PA: 35- 53.

- Ver Straeten, C. A., 2001b. The Schoharie Formation in eastern Pennsylvania *in* Inners, J. D. and G. M. Fleeger, (eds.), 2001 a Delaware River odyssey, Guidebook, 66th Annual Field Conference of Pennsylvania Geologists, Shawnee-on-Delaware, PA: 54- 60.
- Ver Straeten, C. A., C. Brett, and S. S. Albright, 1995. Stratigraphic and Paleontologic Overview of the Upper, Lower and Middle Devonian, New Jersey and Adjacent Areas *in* Baker, J., (ed.), Proceedings of the 12th Symposium of the Geological Association of New Jersey: Contributions to the Paleontology of New Jersey: 229- 239.
- Wilt, D., 2001. Gem of the Middle Devonian: The Centerfield Fossil Zone at Brodhead Creek *in* Inners, J. D. and G. M. Fleeger, (eds.), 2001 a Delaware River odyssey, Guidebook, 66th Annual Field Conference of Pennsylvania Geologists, Shawnee-on-Delaware, PA: 72- 80.
- Wolosz, T. H. and R. J. Wallace, 1981. Coral population variations in a colonizing community (Devonian) *in* Gray, J., A. J. Boucot, and W. B. N. Berry, (eds.), Communities of the past: Hutchinson Ross Publishing Company, Stroudsburg, Pennsylvania: 223- 241.

ADDITIONAL REFERENCES:

- Agostaro, R. and R. H. Waines, 1987. Atypical growth in laminar stromatoporoid coenostea, Glasco Limestone Member, Rondout Formation (latest Silurian), Kingston, southeastern New York: Geological Society of America Abstracts with Programs, 19(1): 1.
- Albright, S. S., 1991. A Review of Paleontological Investigation in the Delaware Water Gap National Recreation Area: DEWA 25th Anniversary Symposium: 73- 81.
- Albright, S. S., 1990. Faunal lists of New Jersey's Silurian and Devonian formations within the Delaware Water Gap National Recreation Area: Geological Association of New Jersey Annual Field Conference, 4: 12- 20.
- Anderson, E. J., 1971. Discriminant function analysis of variation among populations of the brachiopod *Gypidula coeymanensis*: Geological Society of America Abstracts with Programs, 3(1): 14- 15.
- Baker, J. E. B., 1971. A study of the fossil dwarfed fauna of the Middle Devonian Marcellus Formation shales outcropped on Old Mine Road in Sussex County, New Jersey: Master's Thesis, Montclair State College, Montclair, New Jersey.
- Baxter, M. E., 1998. A new classification for certain Lower Devonian North American species of the genera *Uncinulus* and *Plethorhyncha*: Geological Society of America Abstracts with Programs, 30(7): 36.
- Beerbower, J. R. and M. H. Hait, Jr., 1959. Silurian fish in northeastern Pennsylvania and northern New Jersey: Proceedings of the Pennsylvania Academy of Science, 33: 198- 203.
- Berdan, J. M., 1971. Some ostracodes from the Schoharie Formation (lower Devonian) of New York: Smithsonian Contributions to Paleobiology, 3: 161- 174.
- Blodgett, R. B., A. J. Boucot, and W. F. Koch II, 1988. New occurrences of color patterns in Devonian articulate brachiopods: Journal of Paleontology, 62(1): 46- 57.
- Boucot, A. J., 1959. Brachiopods of the Lower Devonian rocks at Highland Mills, New York: Journal of Paleontology, 33(5): 727- 769.
- Boucot, A. J. and K. L. Gauri, 1966. *Quadrikentron* (Brachiopods) a new subgenus of *Strophochonetes*: Journal of Paleontology, 40(5): 1023- 1026.
- Boucot, A. J., J. G. Johnson, J. A. Talent, 1969. Early Devonian Brachiopod Zoogeography: Geological Society of America Special Paper, 119: 1- 113.
- Bowen, Z. P., 1966. Intraspecific variation in the brachial cardinalia of *Atrypa reticularis*: Journal of Paleontology, 40(5): 1017- 1022.
- Bretsky, P. W., 1968. Autecology of Late Ordovician Appalachian bivalvia: Geological Society of America Special Paper: 22- 23.
- Brodhead, L. W., 1870. The Delaware Water Gap; its scenery, its legends and early history: Philadelphia, Pennsylvania, 2nd edition: 1- 276.
- Burns, B. P. and M. J. Balogh, 1984. Fossils; the oldest collectibles: Country Magazine, 5(4): 48- 53.
- Caramanica, F. P., 1970. Sedimentary control of middle Devonian corals: Compass of Sigma Gamma Epsilon, 47(3): 174- 182.
- Carter, J. G. and M. J. S. Tevesz, 1978. Shell microstructure of a Middle Devonian (Hamilton Group) bivalve fauna from central New York: Journal of Paleontology, 52(4): 859- 880.

- Chatterton, B. D. E., D. J. Siveter, G. D. Edgecombe, and A. S. Hunt, 1990. Larvae and relationships of the Calymenina (Trilobita): *Journal of Paleontology*, 64(2): 255- 277.
- Chatterton, B. D. E., G. D. Edgecombe, S. E. Speyer, A. S. Hunt, and R. A. Fortey, 1994. Ontogeny and relationships of Trinucleoidea (Trilobita): *Journal of Paleontology*, 68(3): 523- 540.
- Cleaves, A. B., 1939. The Devonian of Pennsylvania: The Oriskany Group; Pennsylvania Topographical and Geological Survey, 4th series, Bulletin 19- G: 92- 130.
- Cooper, B. N., 1971. Roles of Fossils in Appalachian Stratigraphy *in* Dutro, J. T., Jr., (ed.), *Paleozoic Perspectives; A Paleontological Tribute to G. Arthur Cooper*: Smithsonian Contributions to Paleobiology, 3: 3- 22.
- Davis, J. L., 1994. *Eurypterus*; the state fossil of New York: *Rocks and Minerals*, 69(4): 251- 253.
- Denkler, K. E., 1984. Upper Silurian biostratigraphy of the Andrea Quarry, Pennsylvania: Guidebook for the Annual Field Conference of Pennsylvania Geologists, 49: 102- 104.
- Derstler, K., 1975. Carpodid echinoderms from Pennsylvania: *Geological Society of America Abstracts with Programs*, 7(1): 48.
- Derstler, K., 1979. Biogeography of the stylophoran carpodids (Echinodermata): *Proceedings of the Annual Biology Colloquium and Selected Papers*, 37: 91- 104.
- DeWindt, J. T., 1972. Vertebrate fossils as paleocurrent indicators in the upper Silurian of the central Appalachians: *Compass of Sigma Gamma Epsilon*, 49(4): 125- 137.
- Drake, A. A. and J. Epstein, 1967. The Martinsburg Formation (Middle and Upper Ordovician) in the Delaware Valley Pennsylvania- New Jersey: U. S. Geological Survey Bulletin, 1244- H: 1- 16.
- Eaton, H. N., 1920. The Oriskany sandstone faunule at Oriskany Falls, New York: *American Journal of Science*, 5th series: 427- 430.
- Ellison, R. L., 1963. Faunas of the Mahantango Formation in south- central Pennsylvania: *Pennsylvania Geological Survey*, 4th series, Bulletin G- 39: 201- 212.
- Ellison, R. L., 1965. Stratigraphy and paleontology of the Mahantango Formation in south- central Pennsylvania: *Pennsylvania Geological Survey Bulletin*, G- 48: 1- 298.
- Epstein, A. G., 1970. Stratigraphy of Uppermost Silurian and Lowermost Devonian Rocks and the conodonts fauna of the Coeymans Formation and its correlatives in Northeastern Pennsylvania, New Jersey, and southeasternmost New York: PhD Thesis, Ohio State University: 1- 323.
- Fetterhoff, B. V. and R. H. Waines, 1987. Stratigraphic significance of a halysitid tabulate coral in the Whiteport Member of the Rondout Formation (latest Silurian), town of Esopus, Ulster County, southeastern New York: *Geological Society of America Abstracts with Programs*, 19(1): 14.
- Fritz, M. A., 1951. Genus *Trachytoechus* from the Helderberg of Schoharie, New York: *Bulletin of the Wagner Free Institute of Sciences of Philadelphia*, 26(4): 27- 29.
- Fulton, R. D. L., 1982. Exploring the Mahantango: *Jewelry Making Gems and Minerals*, 540: 38- 40.
- Fulton, R. D. L. and J. D. Inners, 1984. Crinoids from the Mahantango Formation (Middle Devonian), Carbon County, Pennsylvania: *Proceedings of the Pennsylvania Academy of Science*, 58(1): 119.
- Gallagher, W. B., 1990. Paleontology and stratigraphy of the lower Paleozoic deposits of the Delaware Water Gap area: *Geological Association of New Jersey Annual Field Conference*, 4: 80.
- Giffin, E. B., 1978. A thelodont agnathid fauna from the Silurian of Pennsylvania: *Geological Society of America Abstracts with Programs*, 10(2): 44.
- Giffin, E. B., 1979. Silurian vertebrates from Pennsylvania: *Journal of Paleontology*, 53(2): 438- 445.
- Goldring, W. and R. H. Flower, 1942. Restudy of the Schoharie and Esopus formations in New York State: *American Journal of Science*, 240(10): 673- 694.
- Grosvenor, F. A., 1965. Brachiopoda and stratigraphy of the Rondout Formation (Silurian) in the Rosendale Quadrangle, southeastern New York: Master s Thesis, University of Rochester, Rochester, New York: 1- 185.
- Hall, J., 1859. Descriptions and figures of the organic remains of the Lower Helderberg group and the Oriskany sandstone: *New York Geological Survey*, Pal 3: 1- 532.
- Hall, J. and J. M. Clarke, 1888. Descriptions of the Trilobites and other Crustacea of the Oriskany, Upper Helderberg, Hamilton, Portage, Chemung, and Catskill groups: *New York Geological Survey*, *Paleontology*, 7: 1- 236.
- Harper, J. A., 1999. Chapter 7; Devonian *in* Schultz, C. H., (ed.), *The Geology of Pennsylvania*: Pennsylvania Geological Survey and Pittsburgh Geological Survey: 109- 127.

- Harper, J. D., 1970. Trends of faunal morphologic variation and their environmental significance; key to paleoecologic analysis: The American Association of Petroleum Geologists Bulletin, 54(5): 1- 850.
- Heiple, P. W., 1971. Lower Barneveld (Shoreham) faunal aspects of the Martinsburg shale, New Paltz-Kingston area, Ulster County, New York: Field Trip Guidebook of the Annual Meeting of the New York State Geological Association, G2.
- Herpers, H. F., Jr., 1950. An Onondagan faunule in New Jersey: Journal of Paleontology, 24(5): 617- 619.
- Herpers, H. F., Jr., 1951b. Marcellus Formation in New Jersey: Geological Society of America Bulletin, 62(12, Part 2): 1553.
- Hicks, J. and C. Wray, 1991. Crinoid paleocurrent orientations; morphologic and depositional controls: Geological Society of America Abstracts with Programs, 23(1): 45.
- Hoar, F. G. and Z. P. Bowen, 1967. Brachiopoda and stratigraphy of the Rondout Formation in the Rosendale Quadrangle, southeastern New York: Journal of Paleontology, 41(1): 1- 36.
- Hoskins, D. M., 1958. Invertebrate fossils from the Bloomsburg Formation of central Pennsylvania: Pennsylvania Academy of Science Proceedings, 32: 156- 161.
- Inners, J. D., 1975a. Middle Devonian fossils at Shadle, Snyder County, Pennsylvania: Pennsylvania Geology, 6(1): 7- 10.
- Inners, J. D., 1975b. The stratigraphy and paleontology of the Onesquethaw Stage in Pennsylvania and adjacent states: PhD Thesis, University of Massachusetts, Amherst, Massachusetts: 1- 737.
- Inners, J. D., 1984. Spiral feeding- organ supports preserved in the brachiopod *Athyris spiriferoides* (Eaton), Rockville, Dauphin County, Pennsylvania: Pennsylvania Geology, 15(2): 9- 12.
- Inners, J. D., 1989. Clams Mahantango and escargots to go, Perry County style: Pennsylvania Geology, 20(3): 9- 12.
- Inners, J. D. and D. M. Nork, 1983. Prolific corals and other fossils of Devonian age at the Lesh Borrow Pit, Perry County, Pennsylvania: Pennsylvania Geology, 14(2): 10- 15.
- Inners, J. D. and E. D. Hess, 1975. Invertebrate fossils in the upper Mahantango Formation, Suedberg, Schuylkill County, Pennsylvania: Pennsylvania Geology, 6(5): 8- 10.
- Key, M. M., Jr., S. M. Lev, and A. Lighthart, 1991. Skeletal growth rates in hemispherical trepostome bryozoans: Geological Society of America Abstracts with Programs, 23(5): 164.
- Kochanov, W. E. and J. D. Inners, 1993. Sea lilies, corals, and lamp shells in a fossilized Devonian garden, Northumberland County, Pennsylvania: Pennsylvania Geology, 24(1): 7- 12.
- Johnson, J. G. and M. A. Murphy, 1969. Age and position of Lower Devonian graptolite zones relative to the Appalachian Standard Succession: Geological Society of America Bulletin, 80(7): 1275- 1282.
- Laporte, L. F., 1969. Recognition of a transgressive carbonate sequence within an epeiric sea: Society of Economic Paleontologists and Mineralogists: 98- 119.
- Lawrence, S. F., D. P. Lawrence, and D. W. Neal, 2001. Teaching the practice of geology and communication using John McPhee's books: Journal of Geoscience Education, 49(1): 36- 43.
- Lytle, P. T., R. Dalton, G. C. Herman, and D. H. Monteverde, 1995. Stratigraphic Distribution of Conodonts in New Jersey in Baker, J., (ed.), Proceedings of the 12th Symposium of the Geological Association of New Jersey: Contributions to the Paleontology of New Jersey: 193- 208.
- Makurath, J. H. and E. J. Anderson, 1972. Gypidulid brachiopods; their life position and paleoenvironment: Geological Society of America Abstracts with Programs, 4(1): 29.
- Makurath, J. H. and E. J. Anderson, 1973. Speciation in gypidulid brachiopods: Geological Society of America Abstracts with Programs, 5(2): 191.
- Marintsch, E. J. and R. M. Finks, 1978. *Zoophycos* size may indicate environment gradients: Lethaia, 11(4): 273- 279.
- Marintsch, E. J. and R. M. Finks, 1982. Lower Devonian ichnofacies at Highland Mills, New York and their gradual replacement across environmental gradients: Journal of Paleontology, 56(5): 1050- 1078.
- Matteson, D. K. and J. R. Ebert, 2001. Cystoids of the Coeymans Formation, Helderberg Group, New York State; a new species of *Lepocrinites* and *Lepocrinites gebhardi* revisited: Geological Society of America Abstracts with Programs, 33(6): 10- 11.
- Metz, R., 1998. Silurian trace fossils from marginal marine deposits, Lizard Creek Member of the Shawangunk Formation, Delaware Water Gap, New Jersey: Northeastern Geology and Environmental Sciences, 20(2): 101- 116.

- Oliver, W. A., Jr., 1976. Noncystimorph colonial rugose corals of the Onesquethaw and lower Cazenovia stages (Lower and Middle Devonian) in New York and adjacent areas: U.S. Geological Survey Professional Paper: 1-156.
- Oliver, W. A., Jr. and W. S. Hecht, 1994. Well-preserved favositid corals in the Oriskany Sandstone (Lower Devonian) of New York: New York State Museum Bulletin, 481: 265-287.
- Palmer, A. C., 1977. Rare fossils in Schuylkill County: Pennsylvania Geology, 8(4): 30-32.
- Parris, D. C. and K. M. Cruikshank, 1993. Graptolite Biostratigraphy of the Ordovician Martinsburg Formation in the Delaware Water Gap Region *in* Santucci, V. L., (ed.), National Park Service Paleontological Research Abstract Volume, Technical Report NPS/NRPEFO/NRTR-93/11: 25.
- Parris, D. C., K. M. Cruikshank, and J. L. Rich, 1990. New biostratigraphic information on the Ordovician Martinsburg Formation of New Jersey and adjacent areas: Geological Association of New Jersey, Annual Field Conference, 4: 21-59.
- Parris, D. C., L. F. Miller, and S. C. Finney, 1993. Graptolite Age Determination of the Martinsburg Formation at the Port Murray Outlier: Bulletin of the New Jersey Academy of Science, 38(1): 1-3.
- Parris, D. C., L. F. Miller, and S. C. Finney, 1998b. Ordovician Graptolite Biostratigraphy in the Vicinity of the Delaware Water Gap National Recreation Area, New Jersey and Pennsylvania *in* Martin, J. E., J. W. Hogenson, and R. C. Benton, (eds.), Proceedings for the Fifth Conference on Fossil Resources: Dakoterra, 5: 7-14.
- Parris, D. C., S. S. Albright, and W. B. Gallagher, 1990. Road log, paleontological sites on the Ordovician, Silurian and Devonian systems of the Delaware Water Gap region: Geological Association of New Jersey, Annual Field Conference, 4: 1-11.
- Ramsdell, R. C., 1982. Invertebrate fossil collecting in Warren and Sussex Counties, New Jersey, Orange County, New York and Pike and Monroe Counties, Pennsylvania: Montclair State College, Division of Geoscience, Guidebook Series: 1-61.
- Scatterday, J. W., 1988. The Middle Devonian brachymetopid trilobite *Australosutura gemmaea* (Hall & Clarke, 1888), close relatives, descendants, and ancestors: New York State Museum Bulletin, 462: 15-16.
- Schuchert, C., 1889. A list of the fossils occurring in the Oriskany sandstone of Maryland, New York, and Ontario: New York State Museum, Annual Report of the Regents: 50-56.
- Schuchert, C., 1900. Lower Devonian aspect of the Lower Helderberg and Oriskany formations: Geological Society of America Bulletin, B-11: 241-332.
- Scott, D. K., H. A. Curran, and B. White, 1984. Ichnofacies of a shallowing-upward sequence, Schoharie Fm. (Early Devonian), New York State: Society of Economic Paleontologists and Mineralogists, SEPM Midyear Meeting Abstracts, 1: 73.
- Secrist, M. H., 1938. New data on upper Martinsburg fauna [Pennsylvania]: Journal of the Washington Academy of Sciences, 28(9): 394-396.
- Seilacher, A., 1968. Origin and diagenesis of the Oriskany Sandstone (Lower Devonian, Appalachians) as reflected in its shell fossils *in* Muller, G. and G. M. Friedman, (eds.), Recent developments in carbonate sedimentology in Central Europe: Springer-Verlag: 175-185.
- Shultz, C., ed., 1999. The Geology of Pennsylvania: Pennsylvania Geological Survey and Pittsburgh Geological Survey: 1-888.
- Smith, D. A. and S. F. Barrett, 1982. A multivariate statistical analysis of Lower Devonian (Deerpark) faunas of eastern North America: Geological Society of America Abstracts with Programs, 14(7): 619.
- Springer, D. A. and R. K. Bambach, 1980. Gradient analysis as a tool for community paleoecology: Geological Society of America Abstracts with Programs, 12(7): 527.
- Stock, C. W., 1977a. Stromatoporoids as indicators of depositional environment in the Rondout Formation (Upper Silurian/Lower Devonian) of New York: Geological Society of America Abstracts with Programs, 9(3): 321-322.
- Stock, C. W., 1977b. Upper Silurian (Pridoli) Stromatoporoidea of New York: PhD Thesis, University of North Carolina, Chapel Hill, North Carolina: 1-154.
- Stock, C. W., 1995. Actinostromatid stromatoporoids in the Upper Silurian (Pridoli) from the Appalachians of Alabama to Quebec: The Journal of Alabama Academy of Science, 66(1-2): 1-45.
- Stock, C. W. and J. A. Burry-Stock, 1998a. Differentiating between two closely related species of stromatoporoids; a canonical discriminant analysis: Geological Society of America Abstracts with Programs, 30(7): 264.

- Stock, C. W. and J. A. Burry-Stock, 1998b. Two new genera of Upper Silurian actinostromatid stromatoporoids: *Journal of Paleontology*, 72(2): 191- 201.
- Strother, P. K., 1988. New species of *Nematothallus* from the Silurian Bloomsburg Formation of Pennsylvania: *Journal of Paleontology*, 62(6): 967- 982.
- Strother, P. K. and J. H. Beck, 1995. Plant Spores from Lateral Equivalents to the Delaware Water Gap Section in Baker, J., (ed.), *Proceedings of the 12th Symposium of the Geological Association of New Jersey: Contributions to the Paleontology of New Jersey*: 209- 221.
- Swartz, F. M. and F. C. Whitmore, Jr., 1956. Ostracoda of the Silurian Decker and Manlius Limestones in New Jersey and eastern New York: *Journal of Paleontology*, 30: 1029- 1091.
- Thompson, G. H., Jr. and J. P. Wilshusen, 1999. The geologic tourist; geological influences on Pennsylvania s history and scenery in Schultz, C. H., (ed.), *The Geology of Pennsylvania: Pennsylvania Geological Survey and Pittsburgh Geological Survey*: 810- 819.
- Van Tuyl, F. M. and F. Berckhemer, 1914. A problematic fossil from the Catskill Formation [Delaware Water Gap, Pennsylvania]: *American Journal of Science*, 38(Series 4): 275- 276.
- Vokes, H. E., 1938. A large *Tentaculites* from the Shriver Formation (Oriskany) of Pennsylvania: *American Museum Novitates*, 984: 1- 4.
- Wagenhoffer, A. J., 1977. The Biostratigraphy of the Lower Helderbergian formations (Lower Devonian) as exposed along Wallpack Ridge, Sussex County, New Jersey: Master s Thesis, Montclair State College, Montclair, New Jersey: 1- 33.
- Waines, R. H., 1997. The mixopteracean eurypterid *Megalograptus*; a first occurrence in New York state and earliest occurrence for the genus (late medial Ordovician): *Geological Society of America Abstracts with Programs*, 29(1): 87.
- Way, J. H., Jr., 1979. On the demise of a *Trimerus* (Dipleura) *dekayi*: *Pennsylvania Geology*, 10(3): 14- 16.
- White, I. C., 1882. The geology of Pike and Monroe Counties: *Pennsylvania Geological Survey*, 2nd Report G- 6: 1- 333.
- Whitfield, R. P., 1885. Notice of a very large species of *Homalonotus* from the Oriskany sandstone formation: *Bulletin of the American Museum of Natural History*: 193- 195.
- Willard, B., 1928. The age and origin of the Shawangunk Formation: *Journal of Paleontology*, 1(4): 225- 258.
- Willard, B., 1941. Martinsburg formation: *Pennsylvania Geological Survey*, 4th series, Bulletin C- 39, Abstracts: 2012.
- Willard, B., 1949. An Eden faunule in New Jersey: *Journal of Paleontology*, 23(2): 218- 220.
- Willard, B. and F. M. Swartz, 1939. The Devonian of Pennsylvania; Middle and Upper Devonian, by Bradford, Willard; Keyser Limestone and Helderberg group, by Frank McKim Swartz; Oriskany group, by Arthur Bailey Cleaves: *Pennsylvania Topographical and Geological Survey*, 4th series, Bulletin 19- G, xii: 1- 481.
- Wolterding, D., 1977. Facies- associated morphologic changes in the brachiopod *Leptaena rhomboidalis* (Wilckens): Master s Thesis, Queens College (CUNY), Flushing, New York: 1- 93.
- Yochelson, E. L. and J. Kriz, 1974. Platyceratid gastropods from the Oriskany Sandstone (Lower Devonian) near Cumberland, Maryland; synonymies, preservation and color markings: *Journal of Paleontology*, 48(3): 474- 484.
- Yolton, J. S., 1968. Geology in our national park: *New Jersey Academy of Science Bulletin*, 13(1): 1- 95.
- Yolton, J. S., 1976. Recent geologic investigations in the Delaware Water Gap National Recreation Area: *New Jersey Academy of Science Bulletin*, 21(1): 1- 26.

DATA SETS:

- | | |
|------------------|---|
| DS- DEWA-
XXX | Delaware Water Gap National Recreation Area Paleontological Archives. 5/1985 present. (hard copy data; reports; electronic data; photographs; maps; publications). Originated by Santucci, Vincent; status: Active. |
| DS- DEWA-
XXX | Delaware Water Gap National Recreation Area Files, Archive, Museum Records. 9/1965 present. (hard copy data; reports; electronic data; photographs; maps; publications). Originated by Delaware Water Gap National Recreation Area; status: Active. |

- DS- DEWA-
XXX New Jersey State Museum Paleontological Records. 1984 present. (hard copy data; field notes; reports; photographs; maps; collections; publications). Originated by New Jersey State Museum (David Parris and Shirley Albright); status: Active.
- DS- DEWA-
XXX Geology of Delaware Water Gap region. 1900s present. (hard copy data; field notes; reports; photographs; maps; collections; publications). Originated by U.S. Geological Survey (Jack Epstein); status: Active.
- DS- DEWA-
XXX Ichnofossil investigations in the Delaware Water Gap region. 1996- present. (hard copy data; field notes; reports; photographs; maps; collections; publications). Originated by Robert Metz; status: Active.
- DS- DEWA-
XXX Geologic Inventory of Delaware Water Gap National Recreation Area. 2001- present. (hard copy data; reports; maps; publications). Originated by the Geologic Resources Division of the National Park Service (Tim Connors); status: Active.

FORT NECESSITY NATIONAL BATTLEFIELD

Fort Necessity National Battlefield (FONE) was established as a national battlefield in March 1931. The opening battle of the French and Indian War was fought at this site where colonial troops, commanded by the 22-year-old Col. George Washington, were defeated on July 3, 1754.

BASELINE PALEONTOLOGICAL RESOURCE INVENTORIES:

Fort Necessity National Battlefield protects three separate units of property: Fort Necessity, Braddock's Grave, and Jumonville Glen. Fort Necessity and Braddock's Grave share similar geology, while Jumonville Glen preserves slightly older deposits. Although the geologic units that occur within the park are known to contain fossils, no fossils have been formally recorded from within the boundaries of FONE.

The oldest geologic unit exposed in the park is the Mississippian Burgoon Sandstone and can be found in Jumonville Glen. The Burgoon Sandstone is primarily a non-marine, fluvial sandstone (T. Kammer, written communication, 2004). This formation also consists of conglomerate, shale, and coal. Trace fossils have been discovered in this formation in central-western Pennsylvania and plant fossils are noted from northern, western, and central Pennsylvania (Berg et al., 1980).

The other unit exposed in FONE is the Pennsylvanian Glenshaw Formation found in the Fort Necessity and Braddock's Grave areas. This formation is composed of shale, sandstone, limestone, and coal. The Glenshaw Formation is known to be very fossiliferous in many areas of Pennsylvania, Ohio, and West Virginia, most notably in the Brush Creek, Pine Creek, and Ames marine zones. In southwestern Pennsylvania, Roen and others (1968) report that the limestone and calcareous shale contain marine fossils. Biogenic mounds containing abundant vertical burrows, presumably from malacostracan crustaceans, are known from southwestern Pennsylvania and eastern Ohio exposures of the Glenshaw Formation (Carothers and Norton, 1975). Crinoid and trilobite fossils from the Glenshaw Formation were used for investigations of mineralogy and fluorescence of skeletal carbonates by Durika and others (1987). Foraminifera have also been studied from the Glenshaw Formation. Palaeotextulariid foraminifera and endothyroid foraminifera were reported on from the Appalachian basin (Moir et al., 1988; Hoare and Sturgeon, 1998). From a quarry in eastern Ohio, Rollins and others (1979) report a variety of fauna from the Glenshaw Formation including, fusulinids, bryozoans, brachiopods, crinoids and fish fragments. Lepold (2003) reports corals, brachiopods, bivalves, and crinoids from the Glenshaw Formation in eastern Ohio. Conodonts were examined at Ebensburg, Pennsylvania to identify the marine unit as part of the Ames (Merrill, 1988). Additional fauna at the site include foraminifera, brachiopods, bivalves, gastropods, cephalopods, echinoderms, and shark's teeth (Brady et al., 1985). An additional locality in Beaver County of the Ames marine zone produced over 30 species of invertebrates, vertebrates, and trace fossils (Harper, 1986). Finally, conodonts from the Ames and Brush Creek marine zones were used for testing the validity of using uranium, thorium, and lead contents for dating (Kovach and Zartman, 1981).

REFERENCES CITED:

- Berg, T. M., A. R. Geyer, W. E. Edmunds, and other compilers, 1980. Geologic map of Pennsylvania: Pennsylvania Geologic Survey, 4th ser., Map 1.
- Brady, K., J. A. Harper, and J. Inners, 1985. Ames or not Ames? an ambiguous Conemaugh marine zone at Ebensburg: Pennsylvania Geology, 16(6): 7-12.
- Carothers, M. C. and C. W. Norton, 1975. Biogenic mounds in the lower Conemaugh (Missourian, Pennsylvanian) of the Appalachian Basin: Geological Society of America Abstracts with Programs, Northeastern Section, 7(1): 37-38.
- Durika, N. J., J. F. Taylor, and K. R. Cercone, 1987. Mineralogy and fluorescence of skeletal carbonates, Brush Creek marine interval, Virgilian Glenshaw Formation, southwestern Pennsylvania: Geological Abstracts with Programs, 19(7): 649.
- Harper, J. A., 1986. Beaver County fossil locality: Pennsylvania Geology, 17(1): 13-16.

- Hoare, R. D. and M. T. Sturgeon, 1998. Pennsylvanian endothyroid Foraminifera from the Appalachian Basin: *Journal of Paleontology*, 72(3): 405- 418.
- Kovach, J. and R. E. Zartman, 1981. U- Th- Pb dating of conodonts: Geological Society of America Abstracts with Programs, North- Central Section, 13(6): 285.
- Lepold, J. G., 2003. Lithologic and faunal patterns related to shoreline position in the Ames Member of the Glenshaw Formation (Virgilian, Upper Pennsylvanian): Geological Society of America Abstracts with Programs.
- Merrill, G. K., 1988. Conodonts confirm that the Conemaugh marine unit at Ebensburg is Ames: *Pennsylvania Geology*, 19(2): 8- 13.
- Moir, M. M., R. D. Hoare, and M. T. Sturgeon, 1988. Pennsylvanian Palaeotextulariid Foraminifera from the Appalachian Basin: *Journal of Paleontology*, 62(5): 724- 730.
- Roen, J. B., B. H. Kent, and S. P. Schweinfurth, 1968. Geologic map of the Monongahela quadrangle, southwestern Pennsylvania: U. S. Geological Survey Geologic Quadrangle Map, GQ- 743, scale 1:24,000.
- Rollins, H. B., M. Carothers, and J. Donahue, 1979. Transgression, regression and fossil community succession: *Lethaia*, 12(2): 89- 104.

ADDITIONAL REFERENCES:

- Al Qayim, B. A., 1983. Facies analysis and depositional environment of the Ames Marine Member (Virgilian) of the Conemaugh Group (Pennsylvanian) in the Appalachian Basin: PhD Thesis, University of Pittsburgh, Pittsburgh, Pennsylvania: 1- 344.
- Berg, T. M., 1979. Upper Devonian- Lower Mississippian stratigraphic relations in North-central Pennsylvania: Geological Society of America Abstracts with Programs, Northeastern Section, 11(1): 3.
- Berg, T. M. and W. E. Edmunds, 1979. The Huntley Mountain Formation; Catskill- to- Burgoon transition in North- central Pennsylvania: Pennsylvania Bureau of Topographic and Geologic Survey, Information Circular, 83: 1- 80.
- Berg, T. M., C. H. Dodge, and L. J. Lentz, 1986. Upper Devonian and Mississippian stratigraphy of the Broad Top region in Sevon, W. D., (ed.), *Selected geology of Bedford and Huntington counties: Guidebook for the Annual Field Conference of Pennsylvania Geologists*, 51: 81- 91.
- Busch, R. M. and H. B. Rollins, 1983. Correlation of Appalachian Upper Pennsylvanian strata using hierarchy of transgressive- regressive cycles: Geological Society of America Abstracts with Programs, 15(6): 537.
- Carpenter, D., 1969. Stratigraphy and sedimentation of the Glenshaw Formation (Conemaugh Group) (Pennsylvanian) in central Preston County, West Virginia: Master's Thesis, West Virginia University, Morgantown, West Virginia.
- Cercone, K. R. and J. F. Taylor, 1989a. Stop GeeBee fossil locality at Geistown; faunal and lithologic characteristics of the Pennsylvanian (Missourian) Brush Creek marine interval, Glenshaw Formation, Conemaugh Group in Harper, J. A., (ed.), *geology in the Laurel Highlands of southwestern Pennsylvania: Guidebook for the Annual Field Conference of Pennsylvania Geologists*, 54: 222- 224.
- Cercone, K. R. and J. F. Taylor, 1989b. Stop Shelocta fossil locality: taphonomy and geochemistry of the Brush Creek marine interval, Glenshaw Formation, Conemaugh Group in Harper, J. A., (ed.), *Geology in the Laurel Highlands of southwestern Pennsylvania: Guidebook for the Annual Field Conference of Pennsylvania Geologists*, 54: 178- 182.
- Easterday, C. R. and L. E. Babcock, 2000. Fauna and taphonomy of a Mason Creek- type deposit (Pennsylvanian) from eastern Ohio: Geological Society of America Abstracts with Programs, North- Central Section, 32(4): 12.
- Edmunds, W. E., 1981. The Mississippian- Pennsylvanian boundary in Pennsylvania: Geological Society of America Abstracts with Programs, 13(7): 445.
- Fedorko, N., S. W. McClelland, C. W. Norton, and T. W. Henry, 1979. Road log; sixth day in England, K. J., H. H. Arndt, and T. W. Henry, (eds.), *Proposed Pennsylvanian system stratotype, Virginia and West Virginia: American Geological Institute Selected Guidebook Series*, 1: 55- 64.
- Fonner, R. F. and G. A. Chappell, 1987. Geology along I- 64, Wayne County, West Virginia: West Virginia Geological and Economic Survey Publication: 1- 31.

- Gallagher, R. A. and J. M. Parks, 1983. Depositional environments of the Loyalhanna member of the Mauch Chunk Formation, north- central Pennsylvania: Geological Society of America Abstracts with Programs, Northeastern Section, 15(3): 127.
- Harper, J. A., 1992. Life in a fossil shellfish community; an excellent outdoor classroom and a collector s paradise: Pennsylvania Geology, 23(2): 9- 14.
- Harper, J. A. and R. W. Morris, 1978. A new encrinasterid ophiuroid from the Conemaugh Group (Pennsylvanian) of western Pennsylvania, and revision of the Encrinasteridae: Journal of Paleontology, 52(1): 155- 163.
- Henry, T. W., W. H. Gillespie, P. C. Lyons, and C. R. Meissner, Jr., 1979. Stop descriptions; fifth day *in* Englund, K. J., H. H. Arndt, and T. W. Henry, (eds.), Proposed Pennsylvanian system stratotype, Virginia and West Virginia: American Geological Institute Selected Guidebook Series, 1: 43- 54.
- Hoare, R. D., 1996. Upper Pennsylvanian *Endothyranella* (Foraminifera) from the Appalachian Basin: The Compass, 73(1): 18- 21.
- Laughrey, C. D., J. A. Harper, U. Kaktins, D. K. Brezinski, and A. Iranpanah, 1989. Stop Conemaugh Gorge through Laurel Hill; Mississippian and Devonian stratigraphy, depositional systems, and structures *in* Harper, J. A., (ed.), Geology in the Laurel Highlands of southwestern Pennsylvania: Guidebook for the Annual Field Conference of Pennsylvania Geologists, 54: 182- 211.
- Maloney, M. M., R. D. Hoare, and M. T. Sturgeon, 1988. Pennsylvanian palaeotexullariid foraminifera from the Appalachian Basin: Journal of Paleontology, 62(5): 724- 730.
- Merrill, G. K., 1981. Lithostratigraphy, paleoecology, and syndepositional tectonics of Conemaugh depositional systems near Huntington, West Virginia: Geological Society of America Abstracts with Programs, 13(7): 509.
- Merrill, G. K., 1982. Quantitative conodont paleoecology; spatial and temporal ecoclines in the *Cavusgnathus*- biofacies, Ames Member, Conemaugh Group (Pennsylvanian, Virgilian), near Huntington, West Virginia: Geological Society of America Abstracts with Programs, North- Central Section, 14(5): 266.
- Miller, D. R., 1964. Stratigraphy of the lower Connemaugh group in part of the North Potomac Basin: Master s Thesis, West Virginia University, Morgantown, West Virginia: 1- 66.
- Morrison, J. O. and U. Brand, 1985. Pyritization; and example of high- Mg calcite alteration: Geological Association of Canada, GAC/MAC Joint Annual Meeting, 10: A40.
- Risek, R. M., 1995. Paleoenvironmental reconstruction of the Harlem and Ames coal beds (Glenshaw Formation- Upper Pennsylvanian); implications for the Missourian- Virgilian stage boundary: PhD Thesis, University of Pittsburgh, Pittsburgh, Pennsylvania: 1- 321.
- Risek, R. M., 1996. Paleoenvironmental reconstruction of the Harlem and Ames coal beds (Glenshaw formation- Upper Pennsylvanian); implications for the Missourian- Virgilian stage boundary: Geological Society of America Abstracts with Programs, Northeastern Section, 28(3): 94.
- Rollins, H. B. and J. Donahue, 1971. Faunal community asymmetry in the Conemaugh (upper Pennsylvanian) of the Appalachian basin; theoretical implication: Geological Society of America Abstracts with Programs, 3(7): 687.
- Shultz, C., ed., 1999. The Geology of Pennsylvania: Pennsylvania Geological Survey and Pittsburgh Geological Survey: 1- 888.
- Wells, K. E., 1983. Detailed correlation of paleogeographic development of the Woods Run, and Carnahan Run marine units (Upper Pennsylvanian) in southwestern Pennsylvania: Geological Society of America Abstracts with Programs, 15(6): 717.
- Yu, J. and H. B. Rollins, 1987. Ostracode distribution within the Brush Creek Member (Glen Shaw Formation, Upper Pennsylvanian) of the North American Appalachian Basin: International Congress on Carboniferous Stratigraphy and Geology Abstracts of Papers, 11: 108.

DATA SETS:

- DS- FONE- Fort Necessity National Battlefield Paleontological Archives. 5/1985 present. (hard copy
XXX data; reports; electronic data; photographs; maps; publications). Originated by Santucci, Vincent; status: Active.

DS- FONE- Fort Necessity National Battlefield Files, Archive, Museum Records. 3/1931 present. (hard
XXX copy data; reports; electronic data; photographs; maps; publications). Originated by Fort
Necessity National Battlefield; status: Active.

FRIENDSHIP HILL NATIONAL HISTORIC SITE

Friendship Hill National Historic Site (FRHI) was established in 1978 to preserve Albert Gallatin's home along the Monongahela River. This Swiss emigrant is best known for serving as Secretary of the Treasury during Jefferson and Madison's administrations. Gallatin's accomplishments and contributions during the turn of the 19th century to the American Republic are interpreted at the restored Friendship Hill house.

BASLINE PALEONTOLOGICAL RESOURCE INVENTORIES:

Two Pennsylvanian-age geologic units are found within FRHI. Although these geologic units are known to contain fossils, no fossils have been formally recorded from within the boundaries of FRHI.

The oldest geologic unit in FRHI is the Upper Pennsylvanian Casselman Formation. This formation is primarily composed of shale, siltstone, sandstone, limestone, and coal. The lowest portion of the formation contains a marine zone, which is composed of a fossiliferous shale (Edmunds et al., 1999). Additionally, nonmarine bivalve fossils have been reported from the Casselman Formation by Eager (1975). Vertebrate fauna discoveries were made by Raymond (1911) and more recently by Lund (1975). One of the more interesting fossil findings in the Casselman Formation is reported on by Marks and others (1998). A pair of problematic tracks were found in Cambria County. Due to comparison with an analogous trackway found in similarly-aged rocks in Scotland, the authors presume that the trackway was caused by a giant myriapod (6-foot long millipede-type invertebrate).

The other geologic unit found within FRHI is the Upper Pennsylvanian Monongahela Group. This group consists of limestone, shale, sandstone, and coal. Eager (1975) comments on the nonmarine bivalves and Lund (1975) provides descriptions of the fossil vertebrates found in the Monongahela Group within the state of Pennsylvania. In southeastern Ohio, Bain (1992) reports on stromatolites from the Monongahela Group that vary in size from masses that are 30 cm in diameter to continuous beds.

REFERENCES CITED:

- Bain, R. J., 1992. Significance of the microstratigraphy of Pennsylvanian stromatolites from southeastern Ohio: Geological Society of America Abstracts with Program, North-Central Section, 24(4): 4.
- Eager, R. M. C., 1975. Some nonmarine bivalve faunas from the Dunkard Group and underlying measures *in* Barlow, J. A. and S. Burkhammer, (eds.), The Age of the Dunkard, Proceedings of the First I. C. White Memorial Symposium: West Virginia Geological and Economic Survey: 23- 67.
- Edmunds, W. E., V. W. Skema, and N. K. Flint, 1999. Chapter 10; Pennsylvanian *in* Schultz, C. H., (ed.), The Geology of Pennsylvania: Pennsylvania Geological Survey and Pittsburgh Geological Survey: 149- 169.
- Lund, R., 1975. Vertebrate-fossil zonation and correlation of the Dunkard Basin *in* Barlow, J. A. and S. Burkhammer, (eds.), The Age of the Dunkard, Proceedings of the First I. C. White Memorial Symposium: West Virginia Geological and Economic Survey: 171- 182.
- Marks, W. J., R. I. Marks, and A. M. Pompa, 1998. Problematic tracks in the Casselman Formation of Cambria County: Pennsylvania Geology, 29(2- 3): 2- 6.
- Raymond, P. E., 1911. A preliminary list of the fauna of the Allegheny and Conemaugh Series in western Pennsylvania: Pennsylvania Geological Survey, 3rd series, Biennial Report 1908- 1910: 81- 98.

ADDITIONAL REFERENCES:

- Arkle, T., Jr., 1974. Stratigraphy of the Pennsylvanian and Permian systems of the central Appalachians: Geological Society of America Special Paper, 148: 5- 29.
- Bassler, H., 1913. Filicales and Pteridospermae of the Monongahela Formation of Maryland: PhD Thesis, The Johns Hopkins University, Baltimore, Maryland.

- Berman, D. S., 1979. *Edaphosaurus* (Reptilia, Pelycosauria) from the Lower Permian of northeastern United States, with description of a new species: *Annals of Carnegie Museum*, 48(Article 11): 185- 202.
- Berryhill, H. L., Jr. and V. E. Swanson, 1962. Revised stratigraphic nomenclature for Upper Pennsylvanian and Lower Permian rocks, Washington County, Pennsylvania: U. S. Geological Survey Professional Paper: C43- C46.
- Bond, W. B., 1993. Pyrite aggregates from Guernsey limestone quarry, Washington County, Ohio: *Rocks and Minerals*, 68(4): 251- 255, 257- 259.
- Brady, K., J. A. Harper, and J. Inners, 1985. Ames or not Ames? an ambiguous Conemaugh marine zone at Ebensburg: *Pennsylvania Geology*, 16(6): 7- 12.
- Branson, C. C., 1962. Pennsylvanian System of central Appalachians: Pennsylvanian System in the United States A symposium, American Association of Petroleum Geologists: 97- 116.
- Cross, A. T., 1988. Upper Pennsylvanian coals and associated rocks; depositional environments, sedimentation, paleontology and paleobotany, upper Ohio River valley: *The Ohio Journal of Science*, 88(1): 65- 66.
- Darrah, W. C., 1969. A critical review of the Upper Pennsylvanian floras of eastern United States with notes on the Mason Creek flora of Illinois: privately printed, Gettysburg, Pennsylvania.
- Defeu, E. L., 1956. Environment of deposition of the Redstone Limestone and a description of the ostracods of the Monongahela Formation, Belmont County, Ohio: Master s Thesis, Ohio State University, Columbus, Ohio.
- Dominic, D. F., 1987. Quantitative interpretation of fluvial sandstones in the Casselman and Pittsburgh formations, Upper Pennsylvanian, West Virginia: *Geological Society of America Abstracts with Programs*, Northeastern Section, 19(1): 11.
- Eager, R. M. C. and H. W. Peirce, 1993. A nonmarine pelecypod assemblage in the Pennsylvanian of Arizona and its correlation with a horizon in Pennsylvania: *Journal of Paleontology*, 67(1): 61- 70.
- Eble, C. F. and W. C. Grady, 1988. Comparative palynologic, petrographic and coal quality characteristics of Middle and Upper Pennsylvanian coal beds: *Geological Society of America Abstracts with Programs*, 1988 centennial celebration, 20(7): 169.
- Fedorko, N., C. C. Blaine, C. F. Eble, and W. C. Grady, 1992a. Stop 4; Upper Conemaugh Group and lower Monongahela Group strata exposed on the north side of the Morgantown Mall complex, near I- 79 Exit 152, Morgantown, WV: U. S. Geological Survey Open- File Report 92- 0546, preliminary version: 22- 33.
- Fedorko, N., C. C. Blaine, C. F. Eble, and W. C. Grady, 1992b. Stop 5; Upper Conemaugh Group and lower Monongahela Group strata exposed behind the Weston Shopping Center, just east of the I- 79 Weston interchange: U. S. Geological Survey Open- File Report 92- 0546, preliminary version: 33- 36.
- Good, C. W. and T. N. Taylor, 1974. Structurally preserved plants from Pennsylvanian (Monongehela Series) of southeastern Ohio: *The Ohio Journal of Science*, 74(5): 287- 290.
- Greenlee, M., 1985. A stratigraphic and sedimentologic study of the upper Monongahela and lower Dunkard groups in southeast Athens County, Ohio: Master s Thesis, Ohio University, Athens, Ohio: 1- 176.
- Hoover, J., 1967. Stratigraphy of the Monongahela Group (Pennsylvanian) in West Virginia, eastern Ohio and southwestern Pennsylvania: Master s Thesis, West Virginia University, Morgantown, West Virginia.
- Jones, M. I. and J. A. Clendening, 1969. Directional orientation of ostracodes; its use as a paleocurrent indicator in the Dunkard Basin *in* Donaldson, A. C., (ed.), *Some Appalachian coals and carbonates; models of ancient shallow- water deposition*: West Virginia Geological and Economic Survey: 235- 238.
- Karytsas, C. S., 1992. Variation in the petrological, mineralogical and palynological characteristics of some Upper Pennsylvanian coals from the northern Appalachian Basin: PhD Thesis, Pennsylvania State University, University Park, Pennsylvania: 1- 372.
- Kosanke, R. M., 1988. Palynological analyses of Upper Pennsylvanian coal beds and adjacent strata from the proposed Pennsylvanian system stratotype in West Virginia: *Geological Society of America Abstracts with Programs*, 1988 centennial celebration, 20(7): 91.
- Lund, R., E. R. Garton, and D. B. Weishampel, 1979. Fossil vertebrates of the Pennsylvanian System of West Virginia: *American Geological Institute Selected Guidebook Series*, 1: 105- 107.
- Lyons, P. C., R. B. Finkelman, and O. G. Oftendahl, 1980. Resin rods and woody rod- like structures in Pennsylvanian coal beds of Appalachian and Illinois basins: *American Association of Petroleum Geologists Bulletin*, 64(5): 1- 743.
- Martino, R. L., 1992. Conemaugh Group strata in the tri- state- area: U. S. Geological Survey Open File Report 92- 0546, preliminary version: 1- 71.

- Merrill, G. K., 1988. Conodonts confirm that the Conemaugh marine unit at Ebensburg is Ames: *Pennsylvania Geology*, 19(2): 8-13.
- Pfefferkorn, H. W., 1999. Paleobiogeography and biostratigraphy of the Pennsylvanian floras from the Narragansett Basin; a review: *Geological Society of America Abstracts with Programs, Northeastern Section*, 31(2): 60.
- Rothwell, G. W. and A. H. Blickle, 1982. *Psaronius magnificus* n. comb., a marattialean fern from the Upper Pennsylvanian of North America: *Journal of Paleontology*, 56(2, Part 1):459-468.
- Shultz, C., ed., 1999. *The Geology of Pennsylvania*: Pennsylvania Geological Survey and Pittsburgh Geological Survey: 1-888.
- Sohn, I. G., 1975. Dunkard Ostracoda; an evaluation *in* Barlow, J. A., (ed.), *The Age of Dunkard*, *Proceedings of the First I. C. White memorial symposium*: West Virginia Geological and Economic Survey: 265-280.
- Stubblefield, S. P., 1984. Taxonomic delimitation among Pennsylvanian marattalian fructifications: *Journal of Paleontology*, 58(3): 793-803.
- Torguson, W. R., Jr., 1977. Morphology and taxonomy of the Ostracoda assemblage from the Benwood and Arnoldsburg members of the Monongahela Group (Pennsylvanian) in Morgan and Noble counties, Ohio: Master's Thesis, University of Akron, Akron, Ohio: 1-65.
- Wagner, R. H. and P. C. Lyons, 1997. A critical analysis of the higher Pennsylvanian megafloras of the Appalachian region: *Review of Palaeobotany and Palynology*, 95(1-4): 255-283.
- Yochelson, E. L., 1975. Monongahela and Dunkard nonmarine gastropods *in* Barlow, J. A., (ed.), *The Age of Dunkard*, *Proceedings of the First I. C. White memorial symposium*: West Virginia Geological and Economic Survey: 249-263.

DATA SETS:

- DS- FRHI- XXX Friendship Hill National Historic Site Paleontological Archives. 5/1985 present. (hard copy data; reports; electronic data; photographs; maps; publications). Originated by Santucci, Vincent; status: Active.
- DS- FRHI- XXX Friendship Hill National Historic Site Files, Archive, Museum Records. 11/1978 present. (hard copy data; reports; electronic data; photographs; maps; publications). Originated by Friendship Hill National Historic Site; status: Active.

GAULEY RIVER NATIONAL RECREATION AREA

Gauley River National Recreation Area (GARI) was established in 1988 and preserves 25 miles of the Gauley River and 6 miles of the Meadow River. Scenic gorges and valleys contain a variety of natural and cultural features. Most noteworthy are the exciting whitewater opportunities provided by the several Class V+ rapids of the Gauley River.

BASLINE PALEONTOLOGICAL RESOURCE INVENTORIES:

The majority of GARI is placed within the Lower Pennsylvanian New River Formation. The perimeter of the park boundary also crosses into smaller sections of the Middle Pennsylvanian Kanawha Formation. Many of the publications do not specify precise locality information nor do they reference GARI boundaries. Although many fossils are known from these formations in the area, it is unclear if paleontological resources have been formally documented within the park's boundary.

The New River Formation is the oldest geologic unit found within GARI. This formation is primarily composed of coal-bearing sandstones, siltstones, and shale. Many fossil plants have been identified from the New River Formation. Gillespie and Pfefferkorn (1978) reported on many species of plant fossils, including 6 lycopods, 8 sphenopsids, 7 pteridosperms, and 1 cordaite. Four species of the genus *Neuralethopteris*, a pteridosperm, were discovered from the New River Formation (Goubet et al., 2000). The New River Formation contains fresh- or brackish-water invertebrates and additional fossil plants, including some that differ across the New River and Kanawha Formation boundary (Englund et al., 1986; Arndt et al., 1979a). Henry and Gordon (1979) list several fossil invertebrates from the New River Formation: rugose coral, brachiopods (*Lingula carbonaria*, *Orbiculoidea* sp., small marginiferid productid?, and *Composita* sp.), pelecypods (*Nuculopsis* cf. *girtyi*, *Phestia* sp., *Paleyoldia*(?) sp., *Schizodus*(?) sp., and *Palaeosolen* sp.), gastropods (bellerophonacean, *Straparollus* (*Euomphalus*?) sp., and pleurotomariacean), and echinoderms (pelmatozoan columnals). Remains of a fossil fish named for its sculptured fins (*Gyracanthus* sp.) were also found from within the Beckley coal zone from the New River Formation (Lund et al., 1979).

The other geologic unit exposed within the park is the Middle Pennsylvanian Kanawha Formation, which consists of shale and siltstone, as well as smaller amounts of sandstone. Martino (1991) identified 10 marine zones within the Kanawha Formation that contain shells, plant impressions (*Calamites*), and trace fossils (*Olivellites* burrows). Previous work by Martino (1989) on trace fossils identified 7 ichnogenera from the Kanawha Formation of West Virginia, and included investigations of arthropod dwellings and other burrows. Within the Kanawha Formation, Gillespie and others (1978) report on fossil plant species; 6 lycopods, 9 sphenopsids, 4 pteridosperms, and 1 cordaite. Englund and others (1986) report that the Kanawha Formation contains root penetrations, abundant plant impressions, marine brachiopods, brackish-water and marine pelecypods, marine gastropods, and burrows. Henry and Gordon (1979) summarize the invertebrate fauna and list over 80 species discovered from 7 localities within the Kanawha Formation. Arndt and others (1979a, 1979b) also report on multiple occurrences of plant, invertebrate, and trace fossil material from field trip logs through Fayette County, West Virginia. Vertebrate material including fish teeth and scales have been discovered from the Kanawha Formation in Fayette County (Arndt et al., 1979a). Lund and others (1979) list the identified fish material: *Sphaerolepis* sp., *Ectosterohachius* sp., *Sagenodus* sp., *Xenacanthus* sp., *X. triodes*, *Orthacanthus* sp., *O. cf. compressus*, *Hybodus* sp., *Helodus simplex*, *Haplolepis* sp.

REFERENCES CITED:

- Arndt, H. H., K. J. Englund, and W. H. Gillespie, 1979a. Stop descriptions; third day: AGI Selected Guidebook Series, 1: 15- 25.
- Arndt, H. H., T. W. Henry, H. W. Pfefferkorn, J. F. Windolph, Jr., 1979b. Stop descriptions; fourth day: AGI Selected Guidebook Series, 1: 29- 39.

- Englund, K. J., H. H. Arndt, S. P. Schweinfurth, and W. H. Gillespie, 1986. Pennsylvanian System stratotype sections, West Virginia: Geological Society of America Centennial Field Guide, Southeastern Section: 59-68.
- Gillespie, W. H., J. A. Clendening, and H. W. Pfefferkorn, 1978. Plant fossils of West Virginia: West Virginia Geological and Economic Survey, Educational Series, 3A: 1-172.
- Goubet, P., H. W. Pfefferkorn, and W. H. Gillespie, 2000. Neuraethopterids (Trigonocarpalean Pteridosperms) from the Early Pennsylvanian of eastern North America: *PaleoBios*, 20(3): 11-37.
- Henry, T. W. and M. Gordon, Jr., 1979. Late Devonian through Early Permian (?) invertebrate faunas in proposed Pennsylvanian System stratotype area: AGI Selected Guidebook Series, 1: 97-103.
- Lund, R., E. R. Garton, and D. B. Weishampel, 1979. Fossil vertebrates of the Pennsylvanian System of West Virginia: AGI Selected Guidebook Series, 1: 105-107.
- Martino, R. L., 1989. Trace fossils from marginal marine facies of the Kanawha Formation (Middle Pennsylvanian), West Virginia: *Journal of Paleontology*, 63(4): 389-403.
- Martino, R. L., 1991. Stratigraphic and Paleoenvironmental Studies in the Kanawha Formation, Southern West Virginia: *Mountain State Geology*: 6-8.

ADDITIONAL REFERENCES:

- Arndt, H. H., 1979. Middle Pennsylvanian series in the proposed Pennsylvanian System stratotype: AGI Selected Guidebook Series, 1: 73-80.
- Blake, B. M., Jr., 1998. Revised megaflora biostratigraphy of the New River and Kanawha formations (Pottsville Group; Lower and Middle Pennsylvanian) in southern West Virginia *in* Martino, R. L., B. M., Jr., Blake, W. C. Grady, and C. F. Eble, (eds.), Coal geology, paleobotany, and regional stratigraphy of the middle part of the Kanawha Formation, southern West Virginia: Geological Society of America, Southeast Section: 41-56.
- Blake, B. M., Jr. and W. H. Gillespie, 1994. Paleobotanical investigations across the Lower-Middle Pennsylvanian series boundary in southern West Virginia: Geological Society of America Abstracts with Programs, Southeastern Section, 26(4): 4.
- Blake, B. M., Jr. and R. L. Martino, 1992. Stop 12; Mahan Exit, lower member, Kanawha Formation: U. S. Geological Survey Open-File Report 92-0546; preliminary version: 48-53.
- Blake, B. M., Jr., A. F. Keiser, and C. L. Rice, 1994. Revised stratigraphy and nomenclature for the Middle Pennsylvanian Kanawha Formation in southwestern West Virginia *in* Rice, C. L., (ed.), Elements of Pennsylvanian stratigraphy, central Appalachian basin: Geological Society of America Special Paper, 294: 41-53.
- Eble, C. F. and W. H. Gillespie, 1984. Characteristic small spores of the Coalburg Coal in West Virginia: *Proceedings of the West Virginia Academy of Science*, 56(1): 1-14.
- Gillespie, W. H. and H. W. Pfefferkorn, 1979. Distribution of commonly occurring plant megafossils in the proposed Pennsylvanian System stratotype: AGI Selected Guidebook Series, 1: 87-96.
- Martino, R. L., 1998. Stratigraphy and depositional environments of the Kanawha Formation (Middle Pennsylvanian), southern West Virginia *in* Martino, R. L., B. M., Jr., Blake, W. C. Grady, and C. F. Eble, (eds.), Coal geology, paleobotany, and regional stratigraphy of the middle part of the Kanawha Formation, southern West Virginia: Geological Society of America, Southeast Section: 15-36.
- Martino, R. L. and G. L. White, 2001. Sedimentology, paleoecology, and sequence stratigraphy of the Winifrede Shale, Kanawha Formation (Middle Pennsylvanian), southern West Virginia: *Southeastern Geology*, 40(2): 117-134.
- Martino, R. L. and M. K. Adkins, 1986. Fauna of the Winifrede Limestone (Middle Pennsylvanian), Upper Kanawha Fm., Boone County, W. Va.: *Proceedings of the West Virginia Academy of Science*, 58(1): 1-26.
- Martino, R. L. and R. B. Bonnett, 1982. Fauna of the Winifrede Limestone, upper Kanawha Formation, Mingo County, W. Va.: *Proceedings of the West Virginia Academy of Science*, 54(1): 1-19.
- Mason, C. and E. L. Yochelson, 1985. Some tubular fossils (*Sphenothallus*: Vermes) from the middle and late Paleozoic of the United States: *Journal of Paleontology*, 59(1): 85-95.
- Read, C. B. and S. H. Mamay, 1960. Upper Paleozoic floral zones of the United States *in* Short papers in the geological sciences; Geological Survey research 1960: U. S. Geological Survey Professional Paper, 400-B: B381-B383.

- Sohn, I. G., 1983. Ostracodes of the Winifrede Limestone (Middle Pennsylvanian) in the region of the proposed Pennsylvanian System stratotype, West Virginia: *Bulletins of American Paleontology*, 84(316): 1- 53.
- Winston, R. B., 1990. Implications of paleobotany of Pennsylvanian- age coal of the central Appalachian basin for climate and coal- bed development: *Geological Society of America Bulletin*, 102: 1720- 1726.
- Winston, R. B. and R. W. Stanton, 1989. Plants, coal and climate in the Pennsylvanian of the Central Appalachians: *International Geological Congress, Field Trips*, 2: 118- 126.

DATA SETS:

- | | |
|------------------|--|
| DS- GARI-
XXX | Gauley River National Recreation Area Paleontological Archives. 5/1985 present. (hard copy data; reports; electronic data; photographs; maps; publications). Originated by Santucci, Vincent; status: Active. |
| DS- GARI-
XXX | Gauley River National Recreation Area Files, Archive, Museum Records. 10/1988 present. (hard copy data; reports; electronic data; photographs; maps; publications). Originated by Gauley River National Recreation Area; status: Active. |

JOHNSTOWN FLOOD NATIONAL MEMORIAL

Johnstown Flood National Memorial (JOFL) was preserved in 1964 to memorialize the devastating flood of 1889 that was caused by a break in the South Fork Dam. The Johnstown Flood resulted in the deaths of 2,209 people, representing the deadliest flood in American history. Additionally, Clara Barton led the first successful Red Cross disaster relief effort.

BASLINE PALEONTOLOGICAL RESOURCE INVENTORIES:

Two Pennsylvanian- age geologic units are found within JOFL. Although these geologic units are known to contain fossils, no fossils have been formally recorded from within the boundaries of JOFL.

The oldest geologic unit exposed in JOFL is the Pennsylvanian Glenshaw Formation. This formation is composed of shale, sandstone, limestone, and coal. The Glenshaw Formation is known to be very fossiliferous in many areas of Pennsylvania, Ohio, and West Virginia, most notably in the Brush Creek, Pine Creek, and Ames marine zones. In southwestern Pennsylvania, Roen and others (1968) report that the limestone and calcareous shale contain marine fossils. Biogenic mounds containing abundant vertical burrows, presumably from malacostracan crustaceans, are known from southwestern Pennsylvania and eastern Ohio exposures of the Glenshaw Formation (Carothers and Norton, 1975). Crinoid and trilobite fossils from the Glenshaw Formation were used for investigations of mineralogy and fluorescence of skeletal carbonates by Durika and others (1987). Palaeotextulariid foraminifera and endothyroid foraminifera were reported from the Appalachian basin (Moir et al., 1988; Hoare and Sturgeon, 1998). From a quarry in eastern Ohio, Rollins and others (1979) report a variety of fauna from the Glenshaw Formation including fusulinids, bryozoans, brachiopods, crinoids, and fish fragments. Also from eastern Ohio, Lepold (2003) reports brachiopods, crinoids, bivalves, and corals from the Glenshaw Formation. Conodonts were examined at Ebensburg, Pennsylvania and were utilized to identify the marine unit as part of the Ames (Merrill, 1988). Additional fauna at the site include foraminifera, brachiopods, bivalves, gastropods, cephalopods, echinoderms, and shark s teeth (Brady et al., 1985). An additional locality within the Ames marine zone in Beaver County produced over 30 species of invertebrates, vertebrates, and trace fossils (Harper, 1986). Lastly, conodonts from the Ames and Brush Creek marine zones were used for testing the validity of using uranium, thorium, and lead contents for dating (Kovach and Zartman, 1981).

The other geologic unit in JOFL is the Casselman Formation. This formation is primarily composed of shale, siltstone, sandstone, limestone, and coal. The lowest portion of the formation contains a marine zone, which is composed of a fossiliferous shale (Edmunds et al., 1999). Additionally, nonmarine bivalve fossils have been reported by Eager (1975). Vertebrate fauna discoveries were made by Raymond (1911) and more recently by Lund (1975). One of the more interesting fossil findings in the Casselman Formation is reported on by Marks and others (1998). A pair of problematic tracks were found in central Cambria County, north of JOFL. Due to comparison with an analogous trackway found in similiary- aged rocks in Scotland, the authors presume that the trackway was caused by a giant myriapod (6- foot long millipede- type invertebrate).

REFERENCES CITED:

- Brady, K., J. A. Harper, and J. Inners, 1985. Ames or not Ames? an ambiguous Conemaugh marine zone at Ebensburg: Pennsylvania Geology, 16(6): 7- 12.
- Carothers, M. C. and C. W. Norton, 1975. Biogenic mounds in the lower Conemaugh (Missourian, Pennsylvanian) of the Appalachian Basin: Geological Society of America, Northeastern Section, 7(1): 37- 38.
- Durika, N. J., J. F. Taylor, and K. R. Cercone, 1987. Mineralogy and fluorescence of skeletal carbonates, Brush Creek marine interval, Virgilian Glenshaw Formation, southwestern Pennsylvania: Geological Society of America Abstracts with programs, 19(7): 649.

- Eager, R. M. C., 1975. Some nonmarine bivalve faunas from the Dunkard Group and underlying measures *in* Barlow, J. A. and S. Burkhammer, (eds.), *The Age of the Dunkard*, Proceedings of the First I. C. White Memorial Symposium: West Virginia Geological and Economic Survey: 23- 67.
- Edmunds, W. E., V. W. Skema, and N. K. Flint, 1999. Chapter 10; Pennsylvanian *in* Schultz, C. H., (ed.), *The Geology of Pennsylvania: Pennsylvania Geological Survey and Pittsburgh Geological Survey*: 149- 169.
- Harper, J. A., 1986. Beaver County fossil locality: *Pennsylvania Geology*, 17(1): 13- 16.
- Hoare, R. D. and M. T. Sturgeon, 1998. Pennsylvanian endothroid Foraminifera from the Appalachian Basin: *Journal of Paleontology*, 72(3): 405- 418.
- Kovach, J. and R. E. Zartman, 1981. U- Th- Pb dating of conodonts: Geological Society of America Abstracts with Programs, North- Central Section, 13(6): 285.
- Lepold, J. G., 2003. Lithologic and faunal patterns related to shoreline position in the Ames Member of the Glenshaw Formation (Virgilian, Upper Pennsylvanian): Geological Society of America Abstracts with Programs.
- Lund, R., 1975. Vertebrate- fossil zonation and correlation of the Dunkard Basin *in* Barlow, J. A. and S. Burkhammer, (eds.), *The Age of the Dunkard*, Proceedings of the First I. C. White Memorial Symposium: West Virginia Geological and Economic Survey: 171- 182.
- Marks, W. J., R. I. Marks, and A. M. Pompa, 1998. Problematic tracks in the Casselman Formation of Cambria County: *Pennsylvania Geology*, 29(2- 3): 2- 6.
- Merrill, G. K., 1988. Conodonts confirm that the Conemaugh marine unit at Ebensburg is Ames: *Pennsylvania Geology*, 19(2): 8- 13.
- Moir, M. M., R. D. Hoare, and M. T. Sturgeon, 1988. Pennsylvanian Palaeotextulariid Foraminifera from the Appalachian Basin: *Journal of Paleontology*, 62(5): 724- 730.
- Raymond, P. E., 1911. A preliminary list of the fauna of the Allegheny and Conemaugh Series in western Pennsylvania: *Pennsylvania Geological Survey*, 3rd series, Biennial Report 1908- 1910: 81- 98.
- Roen, J. B., B. H. Kent, and S. P. Schweinfurth, 1968. Geologic map of the Monongahela quadrangle, southwestern Pennsylvania: U. S. Geological Survey Geologic Quadrangle Map, GQ- 743, scale 1:24,000.
- Rollins, H. B., M. Carothers, J. Donahue, 1979. Transgression, regression and fossil community succession: *Lethaia*, 12(2): 89- 104.

ADDITIONAL REFERENCES:

- Al Qayim, B. A., 1983. Facies analysis and depositional environment of the Ames Marine Member (Virgilian) of the Conemaugh Group (Pennsylvanian) in the Appalachian Basin: PhD Thesis, University of Pittsburgh, Pennsylvania: 1- 344.
- Busch, R. M., 1984. Stratigraphic analysis of Pennsylvanian rocks using a hierarchy of transgressive-regressive units: PhD Thesis, University of Pittsburgh, Pennsylvania: 1- 449.
- Cercone, K. R. and J. F. Taylor, 1989a. Stop Shelocta fossil locality; taphonomy and geochemistry of the Brush Creek marine interval, Glenshaw Formation, Conemaugh Group: *Guidebook for the Annual Field Conference of Pennsylvania Geologists*, 54: 178- 182.
- Cercone, K. R. and J. F. Taylor, 1989b. Stop GeeBee fossil locality at Geistown; faunal and lithologic characteristics of the Pennsylvanian (Missourian) Brush Creek marine interval, Glenshaw Formation, Conemaugh Group: *Guidebook for the Annual Field Conference of Pennsylvania Geologists*, 54: 222- 224.
- Dominic, D. F., 1987. Quantitative interpretation of fluvial sandstones in the Casselman and Pittsburgh formations, Upper Pennsylvanian, West Virginia: Geological Society of America Abstracts with Programs, Northeastern Section, 19(1): 11.
- Easterday, C. R. and L. E. Babcock, 2000. Fauna and taphonomy of a Mazon Creek- type deposit (Pennsylvanian) from eastern Ohio: Geological Society of America Abstracts with Programs, North- Central Section, 32(4): 12.
- Harper, J. A., 1992. Life in a fossil shellfish community; an excellent outdoor classroom and a collector's paradise: *Pennsylvania Geology*, 23(2): 9- 14.
- Harper, J. A. and R. W. Morris, 1978. A new encrinasterid ophiuroid from the Conemaugh Group (Pennsylvanian) of western Pennsylvania, and revision of the Encrinasteridae: *Journal of Paleontology*, 52(1): 155- 163.

- Hoare, R. D., 1996. Upper Pennsylvanian *Endothranella* (Foraminifera) from the Appalachian Basin: The Compass, 73(1): 18- 21.
- Maloney, M. M., R. D. Hoare, and M. T. Sturgeon, 1988. Pennsylvanian palaeotexullariid foraminifera from the Appalachian Basin: Journal of Paleontology, 62(5): 724- 730.
- Morrison, J. O. and U. Brand, 1985. Pyritization; an example of high- Mg calcite alteration: Geological Association of Canada, Mineralogical Association of Canada, and Canadian Geophysical Union Joint Annual Meeting Program with Abstracts, 10: A40.
- Risek, R. M., 1995. Paleoenvironmental reconstruction of the Harlem and Ames coal beds (Glenshaw Formation- Upper Pennsylvanian); implication for the Missourian- Virgilian stage boundary: PhD Thesis, University of Pittsburgh, Pennsylvania: 1- 321.
- Risek, R. M., 1996. Paleoenvironmental reconstruction of the Harlem and Ames coal beds (Glenshaw Formation- Upper Pennsylvanian); implications for the Missourian- Virgilian stage boundary: Geological Society of America Abstracts with Programs, Northeastern Section, 28(3): 94.
- Rollins, H. B. and J. Donahue, 1971. Faunal community asymmetry in the Conemaugh (upper Pennsylvanian) of the Appalachian basin; theoretical implication: Geological Society of America Abstracts with Programs, 3(7): 687.
- Shultz, C., ed., 1999. The Geology of Pennsylvania: Pennsylvania Geological Survey and Pittsburgh Geological Survey: 1- 888.
- Yu, J. and H. B. Rollins, 1987. Ostracode distribution within the Brush Creek member (Glen Shaw Formation, Upper Pennsylvanian) of the North American Appalachian Basin: International Congress on Carboniferous Stratigraphy and Geology Abstracts of Papers, 11: 108.

DATA SETS:

- | | |
|------------------|---|
| DS- JOFL-
XXX | Johnstown Flood National Memorial Paleontological Archives. 5/1985 present. (hard copy data; reports; electronic data; photographs; maps; publications). Originated by Santucci, Vincent; status: Active. |
| DS- JOFL-
XXX | Johnstown Flood National Memorial Files, Archive, Museum Records. 8/1964 present. (hard copy data; reports; electronic data; photographs; maps; publications). Originated by Johnstown Flood National Memorial; status: Active. |

NEW RIVER GORGE NATIONAL RIVER

New River Gorge National River (NERI) was preserved in 1978 to protect a 53-mile section of the New River from Hinton to Fayetteville, West Virginia. Contrary to its name, the New River is among the oldest rivers on the continent and flows northward cutting through the Ridge and Valley province of the Appalachian Mountains and then cutting a deep gorge in the Appalachian Plateau.

BASELINE PALEONTOLOGICAL RESOURCE INVENTORIES:

The Upper Mississippian Bluefield Formation is found in a small exposure in the southern portion of the park. The Bluefield Formation consists mostly of marine calcareous shale with smaller beds of limestone, sandstone, and siltstone. These deposits reflect a shallow-water marine environment (Englund et al., 1979). Henry and Gordon (1979) report 5 marine faunal assemblages within the Bluefield Formation and that the lower section of the formation is particularly fossiliferous. Plant megafossils have been collected from the upper portion of the Bluefield Formation (Gillespie and Pfefferkorn, 1979). *Stigmara ficoides*, *Cyperites bicarinatus*, *Lepidostrobohyllum* spp., *Calamites radiatus*, *Mesocalamites* sp., *Sphenopteris elegans*, and *Cordaites* sp. have been identified from this formation (Gillespie and Pfefferkorn, 1984a). Additionally, Kammer and others (1987) discuss assigning the problematic edrioasteroid (extinct echinoderms) *Hemicystites? carbonarius* specimen from the Bluefield Formation to the new edrioasteroid genus, *Neoisorophusella*.

The Upper Mississippian Hinton Formation is also exposed within the boundaries of NERI. This formation is composed of sandstone, shale, siltstone, limestone, and coal and represents the interrelationship of marine and terrestrial sediments. Englund and others (1979) report that plant fossils are found in the Hinton Formation and the flora correlates with the Namurian A Stage of Europe. *Stigmara stellata* is a characteristic plant fossil found in this formation. Marine fossils are known from the limestone and calcareous shale deposits. These include rugose corals, bryozoans, brachiopods, pelecypods, gastropods, trilobites, crinoids, and a few fish fossils (Englund et al., 1979a; Miller, 1998). Brackish and freshwater assemblages also occur in the Hinton Formation (Henry and Gordon, 1979). Additionally, Hoare (1993) reports bivalve fauna from the Hinton and Bluestone formations of Virginia and West Virginia that include 49 different species from 29 genera. Miller (1998) reports rare occurrences of amphibian teeth up to 2cm in length from a basal conglomerate of the Hinton Formation. Beuthin and Blake (2004) have revised the stratigraphy and nomenclature for the Upper Hinton Formation and used general fossil content, along with other characteristics, to define the members. The fossils that were mentioned in this revision include ostracodes, lycopsid roots and stems, bivalve-dominated bioherms, corals, conularids, myalinid and pectinid bivalves, bryozoans, brachiopods, gastropods, cephalopods, trilobites, peltatazoans (echinoderms), and burrows.

The Upper Mississippian Bluestone Formation is found within NERI and consists of sandstone, shale, and siltstone. The Bluestone Formation contains abundant ostracodes, pelecypods, and the brachiopod *Lingula* (Englund and others, 1979b). Nonmarine ostracodes within the Bluestone Formation from Virginia and West Virginia were researched by Sohn (1985). These ostracodes are of particular importance because they represent the oldest record in North America of particular adductor-muscle-attachment scar patterns. Henry and Gordon (1979) report on 21 different fossil invertebrate species from this formation. Miller (1998) reports plant fragments, thin-valved bivalves, and imprints of shrimp-like arthropods in a Bluestone Formation shale member. Plant fossils are also known from the Bluestone Formation including *Lepidodendron veltheimi*, *Sphenopteris elegans*, *Stigmara stellata*, *Sphenophyllum tenerrimum*, *Stigmara ficoides*, *Cordaites* spp., *Calamites* spp., and *Asterophyllites longifolius* (Gillespie and Pfefferkorn, 1979).

The Lower Pennsylvanian Pocahontas Formation is primarily composed of coal-bearing sandstone with lesser amounts of siltstone and shale. Ostracod molds and sparse *Lingula* have been noted from this geologic unit (Englund et al., 1986). Henry and Gordon (1979) state that the Pocahontas Formation contains freshwater molluscan assemblages and are generally *Naiadites*-dominated. A greater wealth of information has been produced for the fossil plants of the Pocahontas Formation. Goubet and others (2000) focused

their investigations on the biostratigraphy, phylogeny, paleoclimatology, and paleoecology of the plant genus *Neuralethopteris* based on many specimens collected from West Virginia and Virginia. Englund and others (1986) comment on the occurrences of *Neuropteris pocahontas*, *Lepidodendron dichotomum*, *Lyginopteris hoeninghausii*, *Sphenopteris pottsvillea*, *Sphenopteris preslesensis*, *Mesocalamites eremopteroides*, *Alethopteris evansi*, *Alethopteris davreuxi*, and *Aneimites pottsvillensis*. This report also denotes that *Neuropteris pocahontas*, a marker fossil that helps to delineate the bottom of the Pennsylvanian system, is profuse with well-preserved fronds, pinnules, male reproductive bodies (*Aulacotheca campbelli*), and seeds (*Holcospermum maizeretense*). Gillespie and Pfefferkorn (1979, 1984a) also report on additional plant species found within the Pocahontas Formation: *Neuropteris smithsii*, *Palmatopteris furcata*, *Lepidodendron aculeatum*, *Lepidodendron obovatum*, *Stigmara ficoides*, *Cyperites bicarinatus*, *Lepidostrobophyllum* spp., *Calamites radiatus*, *Mesocalamites cistii*, *Mesocalamites suckowii*, *Asterophyllites longifolius*, *Calamostachys* sp., *Mariopteris pottsvillea*, *Trigonocarpus* sp., and *Cordaite* sp.

The New River Formation is a Lower Pennsylvanian unit found within NERI. This formation is primarily composed of coal-bearing sandstones, siltstones, and shale. Many fossil plants have been identified from the New River Formation. Gillespie and others (1978) reported on many species of plant fossils, including 6 lycopods, 8 sphenopsids, 7 pteridosperms, and 1 cordaite. Four species of the genus *Neuralethopteris*, a pteridosperm, were discovered from the New River Formation (Goubet et al., 2000). The New River Formation contains fresh- or brackish-water invertebrates and additional fossil plants, including some that differ across the New River and Kanawha Formation boundary (Englund et al., 1986; Arndt et al., 1979a). Henry and Gordon (1979) list several fossil invertebrates from the New River Formation: rugose coral, pelmatozoan columnals, *Lingula carbonaria*, *Orbiculoidea* sp., small marginiferid productid?, *Composita* sp., *Nuculopsis* cf. *girtyi*, *Phestia* sp., small pelecypods, *Paleyoldia*(?) sp., *Schizodus*(?) sp., bellerophonacean, *Straparollus* (*Euomphalus*?) sp., pleurotomariacean, and *Palaeosolen* sp. Remains of a fossil fish named for its sculptured fins (*Gyracanthus* sp.) were also found from the Beckley coal zone from the New River Formation (Lund et al., 1979).

COOPERATIVE PROJECTS:

- Proposal for Paleontological Survey of the New River Gorge National River Mitchel Blake, West Virginia Geological and Economic Survey (not yet funded).

REFERENCES CITED:

- Arndt, H. H., K. J. Englund, and W. H. Gillespie, 1979a. Stop descriptions; third day: AGI Selected Guidebook Series, 1: 15- 25.
- Beuthin, J. D. and B. M. Blake Jr., 2004. Revised Stratigraphy and Nomenclature for the Upper Hinton Formation (Upper Mississippian) Based on Recognition of Regional Marine Zones, Southern West Virginia: Southeastern Geology, 42(3): 165- 178.
- Engund, K. J., W. H. Gillespie, and T. W. Henry, 1979a. Stop descriptions; first day: AGI Selected Guidebook Series, 1: 3- 5.
- Engund, K. J., H. W. Pfefferkorn, and T. W. Henry, 1979b. Stop descriptions; second day: AGI Selected Guidebook Series, 1: 7- 14.
- Englund, K. J., H. H. Arndt, S. P. Schweinfurth, and W. H. Gillespie, 1986. Pennsylvanian System stratotype sections, West Virginia: Geological Society of America Centennial Field Guide, Southeastern Section: 59- 68.
- Gillespie, W. H. and H. W. Pfefferkorn, 1979. Distribution of commonly occurring plant megafossils in the proposed Pennsylvanian System Stratotype: AGI Selected Guidebook Series, 1: 87- 96.
- Gillespie, W. H. and H. W. Pfefferkorn, 1984a. Plant fossils of the New River Gorge, West Virginia: Proceedings of the West Virginia Academy of Science, 56(2- 4): 124- 135.
- Goubet, P., H. W. Pfefferkorn, and W. H. Gillespie, 2000. *Neuralethopterids* (Trigonocarpalean Pteridosperms) from the Early Pennsylvanian of eastern North America: *PaleoBios*, 20(3): 11- 37.

- Henry, T. W. and M. Gordon, Jr., 1979. Late Devonian through Early Permian (?) invertebrate faunas in proposed Pennsylvanian System stratotype area: AGI Selected Guidebook Series, 1: 97- 103.
- Hoare, R. D., 1993. Mississippian (Chesterian) bivalves from the Pennsylvanian stratotype area in West Virginia and Virginia: *Journal of Paleontology*, 67(3): 374- 396.
- Kammer, T. W., E. C. Tissue, and M. A. Wilson, 1987. *Neoisorophusella*, a new edrioasteroid genus from the Upper Mississippian of the Eastern United States: *Journal of Paleontology*, 61(5): 1033- 1042.
- Lund, R., E. R. Garton, and D. B. Weishampel, 1979. Fossil vertebrates of the Pennsylvanian System of West Virginia: AGI Selected Guidebook Series, 1: 105- 107.
- Miller, D. J., 1998. Depositional Environments and Sequence Stratigraphy of Upper Mississippian Strata in the Central Appalachian Basin: PhD Thesis, Virginia Polytechnic Institute and State University: 1- 87.
- Sohn, I. G., 1985. Latest Mississippian (Namurian A) nonmarine ostracodes from West Virginia and Virginia: *Journal of Paleontology*, 59(2): 446- 460.

ADDITIONAL REFERENCES:

- Arndt, H. H., T. W. Henry, H. W. Pfefferkorn, J. F. Windolph, Jr., 1979b. Stop descriptions; fourth day: AGI Selected Guidebook Series, 1: 29- 39.
- Blake, B. M., Jr., 1998. Revised megaflora biostratigraphy of the New River and Kanawha formations (Pottsville Group; Lower and Middle Pennsylvanian) in southern West Virginia *in* Martino, R. L., B. M., Jr., Blake, W. C. Grady, and C. F. Eble, (eds.), Coal geology, paleobotany, and regional stratigraphy of the middle part of the Kanawha Formation, southern West Virginia: Geological Society of America, Southeast Section: 41- 56.
- Blake, B. M., Jr., A. F. Keiser, and C. L. Rice, 1994. Revised stratigraphy and nomenclature for the Middle Pennsylvanian Kanawha Formation in southwestern West Virginia *in* Rice, C. L., (ed.), Elements of Pennsylvanian stratigraphy, central Appalachian basin: Geological Society of America Special Paper, 294: 41- 53.
- Christopher, C. C., 1990. Late Mississippian girvanella- bryozoan mud mounds in southern West Virginia: *Palaos*, 5(5): 460- 471.
- Christopher, C. C., Jr., 1992. Marine paleocommunities and paleoenvironments of the Upper Mississippian Bluefield Formation in southern West Virginia: PhD Thesis, West Virginia University, Morgantown, West Virginia: 1- 468.
- Gillespie, W. H. and H. W. Pfefferkorn, 1984b. Plant fossils of the New River Gorge (Mississippian and Pennsylvanian) in West Virginia: *Proceedings of the West Virginia Academy of Science*, 56(1): 1- 15.
- Gillespie, W. H., J. A. Clendenning, and H. W. Pfefferkorn, 1978. Plant fossils of West Virginia: West Virginia Geological and Economic Survey, Educational Series, 3A: 1- 172.
- Godfrey, S. J., 1988. Isolated tetrapod remains from the Carboniferous of West Virginia: *Kirtlandia*, 43: 27- 36.
- Godfrey, S. J., 1989. Ontogenetic changes in the skull of the Carboniferous tetrapod *Greererpeton burkemorani* Romer, 1969: *Philosophical Transactions of the Royal Society of London, Series B: Biological Sciences*, 323(1213): 135- 153.
- Gordon, M. Jr. and T. W. Henry, 1981. Paleontologic evidence concerning the Mississippian- Pennsylvanian boundary in the central Appalachian Basin: *Geological Society of America Abstracts with Programs*, 13(7): 462.
- Henry, T. W. and M. Gordon, Jr., 1992. Middle and upper Chesterian brachiopod biostratigraphy, eastern Appalachians, Virginia and West Virginia: *Oklahoma Geological Survey Circular*, 94: 1- 21.
- Henry, T. W. and M. Gordon, Jr., 1990. Upper Mississippian brachiopod biostratigraphy, eastern Appalachians: *Geological Society of America Abstracts with Programs, South- Central Section*, 22(1): 8- 9.
- Holmes, R., 1984. The Carboniferous amphibian *Proterogyrinus scheelei* Romer, and the early evolution of tetrapods: *Philosophical Transactions of the Royal Society of London, Series B: Biological Sciences*, 306(1130): 431- 527.
- Huffman, S. P. and J. D. Beuthin, 2001. Paleoenvironmental and sequence stratigraphic sequence interpretation of a marine shellbed in the Hinton Formation, southern West Virginia: *Geological Society of America Abstracts with Programs, Southeastern Section*, 33(2): 76.
- Lessing, P., 1986. Geology of the New River Gorge: *Mountains State Geology*: 48- 55.

- Martino, R. L., 1989. Trace fossils from marginal marine facies of the Kanawha Formation (Middle Pennsylvanian), West Virginia: *Journal of Paleontology*, 63(4): 389- 403.
- Martino, R. L., 1991. Stratigraphic and Paleoenvironmental Studies in the Kanawha Formation, Southern West Virginia: *Mountain State Geology*: 6- 8.
- Read, C. B. and S. H. Mamay, 1960. Upper Paleozoic floral zones of the United States *in* Short papers in the geological sciences; Geological Survey research 1960: U. S. Geological Survey Professional Paper, 400- B: B381- B383.
- Romer, A. S., 1969. A temnospondylous labyrinthodont from the lower Carboniferous: *Kirtlandia*, 6: 1- 20.
- Smith, C. J., 1976. The Itmann fossil, from the oldest Pennsylvanian rock units in W. Va.: *West Virginia Geological and Economic Survey Newsletter*, 20: 12- 13.
- Smithson, T. R., 1982. The cranial morphology of *Greererpeton burkemorani* Romer (Amphibia, Temnospondyli): *Zoological Journal of the Linnean Society*, 76(1): 29- 90.
- Sobieraj, J. A., Webb, F., Jr., F. K. McKinney, and J. M. Allen, 1991. Analysis of trace fossil assemblages in the mixed carbonate- siliciclastic Bluefield Formation, southern West Virginia: *Geological Society of America Abstracts with Programs, Northeastern Section*, 23(1): 132.
- Sundberg, F. A., J. B. Bennington, M. C. Wizevich, R. K. Bambach, 1990. Upper Carboniferous (Namurian) amphibian trackways from the Bluefield Formation, West Virginia, USA: *Ichnos*, 1(2): 111- 124.
- Weems, R. E. and J. F. Windolph, Jr., 1986. A new actinopterygian fish (Paeonisciformes) from the Upper Mississippian Bluestone Formation of West Virginia: *Proceedings of the Biological Society of Washington*, 99(4): 584- 601.
- Windolph, J. F., Jr. and R. E. Weems, 1987. The significance of a fossil fish (*Tanypterichtys pridensis*) from the Lower Carboniferous (Namurian) Pride Shale Member of the Bluestone Formation of West Virginia, USA: *International Congress on Carboniferous Stratigraphy and Geology*, 11: 102- 103.
- Winston, R. B., 1990. Implications of paleobotany of Pennsylvanian- age coal of the central Appalachian basin for climate and coal- bed development: *Geological Society of America Bulletin*, 102: 1720- 1726.
- Winston, R. B. and R. W. Stanton, 1989. Plants, coal and climate in the Pennsylvanian of the Central Appalachians: *International Geological Congress, Field Trips*, 2: 118- 126.
- Wnuk, C., 1992. The taphonomic history of an in situ *Mesocalamites* stand from the Lower Pennsylvanian Pocahontas Formation, Camp Creek, West Virginia: *International Geological Congress, Abstracts*, 29: 355.

DATA SETS:

- | | |
|------------------|--|
| DS- NERI-
XXX | New River Gorge National River Paleontological Archives. 5/1985 present. (hard copy data; reports; electronic data; photographs; maps; publications). Originated by Santucci, Vincent; status: Active. |
| DS- NERI-
XXX | New River Gorge National River Files, Archive, Museum Records. 11/1978 present. (hard copy data; reports; electronic data; photographs; maps; publications). Originated by New River Gorge National River; status: Active. |

UPPER DELAWARE SCENIC AND RECREATIONAL RIVER

Upper Delaware Scenic and Recreational River (UPDE) was established in 1968 and preserves a 63-mile stretch of the river. Additionally, the park contains the Roebling Bridge, possibly the oldest existing wire-cable suspension bridge, and the Zane Grey home and museum.

BASELINE PALEONTOLOGICAL RESOURCE INVENTORIES:

Although there are 55,575 acres within the Upper Delaware River corridor, only 31 acres are owned by the National Park Service. However, good exposures of sedimentary rock occur in the park-owned land (D. Hamilton, personal communication, 2004). Although no fossils have been formally recorded within the boundaries of UPDE, the geologic unit that occurs within the park is known to contain paleontological resources in other areas of Pennsylvania and New York.

The only geologic unit exposed in UPDE is the Devonian Catskill Formation. The formation primarily consists of sandstone, siltstone, shale, conglomerate, and mudstone. The Catskill Formation contains both marine and nonmarine fossils (Berg et al., 1980; Harper, 1999). The Academy of Natural Sciences in Philadelphia is currently working on what they refer to as the Catskill Project. Through this research, plants, plant spores, invertebrates, and all major classes of vertebrates have been discovered. Additionally, they have discovered and described two new taxa of limbed vertebrates from the Catskill Formation; *Densignathus rowei* and *Hynerpeton bassetti*. These significant tetrapod discoveries from Clinton County, Pennsylvania have extended the temporal range of North American tetrapods and shed light on morphological evolution (Daeschler et al., 1994). Ted Daeschler, Assistant Curator at the Academy of Natural Sciences in Philadelphia (personal communication, 2004), indicates that in the UPDE region, the Catskill Formation is more likely coarser than the areas they have previously investigated, and the depositional environment is less likely to support much life, especially vertebrate preservation. However, there is greater potential to find nearshore marine invertebrate fossils.

Additionally, the State Museum of Pennsylvania houses many fish specimens and the University of California Museum at Berkeley houses 1 plant and 4 vertebrate specimens from the Catskill Formation. Specific paleobotanical research was conducted by Scheckler and Banks (1971) and Brauer (1980a). Scheckler and Banks investigated a new genus of progymnosperms and suggest some evolutionary trends among the Aneurophytales. Brauer discusses interesting features of a *Barinophyton citrulliforme* and suggests various interpretations. Fossil pollen analyses were conducted from Catskill Formation material in order to help date rocks and differentiate sedimentary units (Traverse, 1974; Wilson and Traverse, 1975). Walter (2001) researched evidence for the earliest known wildfire from a charcoal deposit in the Catskill Formation.

REFERENCES CITED:

- Berg, T. M., A. R. Geyer, W. E. Edmunds, and other compilers, 1980. Geologic map of Pennsylvania: Pennsylvania Geologic Survey, 4th ser., Map 1.
- Brauer, D. F., 1980a. *Barinophyton citrulliforme* (Barinophytales incertae sedis, Barinophytaceae) from the Upper Devonian of Pennsylvania: American Journal of Botany, 67(8): 1186-1206.
- Daeschler, E. B., N. H. Shubin, K. S. Thompson, and W. W. Amaral, 1994. A Devonian tetrapod from North America: Science, 265(5172): 639-642.
- Harper, J. A., 1999. Chapter 7; Devonian in Schultz, C. H., (ed.), The Geology of Pennsylvania: Pennsylvania Geological Survey and Pittsburgh Geological Survey: 109-127.
- Scheckler, S. E. and H. P. Banks, 1971. *Proteokalon* a new genus of Progymnosperms from the Devonian of New York State and its bearing of phylogenetic trends in the Group: American Journal of Botany, 58(9): 874-884.
- Traverse, A., 1974. Plant Microfossils Help Date Rocks of Questionable Age: Earth and Mineral Science, 43(4): 28-29.

- Walter, L. C., III, 2001. Evidence of Earliest Known Wildfires: *Palaios*, 16(2): 171- 174.
- Wilson, B. R. and A. Traverse, 1975. Further information on the palynological stratigraphy of Devonian-Carboniferous rocks of central Pennsylvania: *Geoscience and Man*, 11: 160.

ADDITIONAL REFERENCES:

- Ahlberg, P. E., Z. Johanson, and E. B. Daeschler, 2001. The Late Devonian lungfish *Soederberghia* (Sarcopterygii, Dipnoi) from Australia and North America, and its biogeographical implications: *Journal of Vertebrate Paleontology*, 21(1): 1- 12.
- Allen, J. R. L. and P. F. Friend, 1968. Deposition of the Catskill facies, Appalachian region; with some notes on some other Old Red Sandstone basins: *Geological Society of America Special Paper*, 106: 21- 74.
- Baillieul, T. A., G. J. Indelicato, and H. M. Penley, 1980. Scranton Quadrangle; Pennsylvania, New York, and New Jersey: Bendix Field Engineering Corporation, Grand Junction Colorado: 1- 19.
- Banks, H. P., J. D. Grierson, and P. M. Bonamo, 1985. The flora of the Catskill clastic wedge in Woodrow, D. L. and W. D. Secon, (eds.), *The Catskill Delta: Geological Society of America Special Publication*, 201: 125- 141.
- Berg, T. M., 1972. Clam burrows in the upper Devonian or; Quo Vadis *Archanodon*? : *Pennsylvania Geology*, 3(6): 6- 8.
- Berg, T. M., 1973. Pelecypod burrows in the basal sandstone member of the Catskill Formation, northeastern Pennsylvania: *Geological Society of America Abstracts with Programs, Northeastern Section*, 5(2): 137.
- Berg, T. M., 1977. Bivalve burrow structures in the Bellvale Sandstone, New Jersey and New York: *New Jersey Academy of Science Bulletin*, 22(2): 1- 5.
- Berg, T. M., 1999. Devonian- Mississippian transition in Schultz, C. H., (ed.), *The geology of Pennsylvania: Geological Survey of Pennsylvania Special Publication*: 128- 137.
- Berg, T. M. and W. E. Edmunds, 1979. The Huntley Mountain Formation; Catskill- to- Burgoon transition in North- central Pennsylvania: *Pennsylvania Department of Environmental Resources, Bureau of Topographic and Geologic Survey, Information Circular*, 83: 1- 80.
- Birnie, R. W., N. J. Defeo, and C. V. Price, 1986. Lithologic discrimination using geobotanical and Landsat TM spectral data: *Proceedings of the Society of Photo- optical Instrumentation Engineers*, 660: 112- 117.
- Bjerstedt, T. W., 1987. Latest Devonian- Earliest Mississippian nearshore trace- fossil assemblages from West Virginia, Pennsylvania, and Maryland: *Journal of Paleontology*, 61: 865- 889.
- Bowen, Z. P., D. C. Rhoads, and A. L. McAlester, 1974. Marine benthic communities in the Upper Devonian of New York: *Lethaia*, 7: 93- 120.
- Brauer, D. F., 1980b. Barinophytacean plants from the Upper Devonian Catskill Formation of northern Pennsylvania: PhD Thesis, State University New York, Binghamton, New York: 1- 112.
- Brauer, D. F., 1981. Heterosporous, barinophytacean plants from the Upper Devonian of North America and a discussion of the possible affinities of the Barinophytaceae: *Review of Palaeobotany and Palynology*, 33(2- 4): 347- 362.
- Bridge, J. S. and M. L. Droser, 1985. unusual marginal- marine lithofacies from the Upper Devonian Catskill clastic wedge: *Geological Society of America Special Paper*, 201: 143- 161.
- Bridge, J. S., E. A. Gordon, and R. C. Titus, 1986. Non- marine bivalves and associated burrows in the Catskill Magnafacies (Upper Devonian) of New York State (USA): *Palaeogeography, Palaeoclimatology, Palaeoecology*, 55: 65- 77.
- Buhlig, P. and J. R. Honan, 1998. Mississippian age fishes found at Tioga County, Pennsylvania: *Proceedings of the Rochester Academy of Science*, 18(3): 73.
- Chican, M. A., T. N. Taylor, and D. F. Brauer, 1984. Ultrastructural studies of in situ spores; *Protobarinophyton pennsylvanicum* Brauer: *Review of Palaeobotany and Palynology*, 41(3- 4): 167- 175.
- Claypole, E. W., 1883. On *Helicopora*, a new spiral genus (with three species) of North American fenestellids: *Quarterly Journal of the Geological Society of London, Abstract*, QJ39, G Mag (2) 9: 377- 378.
- Corbo, S., 1979. Vertical distribution of trace fossils in a turbidite sequence, Upper Devonian, New York State: *Palaeogeography, Palaeoclimatology, Palaeoecology*, 28: 81- 101.
- Cressler, W. L., III, 2001. Evidence of earliest known wildfires: *Palaios*, 16(2): 171- 174.
- Cuomo, M. C. and D. C. Rhoads, 1987. Biogenic sedimentary fabrics associated with pioneering polychaete assemblages; modern and ancient: *Journal of Sedimentary Petrology*, 57: 537- 543.

- Daeschler, E. B., 2000. An early actinopterygian fish from the Catskill Formation (Late Devonian, Famennian) in Pennsylvania, U. S. A.: Proceedings of the Academy of Natural Sciences of Philadelphia, 150: 181- 192.
- Daeschler, E. B. and N. H. Shubin, 1998. Fish with fingers?: Nature (London), 391(6663): 133.
- Daeschler, T., 1996. Preliminary description of the pectoral girdle and fin from a new cf. *Sauripterus* specimen: Journal of Vertebrate Paleontology, 16(3, Supplemental): 29- 30.
- Daeschler, T. and N. Shubin, 1994. A Late Devonian tetrapod from Pennsylvania: Journal of Vertebrate Paleontology, 14(3, Supplemental): 22.
- Dallmeyer, R. D., P. Geiser, and N. Clauer, 1985. (super 40) Ar / (super 39) Ar incremental release dating of illites from basal Catskill age rocks in the New York Plateau and eastern Pennsylvania Valley and Ridge: Geological Society of America Abstracts with Programs, Southeastern Section, 17(2): 86.
- Davis, M. C., N. H. Shubin, and E. B. Daeschler, 2001. The evolution of the fin endoskeleton and the origin of limbs; insights from the rhizodontid *Sauripterus*: Journal of Vertebrate Paleontology, 21(3 Supplemental): 44.
- Downs, J. P. and E. B. Daeschler, 2001. Variation within a large sample of *Ageleodus pectinatus* teeth (Chondrichthyes) from the Late Devonian of Pennsylvania, U.S.A.: Journal of Vertebrate Paleontology, 21(4): 811- 814.
- Driese, S. G., C. I. Mora, and J. M. Elick, 1997. Morphology and taphonomy of root and stump casts of the earliest trees (Middle to Late Devonian), Pennsylvania and New York, U.S.A.: Palaios, 12(6): 524- 537.
- Droser, M. L., 1984. Characteristics of Paleozoic marginal marine trace fossil assemblages: Geological Society of America Abstracts with Programs, 16(6): 494.
- Dunagan, S. P. and S. G. Driese, 1999. Control of terrestrial stabilization on Late Devonian palustrine carbonate deposition; Catskill Magnafacies, New York, U.S.A.: Journal of Sedimentary Research, 69(3): 772- 783.
- Elliot, D. K., E. B. Daeschler, H. G. Johnson, R. Cloutier, and R. K. Carr, 2000. Middle and Late Devonian vertebrates of the western Old Red Sandstone Continent: CFS Courier Forschungsinstitut Senckenberg, 223: 291- 308.
- Friedman, G. M., R. F. Lundin, and L. W. Knox, 2001. Ostracodes as indicators of brackish water environments in the Catskill Magnafacies (Devonian) of New York State; discussion and reply: Palaeogeography, Palaeoclimatology, Palaeoecology, 171(1- 2): 73- 83.
- Fuller, M. L., 1902. The Catskill rocks in northern Pennsylvania: Science, 15: 664- 665.
- Gale, P. E., 1985. Diagenesis of the Middle to Upper Devonian Catskill facies sandstones in southeastern New York State: Master's Thesis, Harvard University, Cambridge, Massachusetts.
- Gale, P. E. and R. Siever, 1986. Diagenesis of Middle to Upper Devonian Catskill facies sandstone in southeastern New York: American Association of Petroleum Geologists Bulletin, 70(5): 592- 593.
- Glaeser, J. D., 1963. Catskill reference section and its correlation to other measured surface sections in northeast Pennsylvania: Pennsylvania Geological Survey, 4th series (Bulletin G39): 51- 62.
- Glaeser, J. D., 1974. Upper Devonian stratigraphy and sedimentary environments in northeastern Pennsylvania: Pennsylvania Geological Survey General Geology Report, 63: 1- 89.
- Gordon, E. A., 1988. Body and trace fossils from the Middle-Upper Devonian Catskill Magnafacies, southeastern New York, U.S.A.: Devonian of the World, Proceedings of the Second International Symposium on the Devonian System, Canadian Society of Petroleum Geologists, Volume II, Sedimentation: 139- 156.
- Gordon, E. A. and L. W. Knox, 1989. New evidence indicating brackish environments in alluvial to marine margin deposits, Devonian Catskill Magnafacies, New York: Geological Society of America Abstracts with Programs, Northeastern Section, 21(2): 18.
- Grierson, J. D., 1983. The Catskill flora; where we are with the evidences: Geological Society of America Abstracts with Programs, Northeastern Section, 15(3): 133.
- Grierson, J. D. and H. P. Banks, 1983. A new genus of lycopods from the Devonian of New York State: Botanical Journal of the Linnean Society, 86(1- 2): 81- 101.
- Harvey, A. M. and D. E. Grandstaff, 1999. Preserved plant root traces in Devonian fluvial Paleosols; an early example of niche biology?: Geological Society of America Abstracts with Programs, Northeastern Section, 31(2): 21.
- Hasiotis, S. T., W. Cressler, and J. R. Beerbower, 1999. Terrestrial and freshwater ichnofossils as soil biota proxies in Devonian ecosystems; a major transformation in the organization of lower Paleozoic

- continental ecosystems: Geological Society of America Abstracts with Programs, Northeastern Section, 31(2): 22.
- House, M. R. and W. T. Kirchgasser, 1993. Devonian goniatite biostratigraphy and timing of facies movements in the Frasnian of eastern North America: Geological Society of London Special Publication, 70: 267- 292.
- King, D. C., 1998. Interpretation of stable isotope compositions of pedogenic carbonate in Late Silurian to Late Devonian paleosols, Appalachian Basin: Master's Thesis, University of Tennessee, Knoxville, Tennessee: 1- 123.
- Knox, L. W. and E. A. Gordon, 1999. Ostracodes as indicators of brackish water environments in the Catskill magnafacies (Devonian) of New York State: Palaeogeography, Palaeoclimatology, Palaeoecology, 148: 9- 22.
- Kressel, M. D., J. R. Shalis, and A. E. Wegweiser, 1993. Stop 5; Fossil fish, ichnofossils, and sedimentary structures of the Schaffer Run- Wills Creek confluence section, southeastern Somerset County, Pennsylvania: Guidebook for the Annual Field Conference of Pennsylvania Geologists, 58: 102- 116.
- McCauley, J. F., 1961. Uranium in Pennsylvania: Pennsylvania Geological Survey, 4th series (Bulletin M43): 1- 71.
- McGhee, G. R., Jr., 1976. Late Devonian benthic marine communities of the central Appalachian Allegheny Front: Lethaia, 9: 111- 136.
- McGhee, G. R., Jr. and R. G. Sutton, 1981. Late Devonian marine ecology and zoogeography of the central Appalachians and New York: Lethaia, 14: 27- 43.
- McGhee, G. R., Jr. and R. G. Sutton, 1983. Evolution of late Frasnian (Late Devonian) marine environments in New York and the central Appalachians: Alcheringa, 7: 9- 21.
- Mencher, E., 1938. Sedimentary study of the (Devonian) Catskill facies in New York State: PhD Thesis, Massachusetts Institute of Technology, Cambridge, Massachusetts: 1- 164.
- Mora, C. I., S. G. Driese, and L. A. Colarusso, 1996. Middle to late Paleozoic atmospheric CO₂ (sub 2) levels from soil carbonate and organic matter: Science, 271(5252): 1105- 1107.
- Norton, N. J. and D. Allen, 1970. Analyses of palynomorph assemblages from mid- continent and eastern Devonian formations: Geological Society of America Abstracts with Programs, 2(6): 399- 400.
- Randall, K. A., 1995. *Gyracanthus* (Acanthodii: Gyracanthidae) shoulder girdle elements from the Upper Devonian (Famennian) Catskill Formation, Sullivan County, Pennsylvania: Journal of Vertebrate Paleontology, 15(3, Supplemental): 49.
- Robb, A. J. and C. A. Cuffey, 1989. Fossil fish locality in the Catskill Formation (Upper Devonian) near Port Matilda, Centre County, Pennsylvania: Pennsylvania Geology, 20(6): 2- 8.
- Schuyler, A. and A. Traverse, 1990. Sedimentology of miospores in the Middle to Upper Devonian Oneonta Formation, Catskill Magnafacies, New York: Review of Palaeobotany and Palynology, 64(1- 4): 305- 313.
- Sevon, W. D., 1978. Bluestone in Pike County, Pennsylvania: Pennsylvania Geology, 9(3): 2- 7.
- Sevon, W. D., 1984. A sandstone weathering rate from northeastern Pennsylvania: Geological Society of America Abstracts with Programs, Northeastern Section, 16(1): 63.
- Sevon, W. D. and T. M. Berg, 1978. Geology and mineral resources of the Skytop Quadrangle, Monroe and Pike counties, Pennsylvania: Pennsylvania Bureau of Topographic and Geologic Survey, Atlas, 214a: 33.
- Sevon, W. D., D. L. Woodrow, D. E. Costolnick, J. B. Richardson, M. Attrep, Jr., 1997. Convulsive geologic events and the origin of diamictite in the Spechty Kopf Formation in northeastern Pennsylvania: Guidebook for the Annual Field Conference of Pennsylvania Geologists, 62: 34- 60.
- Shultz, C., ed., 1999. The Geology of Pennsylvania: Pennsylvania Geological Survey and Pittsburgh Geological Survey: 1- 888.
- Slingerland, R. and J. P. Loule, 1988. Wind/wave and tidal sedimentation along the Upper Devonian Catskill shoreline in Pennsylvania, USA: West Virginia Geological and Economic Survey Circular: 1- 61.
- Thayer, C. W., 1974. Marine paleoecology in the Upper Devonian of New York: Lethaia, 7: 121- 155.
- Thoms, R. E. and T. M. Berg, 1974. Comparison of the burrowing habits of a Devonian pelecypod with those of a recent analogue: Geological Society of America Abstracts with Programs, Cordilleran Section, 6(3): 267.
- Thoms, R. E. and T. M. Berg, 1980. Interpretation of fossil fluvial bivalve burrows in Catskill Formation, based on analog with *Margaritifera margaritifera* (L.): American Association of Petroleum Geologists Bulletin, 64(5): 1- 792.

- Thoms, R. E. and T. M. Berg, 1985. Interpretation of bivalve trace fossils in fluvial beds of the basal Catskill Formation (Late Devonian), Eastern U.S.A.: Society of Economic Paleontologists and Mineralogists, Special Publication, 35: 13- 20.
- Thomson, K. S., 1972. New evidence on the evolution of the paired fins of *Rhipidistia* and the origin of the tetrapod limb, with description of a new genus of Osteolepidae: *Postilla*, 157: 7.
- Thomson, K. S., 1976. The faunal relationships of rhipidistian fishes (Crossopterygii) from the Catskill (upper Devonian) of Pennsylvania: *Journal of Paleontology*, 50: 1203- 1208.
- Thomson, K. S. and B. Thomas, 2001. On the status of species of *Bothriolepis* (Placodermi, Antiarchi) in North America: *Journal of Vertebrate Paleontology*, 21(4): 679- 686.
- Warg, J. B. and A. Traverse, 1973. A palynological study of shales and coals of a Devonian- Mississippian transition zone, central Pennsylvania: *Geoscience and Man*, 7: 39- 46.
- Williams, H. S., 1900. Catskill formation sedimentation: *Geological Society of America Bulletin*, 11: 594- 595.
- Williams, E. G. and R. L. Slingerland, 1986. Catskill sedimentation in central Pennsylvania: Guidebook for the Annual Conference of Pennsylvania Geologists, 51: 73- 79.
- Wilson, B. R., A. Traverse, and E. G. Williams, 1984. Palynological delineation of the Mississippian-Pennsylvanian unconformity in west- central Pennsylvania: *International Congress on Carboniferous Stratigraphy and Geology*, 9(2): 337- 344.
- Woodrow, D. L., R. A. J. Robinson, A. R. Prave, A. Traverse, E. B. Daeschler, N. D. Rowe, and N. A. DeLaney, 1995. Stratigraphic, sedimentologic, and temporal framework of Red Hill (Upper Devonian Catskill Formation) near Hyner, Clinton County, Pennsylvania; site of the oldest amphibian known from North America: Guidebook for the Annual Field Conference of Pennsylvania Geologists, 60.

DATA SETS:

- | | |
|------------------|--|
| DS- UPDE-
XXX | Upper Delaware Scenic and Recreational River Paleontological Archives. 5/1985 present. (hard copy data; reports; electronic data; photographs; maps; publications). Originated by Santucci, Vincent; status: Active. |
| DS- UPDE-
XXX | Upper Delaware Scenic and Recreational River Files, Archive, Museum Records. 11/1968 present. (hard copy data; reports; electronic data; photographs; maps; publications). Originated by Upper Delaware Scenic and Recreational River; status: Active. |

ACKNOWLEDGMENTS:

The initial contact and network support for this survey was Network Coordinator Matt Marshall. His support was instrumental in the production of this report.

Tim Connors of the Geologic Resources Division is much appreciated for the information and time that was provided for all parks in the Eastern Rivers and Mountains Network.

Staff at all the Eastern Rivers and Mountains Network parks is thanked for their courtesy, cooperation, and assistance with the completion of this report.

In particular, many thanks are offered to the following Delaware Water Gap National Recreation Area employees for providing outstanding support: DeNise Cooke, Natural Resource Specialist; Jeff Shreiner, Biologist; Craig Thompson, Natural Resource Specialist; and John Wright, Supervisory Park Ranger. Additionally, David Parris from the New Jersey State Museum graciously provided copies of reports on Delaware Water Gap fossils.


Milton Gene Clare, Geologist at New River Gorge National River, is thanked for his exceptional support and assistance with providing geologic and paleontologic information for New River Gorge National River, Bluestone National Scenic River, and Gauley River National Recreation Area.

Much appreciation is given to Don Hamilton, Resource Management Specialist at Upper Delaware Scenic and Recreational River for his insights on the paleontology of his park. Additionally, Ted Daeschler of the Academy of Natural Sciences in Philadelphia is also thanked for providing information on fossils in the Upper Delaware Scenic and Recreational River region.

We are grateful to the following people for their insightful review comments on this report: Shirley Albright, Mitch Blake, Gene Clare, Jack Epstein, Matt Marshall, and David Parris.

Lastly, staff at Santa Monica Mountains National Recreation Area are much appreciated for their logistical and moral support for this endeavor: Woody Smeck, Ray Sauvajot, Denise Kamradt, John Tiszler, and Brendan Clarke.

APPENDIX A: GEOLOGIC TIME SCALE



© 1999, The Geological Society of America. Product code CTS004. Compilers: A. R. Palmer, John Geissman

*International ages have not been established. These are regional (Laurentian) only. Boundary Picks were based on dating techniques and fossil records as of 1999. Paleomagnetic attributions have errors. Please ignore the paleomagnetic scale.

Sources for nomenclature and ages: Primarily from Gradstein, F., and Ogg, J., 1996, *Episodes*, v. 19, nos. 1 & 2; Gradstein, F., et al., 1995, *SEPM Special Pub. 54*, p. 95-128; Berggren, W. A., et al., 1995, *SEPM Special Pub. 54*, p. 129-212; Cambrian and basal Ordovician ages adapted from Landing, E., 1998, *Canadian Journal of Earth Sciences*, v. 35, p. 329-338; and Davidek, K., et al., 1998, *Geological Magazine*, v. 135, p. 305-309. Cambrian age names from Palmer, A. R., 1998, *Canadian Journal of Earth Sciences*, v. 35, p. 323-328.

Note: Picks (Ma) = age of the geologic time unit boundary in millions of years (Ma).

This timescale is available online as a PDF:
<http://www.geosociety.org/science/timescale/timescl.pdf>